STEEL
The Metalworking Weekly

NOVEMBER 7, 1955
Vol. 137 No. 19

METALWORKING OUTLOOK, 81

The Editor's Views, 85

Iron Ore Reserves Will Outlast Us, 87
Lake Superior area will continue as prime source

Management at Work, 97
J. A. Ward: Shells are his specialty

Metal Users Outrun Supplies, 99
Steel, copper and aluminum get tighter, STEEL's survey shows

Lake Superior Ore Shipments Rise, 90

Steel Companies Announce Expansions, 91

Drop Forging Association Stages Fall Meet, 92

Standard Steel Looks for New Markets, 93

Compressed Air Tool Sales Push Ahead, 98

Windows of Washington, 94
Mirrors of Motordom, 101
The Business Trend, 105
Men of Industry, 109
New Products, 167
Behind the Scenes, 6
Letters to the Editors, 10
Calendar of Meetings, 27
New Literature, 179

TECHNICAL OUTLOOK, 129

Quality Control: Everybody in the Act, 130
Better product effort sweeps a company

Three Ways To Plate a Bumper, 132
Oldsmobile adds heat treatment as final touch

The New Materials Market, 158
Atoms mean millions to business

Heat Treating Gray Iron, Part III, 134

High-Nitrogen Steels: New Stainless Family, 138

Broaching Helical Gears, 147

Precision Crane Handling Speeds Press Building, 151

MARKET OUTLOOK, 183

Steel Operations, 183
Price Comparisons, 184
Nonferrous Roundup, 186
Nonferrous Prices, 188
Steel Prices, begin 190
Scrap Prices, 208

Editorial & Business Staffs, 16. Advertising Index, 212. Editorial Index available semiannually. STEEL also is indexed by Engineering Index Inc., 29 W. 39th St., New York 18, N.Y.

blished every Monday by The Penton Publishing Co., Penton Bldg., Cleveland 13, O. Subscription the United States and its possessions, Canada, Mexico, Cuba, Central and South America, one ar, $7.50; two years, $15; all other countries, one year, $20. Single copies (current issues), 50 nts. Metalworking Yearbook issue, $2. Accepted as controlled circulation publication at Cleveland.
pyright, 1955, The Penton Publishing Co.

ACME CHAIN



QUICK DELIVERY

The ACME organization was built to give prompt or immediate service. The flexibility of our equipment, the crew of skilled mechanics, our large inventory of standard sizes of ACME Chains, and good shipping facilities, all go to give you ACME Chains when you want them—where you want them.

By 'quick delivery' we mean shipment the same day your order is received. Delivery on 'special orders' is made a week or two sooner than you would normally expect.

Incidentally:

Special assistance from ACME Engineers is ever available to you. At no obligation, our chain experts will gladly cooperate with your designers on your projects.

WRITE OR PHONE JEfferson 2-9458

NEW CATALOG

76 pages of useful chain data. Write Dept. 10W for your free copy.

Acme Chain Corporation
HOLYOKE MASSACHUSETTS

TMI Knows How To BREAK The "NO" BARRIER

We Like to Hear from Men Who Dare to Ask the Impossible Of Small Diameter Stainless Steel and Alloy Tubing... And Expect to Get It!

✓ "No" is as little a part of their vocabulary as it is ours. Breaking the "no" barrier with a confident "yes" is common practice at TMI ... it's the reason our list of customers reads like a Who's Who in American manufacturing.

✓ If you have a challenge for precision, close tolerance Tru-Round tubing ... straightness, finish, resistance, strength or shape ... TMI should prove a dependable source of material, and satisfaction.

✓ We take the time to solve tubing problems—it's good business for us —good news for you.

Specify TMI

For Small Diameter .050 to .625 O.D. Cold Drawn Stainless Steel and Special Alloy Tubing

The Mark of Quality TMI

TUBE METHODS INC.

METALLURGISTS • ENGINEERS • MANUFACTURERS

BRIDGEPORT (Montgomery County), PA.

behind the scenes

Speech Available

On Oct. 11 Assistant Managing Editor Vance Bell addressed the Detroit district section of the Association of Iron & Steel Engineers. His subject: "The Forward Look in the Steel Industry." Interested persons have been quoting from it ever since, including such distinguished spokesmen as Donald C. Potts, president of the Pittsburgh Steamship Division of the U. S. Steel Corp. and John H. Byrne, executive director of the Lake Erie Watershed Conservation Foundation.

Vance assembled his speech from findings he had used for a steel expansion story (STEEL, Sept. 5, p. 41). We happen to know that he is willing to deliver this speech before any qualified and interested group. We suggest that if you wish to book him, send in your request now to Shrdlu, 419 Penton Bldg., Cleveland 13, O.

Editors Hit Platform

Many of STEEL's editors go barging about the country making speeches; this proves they can think as well on their feet as they can—er—well, any other way. Copy Editor Harry Chandler was in Washington last week solemnly instructing business paper editors in the art of preparing stylebooks. Standing lightly on his large, flat feet, he breathed life into hyphens, and made the role of rules so exciting and pulsating his hearers could scarcely refrain from leaping to their feet and cheering.

Market Editor Bill Rooney, too, makes his way to the platform. On Nov. 29 he will address the 1955 Institute for Small Manufacturers at the University of Pittsburgh.

Managing Editor Walt Campbell, of course, is an old hand at spellbinding. One week he was a speaker at an American Iron & Steel Institute meeting at Pittsburgh; six days later he made his seventh annual appearance before the Cleveland Advertising Club.

As in the case of Vance Bell, STEEL's professionals may be scheduled by special arrangement to appear before qualified groups of STEEL readers. Ol' Shrdlu is available, too, but because his only speech is a chalk talk on the crossfertilization of the dandelion and blackeyed peas, the metalworking crowd just can't work up any enthusiasm for him.

Le Chivalry Est Mort

The Farm Quarterly (F. & W. Publishing Co., Cincinnati) carried an article in its spring issue that gave us furiously to think. It was Editor R. J. McGinnis' development of a subject called "The Farmer Takes a Wife." He took the position that a farmer should select a wife with the same care he exercises when buying a cow. "The farmer," wrote Mr. McGinnis, "should appraise his prospective wife with all his wits about him, and leave love to the idle rich and the sentimentalist."

Sitting calmly (possibly in a fortified bunker), he established farm wives in two categories: Type I and Type II. "Type I should be sound of wind and limb; should be farm reared, not overly fastidious, not too educated. Type II is a decoration, and sometimes a luxury. Intelligent, college educated, she wants a dishwater, a garbage disposal and a glass oven."

WOW, Mr. McGinnis!

Boy, Fetch Blackstone

Here's a little law. The U. S. Supreme Court vacated, as improvidently granted, a writ of certiorari which it had previously issued to review an order of the Court of Appeals of the District of Columbia denying a motion to vacate a stay, pending appeal to that court, of an order of the District Court of the District of Columbia enjoining the comptroller general of the U. S. from refusing to audit a claim of the Blitz Tin Corp. against the U. S.

Was the Blitz Corp. pleased? What was the next step in the litigation?

Shrdlu

(Metalworking Outlook—Page 81)



AUTOMATIC HANDLING

Completely automatic operation of this Fay Automatic lathe, including *loading, machining, chip and coolant disposal* and *unloading*, ups production to 180 pcs. per hour at 100% efficiency in the machining of these shells.





NEW METHODS

By grinding this worm (stock removal .1235″ — one pass) on a J&L 6 x 36″ Automatic Thread Grinder, production is increased 160% per machine over previous methods.





VERSATILE TOOLING

High production methods of tooling for automatic lathes were simplified and applied to three 7B J&L Universal Turret Lathes. Inner and outer Ball Bearing Races are produced on the same machines. Set up time from one lot to the next does not exceed fifteen to twenty minutes per machine.



Jones & Lamson's unique Procurement Plan offers you a choice of methods for procuring new, high-efficiency equipment. You may buy outright; pay-from-productivity on a variety of bases, at interest rates of 3¼% and lower (add-on); or you may use any of several variations of a truly flexible lease plan.

MACHINE TOOL DIVISION

Valuable information is yours for the asking. Simply fill in the coupon below, *clip it to your letterhead*, and mail.

Jones & Lamson Machine Company
517 Clinton St., Dept. 710,
Springfield, Vermont, U. S. A.

Please send me the Jones & Lamson *Machine Tool Replacement Information Kit.*

Name.....

Title.....

LACLEDE-CHRISTY does it again!

What more can you ask? Laclede-Christy Silica Brick completed 224 heats in the roof of a 250 ton open hearth furnace at a leading midwest steel mill. Based on a year's average, Laclede-Christy out-lasted other silica brick by 27 to 67 heats—for an average savings of *at least* 30%!

Is this the kind of refractory service you're looking for? Your source of supply—Laclede-Christy—is nearby.

LACLEDE-CHRISTY COMPANY

HKP
H. K. PORTER COMPANY, INC.

DIVISION OF H. K. PORTER COMPANY, INC.
2000 Hampton Avenue • St. Louis 10, Missouri
Mission 7-2400

LACLEDE-CHRISTY COMPANY
FOUNDED 1844
Quality First

LETTERS
TO THE EDITORS

Story Is Required Reading

Your article, "What Cost Price Fighting?" (July 25, page 41), is required reading for everyone connected with our company.

We have been hearing quite a lot about price competition as though it were something brand new. It isn't. It has always been with us; it always will be. It never has made sense; it never will. It makes less sense in this year of the greatest activity in the metal cutting industry.

We are on record as being unalterably opposed to reducing our quality.

C. V. Briner
Manager, Gage Division
Pipe Machinery Co.
Wickliffe, O.

Three Shifts or One Shift?

What are the facts that allow the automobile industry to conclude it is better to buy more high cost equipment to reduce overtime cost rather than to absorb the present overhead by working the equipment more hours? This was stated in the paragraph, "A Spur for Expansion," in the Metalworking Outlook column of June 20 (page 53).

We have thought it more economical to have a small number of machines manned three shifts rather than a lot of machines manned on a single-shift basis. We further have believed that rather than buy more equipment, it is more economical to operate our plant six days, even seven.

This is based on the assumption that we will absorb our fixed cost in the first five days. This materially reduces the cost for Saturday and Sunday work. We pay overtime at the rate of 1½-times on Saturday, double time on Sunday.

Kenneth L. Tingley
Superintendent
Continuous Strip Mill
Scovill Mfg. Co.
Waterbury, Conn.

• *At the risk of oversimplification, here, are some of the tenets:*

1. Because of the auto industry's yearly cycle of model changes, much of its equipment must be written off in a short time. From an internal accounting standpoint, it can't amortize a good portion of its equipment on the basis of output or hours of use as other industries can. There's little incentive for getting in hours just for the sake of hours. As overtime costs mount, the urge to reduce overtime hours grows proportionately stronger.

2. Overtime and multiple shifts are resorted to if demand warrants. Facilities are meant to meet only the minimum demand on a single-shift, no-

(Please turn to page 12)







Conomatics Provide Radial Screw Adjustment of Forming Tool Slides

Models 2⅝" LA, 3½" AD, 5" KL, and 5¼" KR Conomatic Four Spindle Bar Machines are equipped with a number of quick job-change features. One of these is the all-position end attachment drive for the mounting of endworking opposed spindles in all positions, with independent feed to as many as three opposed spindles on a single setup.

Another feature that is of considerable importance in tooling up is the radial screw adjustment of all sideworking slides. Trial cuts may be taken to correct diameters with form tools without changing the clamped positions of the form tool holders.

All Conomatic quick changeover models are equipped with dial adjustment of the working stroke of all tool carrying slides. Besides the Four Spindle machines there are three quick change Six Spindle models in 9/16", 1" and 1⅝" sizes.
Write, wire, or phone for literature.



Conomatic

CONE AUTOMATIC MACHINE COMPANY, INC., WINDSOR, VT., U.S.A.



Model MOD OIL-ACTUATED Multiple Plate Clutch (inset) is one of 6 Twin Disc Machine Tool Clutches incorporated in this power driven 8' Rotary Table with 50-ton capacity—manufactured by one of the world's largest machine tool makers, Giddings & Lewis Machine Tool Co., Fond du Lac, Wis.

Why 6 Twin Disc Clutches are *standard* on new Giddings and Lewis Rotary Table

For *more constant* torque transmittal . . . *longer* wear life . . . *adequate* capacity in a small package . . . *elimination* of adjustment . . . and remote control at *minimum cost*—Giddings & Lewis uses *six* Twin Disc OIL-ACTUATED Multiple Plate Clutches as standard equipment for their new power driven 8' rotary table with 50-ton capacity. Included are: (1) Model MOD-806 and (2) Model MOS-806's on feed drive, with (3) MOS-806's on main transmission.

The Models MOS (single) and MOD (duplex OIL-ACTUATED Multiple Plate Clutches are Twin Disc's answer for a high energy, high inertia, high horsepower clutch especially adaptable to applications creating high temperatures and operating under heavy, abusive loads.

Both models are readily adaptable to remote or push button control without mechanical linkage. Since the floating or pressure plate forms the ram of the cylinder, ram travel increases automatically as plate stack wears. This eliminates adjustments to compensate for plate wear and constant torque transmitting ability is thus provided during entire life of clutch plates.

Find out how these OIL-ACTUATED Multiple Plate Clutches can be applied to your machines—write today to Twin Disc Clutch Company, Racine, Wis.

TWIN DISC
CLUTCHES AND HYDRAULIC DRIVES

TWIN DISC
Clutches

LETTERS

(Concluded from page 10)

overtime basis. By going to overtim and multiple shifts, they can rapid expand output (which they did th year to meet the unexpected needs f an estimated 8 million cars).

3. Round-the-clock operations hav little cost advantage for automaker While it costs money to start and sto a continuous rolling mill, there's litt premium involved in starting and stop ping a stamping press.

STEEL Mails Money Back



We would appreciate your sending u the article, "Business Consultants: Thei Uses and Limitations" (Aug. 15, pag 123). This was listed as No. 95.99 in th *Distribution Data Guide* (September 1955), published by the U. S. Depart ment of Commerce.

Enclosed is a money order for 5 cents—the cost listed in the Guide.

W. H. Gran
Regional Manage
East Central Regional Offic
Air Conditioning Divisio
General Electric Co
Clevelan

• *This is one of many letters requestin this article in which 50 cents was en closed.* Distribution Data Guide *is list ing the charge for a single copy of* STEEL. *This article is available as a reprint. N charge is made for one to three reprints The money is being returned.*

Guides to Purchasers

I wish to request one copy of th Metal Selector (insert) and the Ar Welding Electrode Buyers Guide (pag 142) in the Oct. 10 issue. We will fin these articles of use in our purchasin department.

We enjoy your fine publicatio throughout our offices.

J. Gilbert Blu
Purchasing Dept
Fisher Governor Co
Marshalltown, Iow

Navy Lauds Value Analysis

Your article, "Value Analysis" (Sept 19, page 101), was most enlightenin and timely.

As you state, the U. S. Navy has em barked on such a program within it industrial establishment under the nam of value engineering. The fruits of th effort will be most welcome to all o us who want the greatest possible re turn for our invested dollar—whethe in industry or in national defense an security.

I would appreciate three copies of thi article to stimulate interest in this fiel at this shipyard.

All parts of the 1955 Program fo Management have been excellent i scope and presentation.

Commander James V. Hogg, USN
Production Analysis Superintenden
San Francisco Naval Shipyar
San Francisc

All Along the Line



Operator's station, entry end, 36-inch hot-rolled pickling line. Allis-Chalmers control, initiated from desk, gives positive, precision control of material speed.

Allis-Chalmers dc control board and metering panels, m-g set, on delivery section of the pickling line.





Allis-Chalmers m-g set and dc control board on the annealing line. Allis-Chalmers m-g sets and controls are recognized in the steel industry for dependable, economical service.



Pinch roll drive on delivery end of annealing line. Allis-Chalmers fan-cooled motors drive various parts of the processing line.

CHALMERS

making a
MARKED IMPROVEMENT
in 2-COLOR
PLASTIC LID MARKING

Popular new plastic container lids present unusual marking problems. Markem—source of better marking methods for 44 years—solves them. A new Markem machine prints complete label detail and decorative or trademark designs—in two colors—on polyethylene, styrene and paperboard lids, at production rates. Automatic feed and ejection equipment is available. If your problem is marking container lids—or some other part, product or package—let Markem help you. Write Markem Machine Company, Keene 30, New Hampshire.

MARKEM ...TO MAKE YOUR MARK

STEEL
The Metalworking Weekly

Editor, IRWIN H. SUCH
Managing Editor, WALTER J. CAMPBELL
Assistant Managing Editors, VANCE BELL, JOHN S. MORGAN

WILLIAM M. ROONEY ..... *Market Editor*
J. D. KNOX ..... *Steel Plant Editor*
HARRY CHANDLER .. *Copy Editor*
ALLEN G. GRAY ..... *Technical Editor*
ROBERT F. HUBER ..... *Machine Tool Editor*
FRANK R. BRIGGS ..... *Associate Editor*
ROBERT O. JAYNES ..... *Associate Editor*
MICHAEL A. L. WEBSTER *Associate Editor*
VAN CALDWELL ..... *Associate Editor*
JAMES P. MORRISSEY ..... *Associate Editor*
AUSTIN E. BRANT ..... *Assistant Editor*
BYRON E. KENNEL ..... *Assistant Editor*
A. DONALD POSTMA ..... *Assistant Editor*
ROSS WHITEHEAD ..... *Assistant Editor*
H. H. VON KOSCHEMBAHR .. *Assistant Editor*
MARY T. BORGERHOFF ..... *Assistant Editor*
MARY ALICE LYMAN ..... *Assistant Editor*
EILEEN CORTES ..... *Assistant Editor*
MARY ANN STUVE .... *Editorial Assistant*
BEVERLY CLINE ... *Editorial Service*
JUNE TUTTLE ..... *Editorial Assistant*

Resident Editors

New York 17 ..... 60 E. 42nd St.
B. K. PRICE, L. E. BROWNE
STANLEY B. STEWART
Murray Hill 2-2581

Chicago 11 ..... 520 N. Michigan Ave.
ERLE F. ROSS, WILLIAM E. DEAN
Whitehall 4-1234

Pittsburgh 19 ..... 2837 Koppers Bldg.
ROBERT M. LOVE
Atlantic 1-3211

Detroit 26 ..... 1249 Washington Blvd.
FLOYD G. LAWRENCE
Woodward 3-3488

Washington 4 .... 1123 National Press Bldg.
E. C. KREUTZBERG
Executive 3-6849

London, 2 Caxton St., Westminster S. W. 1
VINCENT DELPORT
European Editor

Editorial Correspondents

Birmingham ..... R. W. KINCEY
Birmingham 3-1121

Buffalo ..... L. G. FELDMANN
Cleveland 5353

St. Louis ..... MAC L. HUTCHENS
Republic 7752

Youngstown ..... GEORGE R. REISS
Riverside 7-1471

Los Angeles ..... NORMAN LYNN
Webster 5-3040

San Francisco ..... EDWIN HAVERTY
Yukon 6-5151

Seattle ..... R. C. HILL
Melrose 1895

Cincinnati ..... JACK DUDLEY
Beechmont 7598

Toronto, Canada ..... F. S. TOBIN
Empire 4-9655

Birmingham, England ..... J. A. HORTON

Paris, France ..... LEON JAUDOIN-PROM

Liege, Belgium ..... JACQUES FOULON

Dusseldorf, Germany .. DR. HERBERT GROSS

BUSINESS STAFF

Advertising Director ..... H. G. ROWLAND
Advertising Service Mgr. ... DORIS MITCHELL
Production Manager ..... A. V. ANDERSON
Circulation & Promotion Dir. .. S. F. MARINO
Circulation Manager ..... G. R. EBERSOLE
Marketing Director ..... D. C. KIEFER
Market Research Dir. ... N. R. LADABOUCHE
Direct Mail Service ..... AMY LOMBARDO
Reprints ..... JUNE SCHILENS
Classified Advertising .. BETTY MARKWORTH

Advertising Representatives

New York 17 ..... 60 E. 42nd St.
K. A. ZOLLNER, GUY LABAW
Murray Hill 2-2581

Philadelphia ..... 200 Wynnewood Ave.
Wynnewood, Pa.
WM. J. VERSCHOOR—Midway 2-6512

Farmington, Conn. .... 12 Farmstead Lane
CALVIN FISHER JR.—Orchard 7-1756

Rochester, N. Y. ..... 217 Ridgeview Dr.
East Rochester, N.Y.
HAROLD A. DENNIS—Browning 2105

Pittsburgh 19 ..... 2837 Koppers Bldg.
J. C. SULLIVAN—Atlantic 1-3211

Cleveland 13 ..... Penton Bldg.
J. K. GILLAM, WM. J. D'ALEXANDER
Main 1-8260

Cincinnati 6 ..... 2215 Victory Pky.
E. L. FRANKE—Parkway 1-3640

Detroit 26 ..... 1249 Washington Blvd.
C. A. TALLINGER JR.—Woodward 3-3488

Chicago 11 ..... 520 N. Michigan Ave.
L. C. PELOTT, W. L. POLAND
JOHN W. VAUGHAN
Whitehall 4-1234

Los Angeles 48 .. 6262 Commodore Sloat Dr.
F. J. FULLER—Webster 1-6865

San Francisco 4 ..... 57 Post St.
F. J. FULLER, Robert W. Walker Co.
Sutter 1-5568

Griffin, Georgia ..... 331 S. 12th St.
FRED J. ALLEN—Griffin 7854

BPA

Published Every Monday by
THE PENTON PUBLISHING CO., Penton Bldg., Cleveland 13, O.
MAin 1-8260

G. O. HAYS ..... *President and Treasurer*
R. C. JAENKE ..... *Executive Vice President*
F. G. STEINEBACH .... *Vice President and Secretary*
F. O. RICE ..... *Vice President*
J. P. LIPKA ..... *Asst. Secy. and Asst. Treas.*

Also Publisher of
FOUNDRY, MACHINE DESIGN, NEW EQUIPMENT DIGEST, AUTOMATION

NBP

Member of Business Publications Audit of Circulation Inc., Society of Business Magazine Editors and National Business Publications Inc.

CALENDAR
OF MEETINGS

. 7-9, American Society for Personnel Administration: Annual meeting and exhibit, nrad Hilton hotel, Chicago. Society's address: P. O. Box 1413, Milwaukee, Wis. ecretary: Russell L. Moberly.

. 9-10, Council of Profit Sharing Industries: nnual conference, Huntington-Sheraton ho-l, Pasadena, Calif. Council's address: 327 . Madison St., Chicago 6, Ill. Executive ecretary: Joseph B. Meier.

. 9-10, Society of Automotive Engineers n.: Fuels and lubricants meeting, Bellevue-tratford hotel, Philadelphia. Society's address: 29 W. 39th St., New York 18, N. Y. ecretary: John A. C. Warner.

. 9-11, Industrial Management Society: nnual time and motion study and management clinic, Sherman hotel, Chicago. ociety's address: 35 E. Wacker Dr., Chiago 1, Ill.

. 9-12, National Association of Aluminum Distributors: Annual meeting, Arizona-Biltmore hotel, Phoenix, Ariz. Association's address: 1900 Arch St., Philadelphia 3, Pa. ecretary: R. Bruce Wall.

. 10-11, American Zinc Institute Inc.: Fall neeting, Galvanizers committee, Drake hotel, hicago. Institute's address: 60 E. 42nd St., lew York 17, N. Y. Secretary-treasurer: . V. Gent.

. 13-18, American Society of Mechanical ngineers: Annual meeting, Congress, Hilton nd Sheraton-Blackstone hotels, Chicago. ociety's address: 29 W. 39th St., New York 8, N. Y. Secretary: C. E. Davies.

. 14-16, National Metal Trades Association: nnual convention, Commodore hotel, New ork. Association's address: 122 S. Michgan Ave., Chicago 3, Ill. Secretary: Charles . Blatchford.

. 14-17, International Automation Exposiion: Navy Pier, Chicago. Information: Richrd Rimbach Associates Inc., 845 Ridge ve., Pittsburgh 12, Pa.

. 14-17, Wire Association: Annual meeting, aSalle hotel, Chicago. Association's address: 453 Main St., Stamford, Conn. Secetary: Richard E. Brown.

. 14-18, Chicago Exposition of Power & echanical Engineering: Chicago Coliseum, hicago. Information: International Exposion Co., 480 Lexington Ave., New York 17, . Y.

. 14-18, National Electrical Manufacturers ssociation: Annual meeting, Traymore ho-l, Atlantic City, N. J. Association's address: 155 E. 44th St., New York 17, N. Y. lanaging director: Joseph F. Miller.

. 16-18, Society for Experimental Stress nalysis: Annual meeting and exhibit, Sherian hotel, Chicago. Society's address: P. O. ox 168, Cambridge 39, Mass. Secretary-reasurer: W. M. Murray.

. 27-30, American Institute of Chemical ngineers: Annual meeting, Hotel Statler, etroit. Institute's address: 25 W. 45th St., ew York 36, N. Y. Secretary: F. J. an Antwerpen.

. 27-Dec. 2, American Institute of Steel onstruction Inc.: Annual meeting, Boca aton hotel and club, Boca Raton, Fla. nstitute's address: 101 Park Ave., New ork 17, N. Y. Secretary: M. Harvey medley.

. 28-Dec. 1, Air Conditioning & Refrigertion Exposition: Atlantic City Auditorium, tlantic City, N. J. Information: Banner & reif, 369 Lexington Ave., New York 17, . Y.

. 5-9, National Exposition of Chemical Inustries: Commercial Museum and Convenon Hall, Philadelphia. Information: Interational Exposition Co., 480 Lexington, Ave., ew York 17, N. Y. Manager: E. K. tevens.

. 7-9, American Institute of Mining & letallurgical Engineers: Electric furnace teel conference, William Penn hotel, Pittsurgh. Institute's address: 29 W. 39th St., ew York, N. Y. Secretary: E. H. Robie.

. 7-9, National Association of Manufacrers: Annual meeting and exhibit, Waldorf storia, New York. Association's address: E. 48th St., New York, N. Y. Secretary: oel Sargent.

Make use of CROWN facilities

If you contract for these



Complete Machines
Assemblies
Sub-Assemblies
Machine Parts

Get this book
describing CROWN'S manufacturing facilities

As one of the leading manufacturers of machinery for the soft drink, brewing and dairy industries, Crown has extensive machine shop facilities and a wealth of experience in producing parts and assemblies of the highest order. Let us show you how our plant and organization can serve you.

CROWN CORK & SEAL COMPANY, INC.
Baltimore 3, Maryland.

CROWN

MAIL THIS COUPON NOW

Crown Cork & Seal Company, Inc.
Advertising Department—Section S
Box 1837 • Baltimore 3, Md.

Please send me a copy of the book describing your facilities for manufacturing General Industrial Equipment.

Name_____

Company_____

Address_____

City_____ Zone_____ State_____

FROM BATHTUBS

TO AIRCRAFT PARTS



Metalworking Outlook

Discouraging Note

Chrysler Corp. and the independent automakers have experienced a moderate slip in sales percentages since last spring. February, March and April saw Chrysler accounting for nearly 20 per cent of industry registrations. The proportion has dropped to about 15 per cent. Studebaker, Packard and Hudson have suffered similar declines. Nash has done a little better, maintaining its proportion at or near 1.5 per cent of industry registrations since April. Record unit sales for most makes this year obscure the percentage situation.

Ford Makes Gains

Estimated Ford Motor Co. earnings before taxes this year will surpass the aggregate earnings of the company for the entire 21 years before World War II. Ford has boosted its employment in the U.S. to 193,000, up 55 per cent since 1946. Its total wage payments, excluding fringe benefits, will peak at more than $1.1 billion this year. Assets at the end of 1954 totaled $2.1 billion. Its latest expansion plan: A 600,000-sq-ft parts manufacturing plant near Ypsilanti, Mich., slated for completion in 1957.

More Steel Imports?

Even with steel as tight as it is in the U.S., don't look for any marked increase in imports. The supply situation is nearly as short in West Europe and Britain. Tubing and wire imports may be increased moderately from such producers as West Germany. From all reports, Communist-dominated countries are having nothing like the steel shortages we are experiencing.

Russian Profile

A typical Russian atom scientist earns the equivalent of $9000 a year, tax free. He employs a couple of maids, has two cars, good housing and an excellent social position. He's in his 30s and directs six men or so. There's no evidence that he's bludgeoned into working on atom research. Quite the contrary: Because of the material benefits of such a job, the competition for the work is keen. That's a profile drawn by Dr. Ralph E. Lapp, director of Nuclear Science Service, Washington. Last summer he was a delegate to the Geneva conference on peacetime uses of atomic energy.

New Price System

Keep your eye on an unusual steel pricing system being tried by Northeastern Steel Co., Bridgeport. It will tie its hot-rolled strip quotation to the cost of steel scrap. With No. 1 heavy melting scrap ($26.50, brokers' buying price, Boston), as a base for an escalator differential, each dollar

increase in scrap cost will add $1 to the selling price of hot strip. A 60-day lead time will be used in establishing the price differential. The Boston heavy melting quotation was $37.50 on Nov. 1, $11 over the scrap base, so the January hot-strip price will be $11 per ton over the base price, plus extras. Sales on Nov. 7, when the system starts, are $9 above the base, because the scrap price 60 days ago was $35.50. The system also applies to narrow light gage plate. It won't be applied on production to come from some new steelmaking facilities being built by Northeastern.

Job for Studebaker-Packard?

Studebaker-Packard Corp. may be the third manufacturer of the Pratt & Whitney J-57 engine. The move reportedly will be forced by the Air Force decision to boost output of the B-52 eight-engine bomber, the F-100, the F-101, the F-102 and the F-104 which all use that power plant. Currently, P&W and Ford produce the unit.

On the Fire: Research Grants

Watch for the Pentagon to review its policy on granting research contracts. In July and August, less than 5 per cent of some $187 million awarded by the military departments went to firms having 500 employees or less. The protests from small business champions in Congress are already starting.

Gains in Farm Equipment

Despite farmers' complaints about income and subsidies, farm equipment makers generally are doing much better financially this year than last. But 1954 was a bad year for the industry. Prospects for 1956: Continuing improvement.

Aluminum for Venezuela

Three American firms and one Canadian aluminum company are considering participation in an aluminum reduction plant proposed for Venezuela. The facility would use electrical energy from a hydroelectric plant planned for the Caroni river. Aluminum Co. of America, Reynolds Metals Co. and Kaiser Aluminum & Chemical Corp. are the U.S. firms interested. Aluminum Co. of Canada is also nibbling.

Straws in the Wind

Form 1120, the new corporate income tax return for 1955, is ready; it's a six-page affair, compared with the old four-page job and is completely revised . . . Look for the Navy two years hence to seek to build nuclear power plants for surface craft . . . Consumer credit hit a record $26.7 billion in September . . . Twenty-three per cent of all installed power generating capacity by 1980 will be atomic, General Electric Co. predicts . . . This week a Senate subcommittee headed by Sen. Joseph C. O'Mahoney (Dem., Wyo.) will "study" whether General Motors Corp. is too big.

You and the ILO

Even while the teams of smiling Russians absorb American know-how and Big Four ministers pay homage to the Geneva spirit in the Swiss capital, communism continues to pursue its campaign of subtle infiltration.

Its latest approach is through the International Labor Organization created by the Treaty of Versailles in 1919. After the demise of the League of Nations, the ILO continued to function. In 1945, it became an independent affiliate of the United Nations.

As constituted, the ILO is an association of 69 countries. The United States joined in 1934. The U.S.S.R. and seven satellites waited until 1954.

The ILO has a permanent staff of 800, with headquarters in Geneva. Each nation sends four delegates to an annual international conference. Two represent government. Employers and workers have one delegate each.

While the international conference is the supreme authority, work is controlled principally by a governing body of 40—government has 20 representatives, employers, 10, workers, 10. It meets three times a year. To carry on its work, ILO has a 1955 budget of $6.7 million, of which the U. S. pays 25 per cent and the Iron Curtain countries 14.5 per cent. Next year, ILO is getting $12 million.

The purpose of the ILO is to draft international labor standards in the form of conventions or recommendations. Conventions, when ratified, are binding like treaties. The U. S. has ratified seven which deal mostly with maritime employment. Others are pending.

In practice, the ILO has strayed from its original purpose. Under the pretext of helping the workingman, it makes proposals that would force socialism on individual nations. Thirty-two communist representatives in ILO are precipitating a further swing to the left by using the organization as a new medium for the Red propaganda machine.

When the governing body meets this month, there'll be a showdown on whether employer and employee delegates from communist countries really represent free employers and free workers.

If members from those countries are not disqualified, the ILO is likely to become another communist-dominated organization that can have profound effects on world politics in general and on your employee relations in particular.

Place your protest to this threat to U. S. free enterprise with your Senator or Congressman.

Irwin H. Such

EDITOR

But can you be sure it will work as well next month?

When your steel starts with ore from the same mines, reduced to iron in the same blast furnaces, refined to steel in the same open hearth furnaces, rolled on the same mills, by the same men, time after time, order after order . . . you can be certain that your steel is as uniform in quality as the best raw material sources, the finest steelmaking facilities and the most experienced steelworkers can make it.

INLAND STEEL COMPANY
38 South Dearborn Street • Chicago 3, Illinois

Sales Offices: Chicago • Milwaukee • St. Paul
Davenport • St. Louis • Kansas City • Indianapolis
Detroit • New York

Principal Products: Sheets • Strip • Structural Shapes • Plates • Bars • Tin Mill Products • Rails and Track Accessories • Coal Chemicals

IRON ORE SUPPLIES for 1970

All Figures in Millions of Gross Tons



POTENTIAL DOMESTIC SUPPLY

	1955	1960	1965	1970
Lake Superior direct ores				
Open-pit	50	30	10	5
Underground	20	20	20	20
Lake Superior concentrates				
Taconite	2	15	20	25
Other	30	35	35	30
Southeastern states				
Direct ore	7	7	7	7
Concentrates	3	3	3	3
Northeastern states	6	6	6	6
Western states				
Direct ore	9	10	13	15
Concentrates	1	2	2	2
By-product ore	1	1	2	2
Total Domestic	129	129	118	115

POTENTIAL FOREIGN SUPPLY

	1955	1960	1965	1970
Canada				
Quebec-Labrador	5	15	20	30
Steep Rock	3	5	5	5
Michipicoten	1	2	2	2
Other	1	1	1	1
Latin America				
Brazil	1	2	2	2
Venezuela	6	13	15	20
Other	1	1	1	1
Africa				
Algeria, Tunisia	1	1	1	1
Liberia, Br. West Africa	2	3	4	4
Europe				
Sweden, Norway	2	2	2	2
Total Foreign	23	45	53	68
Total Ore Supply	152	174	171	183

Source: R. W. Holliday, U. S. Bureau of Mines

ron Ore Supplies Will Outlast Us

NLY a Methuselah could expect o see our iron ore supply run out. Ie lived 969 years.

The iron ore resources in the . S. alone could supply a steel ndustry 50 per cent bigger than nat of today for 150 years of ca- acity operations. Foreign coun- ries (including Canada) could add nother 80 years of supply at this ace.

A 50 per cent expansion in the teel industry of the U. S. in the ext 15 years (see STEEL, Sept. 5, . 41) will not run aground for ant of ore.

Job Ahead—All those reserves are not direct-shipping ores: 65 per cent must come from beneficiation (treatment to make the iron available or concentrated). Beneficiation varies from screening and washing to complex operations such as fine grinding, roasting, magnetic separation and flotation.

Beneficiated materials will be more costly than direct-shipping ores, but that's no stopper. When a material is needed, the consumer will pay the price to get it. This brings out the material.

Higher prices are already bringing out iron-bearing materials (taconite, for instance) that couldn't have been touched a few years ago. Reflecting this incentive, the price of iron ore in the last 15 years has risen 119 per cent—greater than the rate of inflation in our economy. The cost of living, for example, rose 92 per cent in that period.

In the Wind—The price of domestic iron ore will go up on shipments beginning with the 1956 Great Lakes shipping season. Don't be surprised if it's $1 a gross ton. Iron ore producers have to

cover themselves on three wage increases—those of 1954 and 1955, and the one coming in 1956. Because the steel business was slow when the ore producers set prices for 1955, they added only 10 cents a ton—the smallest increase in the last 25 years, and not enough to cover the 1954 wage increase. Since they set the 1955 price, wages have gone up again—in mid-1955. In mid-1956, wages will climb some more.

A $1-a-ton increase is not without precedent. Ore went up that much in the 1949 shipping season. A 50-to-65-cent increase has not been uncommon.

The Make-Up—The sources of iron ore in the U. S., according to R. W. Holliday, commodity-industry analyst for the U. S. Bureau of Mines, are made up like this: 4170 million gross tons of ore over 50 per cent in iron content, 2215 million gross tons with an iron content of 35 to 50 per cent and 61,033 million gross tons with an iron content of 25 to 35 per cent.

The Lake Superior region still bulks large as a supplier. It has 3605 million tons of the ore over 50 per cent in iron and 60,000 million tons of the ore (taconite) containing 25 to 35 per cent iron.

The next most important U. S. region is the Southeast. Its resources are 105 million tons of ore over 50 per cent in iron content, 1127 million tons in the 35 to 50 per cent group and 1033 million tons in the 25 to 35 per cent bracket.

High Quality—The supply of foreign ores is heavy in the high grades—9595 million tons having more than 50 per cent iron. Others: 7750 million tons of 35 to 50 per cent; 100 million tons of 25 to 35 per cent. Canada is the largest single foreign source. It has 4570 million tons of ore containing more than 50 per cent iron.

As the easily mined iron ores become less plentiful in the U. S., we'll rely more heavily on foreign supplies. Today, 15 per cent of our ore is coming from foreign sources. Mr. Holliday says that figure will jump to 26 per cent in 1960, 31 per cent in 1965 and 37 per cent in 1970. Almost one-half of our imports consistently will be from Canada.

Rivals—The Quebec - Labrador area will be the biggest single Canadian factor. One other foreign area (Venezuela) will rival it. Security considerations favor Canadian ore, but year-round operation and premium grade favor Venezuela. Other foreign sources will include Brazil, Liberia and British West Africa, Algeria and Tunisia, Sweden and Norway.



Sources: Supplies, by R. W. Holliday, U S. Bureau of Mines
Needs, by STEEL

The Lake Superior region of the U. S. will continue to be the single biggest source of iron-bearing minerals, even though the easily obtained open-pit ores are diminishing.

Changing Patterns—Direct-shipping ores—now accounting for 70 per cent of the domestic Lake Superior supply—will decline to 30 per cent by 1970. Seventy per cent of the direct-shipping ores are now in open pits. The remainder is underground. By 1970, only 20 per cent will be in open pits, 80 per cent underground.

The rest of the domestic supplies in the Lake Superior region are concentrates. Now 30 per cent of shipments, they will account for 70 per cent by 1970. With taconites just getting a foothold, almost all the concentrates now are from lean ores. While they will hold their own tonnage wise, they will decrease percentagewise as taconites develop. By 1970, taconites will account for 5[illegible] per cent of the dometsic Lake Superior concentrates.

Another Incentive—As supplies of direct-shipping ores run lower beneficiated material comes more and more into the picture. But that isn't the sole stimulus to beneficiation. Operators of blast furnaces want to increase the efficiency of their stacks. One way to do this is to use iron-bearing materials that have been upgraded.

With a 60-per-cent iron material instead of a 50, furnace output can be increased 20 per cent. Four furnaces can do the work of five. That's important, for a blast furnace costs $10 million to $12 million. Auxiliary facilities, such as coke ovens and materials handling equipment, can add another $1 million.

Reducing the Needs—Beneficiation of iron-bearing materials will lower the ratio of tonnage needed per ton of steel output. For every net ton of steel ingots produced 1.2 net tons of iron ore are being used. A 20-per-cent increase i[illegible]



Bucyrus-Erie Co.

No stone is left unturned in the search for iron ore. The Morton mine (operated on the Mesabi by the M. A. Hanna Co.) is being converted from an underground to an open pit operation. Inactive many years because of quicksand seepage, the property is yielding much-needed ore that couldn't be mined profitably by conventional methods. A walking dragline strips the overburden to an average depth of 190 feet to uncover ore. Concrete shaft (center) is a relic of the underground mine

on content of ore through beneciation would lower the ratio to net ton of ore for 1 net ton of aw steel.

This upgrading will not be chieved at once, but over the next ve years considerable strides will e made. At the end of the next en years it's entirely possible that ost of the iron-bearing materials harged into blast furnaces will ave a 60-per-cent iron content, hanks to beneficiation.

Search Is On—The taconite projects have stolen the show in eneficiation, but many other tudies are going on. One is a oint project of Republic Steel orp., Cleveland, and National ead Co., New York, to upgrade outhern iron ore and iron-bearing aterials. A large-scale pilot lant was built last year at Republic's Spaulding iron ore mine near irmingham, where production cale studies of the contemplated pgrading project are being made. he iron ore concentrate is exected to be upgraded sufficiently o warrant its use in blast furaces.

National Lead has broad experince in the treatment of nonferous ores, supplemented by extensive research in Norway during the last nine years. Republic's experience runs from southern iron ore to the beneficiation and use of low-iron content southern nonmagnetic materials.

Atom May Help—Use of atomic energy is one of the hopes of those studying beneficiation of low-grade, iron-bearing materials. When Dr. Robert P. Peterson, a nuclear physicist, joined Republic Steel Corp. a year and a half ago, he said: "It is within the realm of possibilities that by producing heat from a reactor at the source of low-grade ores, atomic energy may play an important part in the economic concentration of low-grade iron ores. This is a new field, but it is one in which there may be great promise."

The quest for iron-bearing minerals will continue as long as we have an expanding population and a rising standard of living. Both increase our use of steel. This means we have to add to our steel in use. We can do so only by extracting it from mineral sources.

• *Extra copies of this article are available in quantities from one to three until supply is exhausted. Write Editorial Service,* STEEL, *Penton Bldg., Cleveland 13, O.*

Boosting Rare Metals Output

Fansteel Metallurgical Corp., North Chicago, Ill., will spend $1 million on an expansion of tantalum and columbium production.

Dr. Frank H. Driggs, president, said that about $200,000 is to be spent on new buildings and alteration of existing ones. The balance will go for chemical processing equipment, electric furnace equipment and electrical switchgear.

Coke Making Capacity Rises

Wilputte Coke Oven Division, Allied Chemical & Dye Corp., New York, has been awarded a contract by United States Steel Corp. for the design and construction of 192 by-product coke ovens (three batteries) and auxiliary equipment at Clairton, Pa. Wilputte is completing an identical installation there.

McKee To Build Sinter Plant

One of the nation's largest iron ore sintering plants is scheduled for the Fairless Works of U. S. Steel Corp. in Morrisville, Pa.

The plant will be built by Arthur G. McKee & Co., Cleveland. Its cost is estimated at $6 million.

It will be the third best peacetime year as . . .

1955 Ore Shipments Rise

LAKE SUPERIOR iron ore shippers with their season nearly over are looking forward to an equally good year in 1956.

This year they expect shipments will total between 85 million and 86 million gross tons. For next year, predictions range from 80 million to 90 million tons.

Forecast—Here's the way one industry leader sees the situation: The 85 million tons shipped in the 1955 season will be more than matched by the consumption of 90 million tons of Lake Superior ore from Apr. 1, 1955, to Apr. 1, 1956. Lake shippers will start next year in an enviable position. Stocks at Lake Erie docks and U. S. and Canadian mills will hit a low point of about 15 million tons in the spring.

No shortages of any grades of ore are expected if shipping starts by Apr. 15. And the ore fleets don't expect to lose any time in getting started next year.

Changes — Lake Superior ore shipments this year will be about 25 million gross tons over last year's but 11 million under 1953's record.

Production of steel this year probably will exceed by 4 million net tons the record 111.6 million tons made in 1953.

Increasing imports of foreign ore (see page 87) have taken the edge off the demand for Lake Superior material. About 9 million more tons of ore will be imported this year than in 1953. Imports will be up about 5 million tons over last year.

Ore shipments in the future will depend on steel operations and the speed with which foreign ore becomes available. Don't expect the Lake Superior region to again ship 99 million tons (including rail and Canadian shipments) as it did in 1953 unless there's an extreme emergency.

Better Ore—With taconite shipments containing better than 58 per cent iron, deliveries can be smaller and still produce the same amount of steel. The percentage of beneficiated ore was 3.4 per cent higher in 1954 than in 1953. This trend seems to be continuing.

All-rail freight from the Mesabi has been affected by the trend to foreign ore. This winter, few rail shipments will be needed to supplement lake transport. Total rail shipments will be about 2¾-million tons, more than last year but less than any year from 1950 through 1953.

Evidence of the increasing use of foreign ore: The *SS Bertha Entz* unloads 20,895 tons of Labrador ore at a Philadelphia pier. Time taken: Less than 9 hours

Alan Wood Orders Equipment

Alan Wood Steel Co., Conshohocken, Pa., will install a 4-high temper mill for its cold rolled department. A new pinwheel-type coiler was ordered recently for its hot-strip mill. Both orders were placed with United Engineering & Foundry Co., Pittsburgh.

The two installations will cost more than $2 million and are part of the second phase of the expansion and modernization program at the Ivy Rock, Pa., plant. The first phase cost more than $45 million in new equipment and buildings during the post World War II period.

Bliss To Make Voss Levelers

E. W. Bliss Co.'s Rolling Mill Division, Salem, O., is building a unique type of leveler for flattening sheet, strip and plate steel and nonferrous materials through a special arrangement with the Voss Engineering Co., Pittsburgh. It produces commercial flatness with the high speed characteristics of conventional roller levelers. The Voss machine relies on a set of long, slender, individually driven work rolls supported by a lattice of short, heavy back-up rollers. These can be precisely adjusted in any direction, either in groups or as a whole. Bliss also will build the Voss chain roller leveler.

To Boost Plastic Pipe Output

Production of plastic pipe by Republic Steel Corp. will be doubled within the next few months. Facilities are being installed in the Cleveland plant of its Pressed Steel Division to produce a wide range of plastic tubular products.

Armco builds new blast furnaces at Middletown, O.

Three More Expansions

New steel company programs keep coming through. Some of the latest: Inland, Wheeling and Carpenter. These three companies will spend $334 million before 1960

INLAND Steel Co., Chicago, Wheeling Steel Corp., W. Va., and Carpenter Steel Co., Reading, Pa., have announced expansion programs. All will be complete by 1960. Total cost: Some $334 million.

Inland's plans are centered on a three-year expansion of the basic steel plant at East Chicago, Ind. Capacity will be increased by 15 per cent, to 6 million tons of ingots a year by 1959. Three new 315-ton, open hearths will provide most of the gain; the remainder will come from improvements to existing furnaces and operating techniques.

Ready for More—Inland's expansion also includes a new blooming mill. Initially, it will handle 1.8 million tons of ingots a year, but it can be equipped for more than 4.7 million tons. A new cold rolling department will be built. By 1959, this will add some 50 per cent to Inland's production of cold-rolled sheet. With auxiliary facilities, its capacity can be built up to 790,000 tons of cold-rolled products each year (see page 115 for more news from Inland).

Wheeling's program will cost $65 million. John L. Neudoerfer, president, says that many of the plans are still in the engineering stage, and that estimates of the amount to be added to ingot capacity are not available. Mr. Neudoerfer says the expansion will be pushed as fast as possible. Though he notes that steel mill equipment builders are unusually busy, he expects the program to be completed within "two or three years."

Detail—Additional steelmaking facilities will be put in to supplement Wheeling's open hearths. The company's two bessemer converters eventually will be replaced. Capacity increases also will be made in the hot strip and cold rolling departments, both of which are to be modernized. Improvements will be made in the skelp and pipe mills at Benwood, W. Va.

Carpenter Steel's immediate plans include a large hydraulic forging press and an electric furnace, both of which are for delivery early next year. The new furnace will increase the company's melting capacity 20 per cent. High speed bar turning equipment, heat treating facilities and new materials handling units also are planned. Carpenter figures that it will spend some $9 million before its expansion is completed.

Barium Steel Consolidates

Barium Steel Corp., New York, N. Y., has merged its plate, pig iron, structural and steel tube plants into a new company to be known as Phoenix Iron & Steel Co. The main divisions will be known as Plate Division, Harrisburg, Pa., (formerly Central Iron & Steel Co.); Blast Furnace Division, Chester, Pa., (formerly Chester Blast Furnace Inc.); Structural Division; and Phoenix Steel Tube Division, both of Phoenixville, Pa.

J. A. Sisto, Barium's chairman, says that the integration will provide more efficient production and quality controls from pig iron to finished products, in addition to other operating benefits resulting from centralized management.

Hoskins Expands in Canada

Hoskins Mfg. Co., Detroit, organized Hoskins Alloys of Canada Ltd. as a wholly owned subsidiary and purchased the Wire Drawing Division of Walker Metal Products Ltd., Windsor, Ont. The Canadian subsidiary will occupy a plant being built in the Toronto, Ont., area. Elmer Berndt is operating vice president in charge of Hoskins' Canadian operation.

Ladish Buys Two Plants

Ladish Co., Cudahy (Milwaukee), Wis., maker of drop forgings, pipe fittings and rolled rings, purchased two manufacturing plants in Los Angeles: CBS Steel & Forge Co. and General Pacific Corp. They will be operated as the Ladish Pacific Division, 3321 E. Slauson Ave. J. L. Varga, who established Ladish Co. of Canada Ltd., will manage the new property.

Pressure on Profits

Speakers at Drop Forging Association's fall meeting stress the profit squeeze. New money demands for plant expansion and research are called critical

WHAT'S a fair profit? How do you make one?

That was the dual theme of the fall industry meeting of the Drop Forging Association at Chicago (Oct. 27-28). Norman W. Foy, vice president of Republic Steel Corp., Cleveland, said that in steel an improved profit picture is essential if the expansions planned for the next 25 years are to be carried through.

Pressure on Profits—Steel, remarked Mr. Foy, must improve its attractiveness to investment capital. Income for all manufacturing (expressed as a return on capital investment) has averaged 12.5 per cent over the last 15 years. Income for steel for the same period was 9.2 per cent.

Built today, he added, a new, fully integrated steel plant could only be expected to give a 2 or 3 per cent return on investment.

The major part of steel's expansion program will have to come from new facilities. By 1960 at the latest, by which time all feasible additions to present capacity will have been made, the pressure on profits will come to a head.

Competition Key—Gordon Walker, president of Walker Forge Inc., Racine, Wis., following through on the "Profits and Prosperity" theme, said that the profit problem was tied up in maintaining the drop forging industry's growth rate against increasing competition from other metalworking processes.

He made these suggestions: Set up incentive and stock ownership programs for supervisory employees; establish management development programs; make research expenditures part of the regular budget; and spread the exchange of technical information within the industry.

Structural Steel Bookings Up

Bookings of fabricated structural steel were 339,461 tons during September.

The American Institute of Steel Construction says this is 64 per cent higher than last September's bookings and is the second highest monthly level of 1955.

September shipments of 289,128 tons were the highest monthly total this year; a 9 per cent increase over the same period in 1954.

Backlogs of work available for fabrication stood at 1.9 million tons as of Sept. 30, according to AISC.

Machine Tool Orders Pick Up

Machine tool shipments for the first nine months of this year total $476.3 million, compared with $722 million a year ago.

Shipments in this period last year were high because toolmakers were catching up with the 1953 backlog of defense orders. For the year they hit $891.7 million.

The machine tool industry estimates new orders for the current nine-month period to be $579 million—almost $158 million over the $421 million for the first three quarters of 1954. Shipments and new orders are for metal cutting types only.

The new order index for September stands at 207.1; shipments are 195.1. In August, new orders indexed at 221.3, shipments at 164.6.

Although September orders dropped, manufacturers say a downward trend isn't indicated. Many companies were holding orders until the Machine Tool Show was over.

Some firms say orders from the show are running their bookings up to 20 or 30 per cent over September orders.

Steelworker Local Celebrates

United Steelworkers of America, Local No. 2, celebrated its 60th birthday, Saturday, Nov. 5, in Joliet, Ill.

The local represents about 375 workers at Phoenix Mfg. Co. Company-Union relations record for 60 years: Two authorized strikes in 1913 and 1942; one postwar wildcat walkout.

Local No. 2's first charter was under the Amalgamated Association of Iron, Steel and Tin Workers of America. It affiliated with the steelworkers in 1942.

New Process Adds Life to Backup Rolls

Blaw-Knox Co., Pittsburgh, finds that cold rolling backup roll fillets increases tensile strength, bolstering fatigue limits to reduce breakage in the fillet

ffice Automation

oses no threat to employment, y bring men back to skilled rical work, study reveals

IE NATIONAL OFFICE Man-ement Association has some swers on what automation will to office employment by 1960. W. H. Evans, NOMA executive ce president, reports: "Automa-on may well reverse the trend nich has women office employees itnumbering men." He adds: Education is needed to learn how use machinery effectively."

Two-Year Survey—NOMA hired rexel Institute, Philadelphia, to udy the problem. Here's what came up with.

The number of office machines ill increase at a rate limited only industry's ability to develop achines and train operators.

Employment—By 1960 there ill be 300,000 office machine op-rators, compared with 150,000 1950. Employment apparently ill double every ten years for the xt few decades. Total office nployment will increase about 4 million in the same period.

The survey bears out Mr. Evans' atement. It says: "Men who ve been leaving office work in owing numbers are being wooed ck to the office by machines." eavy and complicated equipment usually entrusted to male work-s.

Premium on Experience — The ffice machine demands skilled of-ce workers. The demand for em now exceeds requests for un-illed workers.

The final point of the study in-cated that a further economic swing will produce a shortage experienced workers.

In summarizing study results, r. Evans warned: "Impending anges cannot happen overnight. me is required to develop and oduce equipment. Manufactur-g costs must be reduced to make ch machinery practical for any t the larger companies. Many mpanies will hold off purchasing ch equipment during the pio-ering period. Finally, many her companies are probably too nall to ever use electronic equip-ent economically."



Mounting railroad wheel assembly with disc brakes

Sales with a Future

SERVING growing industries is the prosperity prescription at Baldwin - Lima - Hamilton Corp.'s Standard Steel Works Division, Burnham, Pa.

Before World War II, Standard sold 90 per cent of its products to railroads. When diesels came along, a study showed railroads would use smaller volumes of steel forgings, castings and rolled wheels, tires and rings.

More Customers Needed—Then came the decision to serve industries which had brighter prospects for increased purchasing. Railroads still require a hefty 40 per cent of shipments, but other leading customers have taken on a new look.

Best ring customers are producers of all types of rotary machinery. Among the steadiest users are manufacturers of gear rings and the oil and chemical processing industries.

Atomic Age Consumers — "We intend to increase our volume of sales to builders of jet aircraft engines and atomic energy plants," reports Fred E. Greger, sales manager. Standard also is looking farther afield — selling railroad tires and wheels to India and Korea.

First Results — Standard's new look at customers and applications already is paying off.

"Development of our industrial business is largely due to a more intensive search for new applications following a bolstering of our sales force," explains John D. Tyson, vice president and general manager.

For Better Quality — "Demand for top quality of product has increased rapidly in postwar years from both railroads and other customers," asserts Mr. Tyson. "While we are taking a completely new look at customers and building our sales force, quality becomes even more important."

Standard has installed a direct-reading Spectrograph to analyze heats. It insures improved quality as it permits almost instant analysis of steel in the open-hearth furnace.

All this adds up to more customers and better sales for Standard.



California Division of Highways

Congress balked last spring, but now the heat's on for . . .

More Money for Roads

NEW HIGHWAYS will be a "must" item on the calendar when Congress gets back to work. Pressure for better roads is strong—there was much disappointment because highway legislation withered on the vine last spring.

It's almost certain that more federal money for roads will be put up—but it's just about as certain that it won't be as much as government and private groups say is needed.

Defense Need—Current federal aid to highways is pegged at $875 million a year, most of which is matched 50-50 by states. That will probably be upped past $1 billion — some improvement but only about half of what experts say is needed to kick off a really effective highway program. It's far below the $5 billion a year such a program would need after it got rolling.

Top attention is on the 40,000-mile interstate highway system—it's vital to national defense. Recommendations are for more than 50 per cent federal aid on that part of the road network—over 90 per cent in some cases.

Money Snag—Financing is the big problem. Bond issue suggestions haven't proved popular. More likely are a pay-as-you-go plan, higher taxes on highway users. Also likely to come up are tries to end the hodgepodge of state highway laws—especially as they apply to truckers.

There are over 60 million motor vehicles registered in the U. S. In ten years there will be 80 million; in 1975, 92 million, predicts the Independent Advisory Committee to the Trucking Industry Inc.

The number doubled in the last ten years with only about a 1-per-cent addition to national road mileage—that explains the cry for more and better roads.

Automation Gets O.K.

No blue laws against auton tion will result from recently e ed hearings. That's the pred tion of Rep. Wright Patm (Dem., Tex.) who headed the s committee.

Areas that may get attenti are incidental to automation, su as the sore need to train scienti and technicians and the traini and retraining of displaced wor ers. But even that's in the futu

Representative Patman s a most industry representatives the hearings recognize their r sponsibility to retrain workers. H did, however, hit the railroads f "not recognizing their respons bilities." It's possible that legi lation might be needed on the sta or local level if unemployme comes to the railroad industry b cause of automation-caused la offs, he said.

Here and There

The government's budget ma balance this year. Reason: R ceipts substantially higher tha expected. In the July-Augus September quarter, income wa $1.3 billion higher than a year ag —originally, a $1.8-billion increas for the full year starting in Jul was forecast. But spending wi be higher, too—mostly in the D fense department . . . Expec plenty of scrapping in Congres before any tax cuts—Sen. Harr Byrd (Dem., Va.) says it's unsaf to make a permanent tax redu tion based on present boom cond tions and revenue; any budge surpluses now should be used t pay off the debt . . . Sen. Walte George (Dem., Ga.) favors ta cuts in 1956 for low and middle in come groups. Both senators ar on the tax writing Senate financ committee . . . Defense contract worth $101.5 million were let i flood disaster areas in seven week following Hurricane Diane, say the Defense department . . . Mor consolidation of buying by th Armed Forces is being considere by the Defense department.





J. A. Ward: His Business Is Blockbusters

WHEN the huge (17,000 acres) Louisiana Ordnance plant was being built, they say four wells had to be drilled to get water. The first three were capped. They produced oil.

General Manager J. A. Ward is still chuckling, but disclaims any first-hand knowledge of the incident. It *is*, however, the way he works. When he needs water, he *gets* water.

As civilian head of the Army Ordnance Corps installation, he is the top shell production expert for Remington-Rand division, Sperry-Rand Corp. His job: Be ready for maximum production while operating efficiently at only a fraction of shell-producing and shell-loading capacity.

Mr. Ward went to the base, near Shreveport, in February, 1951, when it was re-opened as a shell-loading facility. Starting with a group of buildings, he oversaw installation of all equipment and the start of production. He also supervised the erection and equipping of a shell manufacturing plant on the base. This plant was in pilot-line production six months after ground was broken.

The plant is one of the most modern of its kind in the country. In full production on one line, three more are ready to go whenever they are needed.

Solid Ground—This isn't his first shot at the ordnance game. He formerly was director of maintenance at the Remington-Rand-operated Sangamon Ordnance Plant. While there, he designed and built many special machines that now are standards in shell production.

That was during World War II. After the war, he went with Standard Brands Inc. as chief engineer of the Chase & Sanborn division. Then he returned to the ordnance business at Shreveport.

An electrical engineer from Purdue University, his career has covered most phases of management. He was with Cities Service Co. for 12 years as a sales engineer and superintendent of an operating department. After that, he was general manager of the Manufactured Gas division, Republic Light, Heat & Power Co,, Tonawanda, N. Y.

Mr. Ward makes his home on the closely guarded base. His favorite pastimes, duck hunting and fishing, are naturals for Louisiana.

Rotor Tool Co.

Compressed air industry says automation will help . . .

Air Tool Sales Increase

COMPRESSED AIR tool sales are expected to hit about $125 million this year.

The 25 member companies of the Compressed Air & Gas Institute are willing to admit sales have jumped 50 per cent in the last ten years. They also look for a 17 to 20 per cent increase next year. These figures do not include a baker's dozen of smaller companies that may manufacture one or two specialty tools.

Compressors—Perhaps the most important part of any air or gas operation is the stationary or portable compressor. There are two general types: Positive displacement (reciprocating and rotary) and dynamic (centrifugal, axial and mixed flow).

A bicycle pump is a good example of a positive displacement compressor. Dynamic types impart velocity and pressure to air through rotating vanes.

Why Use Air — One big reason for the increasing use of compressed air is the variety of projects to which it can be adapted. Long used for pavement breakers, foundry chipping hammers and drills, compressed air hoses today are conveying grain from storage bins and agitating chemical liquids by aeration. Air also is used as a coolant or lubricant in many industrial operations. Air tools are particularly well suited to jobs where an explosion might be caused by sparks from electric tools.

Who Uses Them—Automakers use more air tools than any other industry. Aircraft manufacturers run a close second. Construction and mining have used air tools for years.

Automation—This is the coming trend for compressed air. Right now in automobile factories, multiple nut runners, operated by air, fasten up to 20 nuts at a time. Air-powered conveyor lines then move parts to another section.

Problems — Some experts have expressed a fear that new power developments may throw compressed air into the discard, but manufacturers don't agree.

Leslie B. Schramm, secretary of Schramm Inc., West Chester, Pa., and president of CA&GI says: "Twenty years from now supersonic sound might replace air drills for mining operations, but compressed air will still be used to haul out the broken rock."

Meanwhile, the immediate problems center on portable tool torque control, reducing noise and maintaining stable pressures in air lines.

GM Hits Employment Record

General Motors Corp. employed more people in the first three quarters of this year than at any similar time in the company's history.

Harlow H. Curtice, president, says that an average of 621,958 GM employees earned $2321 million during the first nine months of 1955. This compares with 577,069 wage earners, who totaled $1930 million in a similar 1954 period.

Third quarter employment and payroll figures added up to 615,966 and $758 million, compared with 1954's 538,619 and $601 million.

Overtime in GM plants in this country brought the average workweek for nine months up to 42.7 hours from 39.9 hours a year ago. Average weekly earnings rose to $102.21 from $89.85 in 1954.


Steel, Copper, Aluminum
(% of respondents who added to inventories)
STEEL QUARTERLY SURVEY
16%
16%
10%
12%*
First Quarter 1955
Second Quarter 1955
Third Quarter 1955
Fourth Quarter 1955
urvey includes: Steel products (bars, strip, sheet, plate, structural shapes, wire, tubing), pig iron, copper
nd brass mill products, copper wire and cable and aluminum products
Estimated

Metal Users Outrun Supply

'MILL DELIVERIES extended; varehouse stocks inadequate."

"More lead time required to naintain good inventory position."

"Steel mills 'way behind on verything."

"We are buying at premium rices because we can't get de-ivery from mills or warehouses."

Worries—Those are purchasing gents' comments to STEEL's latest heckup on the inventory and de-ivery situation on steel, copper nd aluminum.

"A sad picture," is the way one iscouraged PA sums it up—at a ime when metal producers are vorking at near capacity.

Pointing up the seriousness: Steel shortage is forcing a one-hird cutback in freight car output t Pullman Standard Car Mfg. Co.'s Butler, Pa., plant. About 200 on the plant's 1600-man work-orce will be laid off; the com-any hopes to bring them back about the first of the year.

To Come—One-third of the PAs think the situation will get worse in the coming three months. A few hope to build up their stock; the majority think they'll be able to hold their own (though many added "I hope" to their replies).

Causes of the pessimism: "Although we are in a fairly good position, deliveries have been extended much too far to remain in a well stocked position," ventures a New York area PA.

Next Year—"Deliveries are fairly adequate now. Our concern is for early 1956! We cannot place orders in sufficient quantities and in proportion to present use," says a PA in Pennsylvania.

Aggravating the situation: Some steel users that generally have declines this time of year report business is holding up better than usual.

Quotas—The reaction to being put on quota or allocation by mills is mixed. A Chicago PA sees perhaps a slight improvement in his firm's position.

Not so fortunate are firms in lines that had a bad time last year. The PA for a big farm equipment producer sees his firm's inventories dipping: "Allotments are based on previous year purchases, which in our case were low."

Tears—Adding to the problems: 1. "Some suppliers are overextended on delivery promises, so it fouls up their deliveries. Takes a heap of crying to get delivery as promised," writes a Clevelander.

2. "Mill not accepting any orders for the balance of 1955. Books not open for 1956," says a PA in Pennsylvania.

3. "Have been successful in having orders accepted by mills, but deliveries run 30 to 60 days later than required. Deliveries of even current orders are running two to four weeks late," reports an upstate New York executive.

Sliding—The tightening supply situation shows up in inventory levels indicated on survey returns. On most items, roughly half the respondents say they are in the 30-to-60-day range. Most of the rest are below that. Biggest movement over the last three months was a drop from the 60-to-90-day category. The 10-to-30-day and less-than-ten-day ranges expanded.

Three-fourths of users report delivery problems on one or more products. Greatest demand was for more plates, both light and heavy; about two-thirds of the users have supply difficulties.

Snags—Structural shapes are another particularly sore spot, a little surprising considering the season. Sheets are also tight, mostly because of auto needs.

Users of bars have strongly felt tightening steel supply. "Carbon bar situation is bad, with most mills out of the market for January and possibly part of February," notes an Ohio executive.

Copper and its alloys were harder to get. Aluminum remains tight.

A good many steel, copper and aluminum users are in the same boat with this Virginia firm: "We are using material faster than we can replace it from normal sources of supply."



How Great Lakes Steel *X-rays* quality



Above: Stacking sheets after the X-ray check. *Below:* With dozens of tests passed and uniformity assured, the flat-rolled steel is O.K.'d for wrapping and delivery.



Why do sheets from Great Lakes Steel consistently meet customers' specifications? The X-ray machine is one of the answers. Here an indicator (shown above) signals the thickness of steel sheets as they pass on a conveyor belt. Any sheet failing to meet the established standard is immediately ejected.

Throughout the Great Lakes mills, modern machines and experienced men work together to maintain the consistent quality of our flat-rolled products. Our service includes close contact with customers by Great Lakes representatives, men who are concerned not only with steel production but also with the performance of our steel in the plants of customers.

The next time you have a problem in steel, give us a call. You will find that both quality and service are *consistent* at Great Lakes Steel.

GREAT LAKES STEEL CORPORATION

Ecorse, Detroit 29, Michigan • A Unit of

NATIONAL STEEL CORPORATION

District Sales Offices: Boston, Chicago, Cincinnati, Cleveland, Grand Rapids, Houston, Indianapolis, Lansing, Los Angeles, New York City, Philadelphia, Pittsburgh, Rochester, St. Louis, San Francisco, Toledo, Toronto

New models come out, too, for . . .

Checker Cab: Automaker

NDEPENDENT automaker is a erm perhaps best defined by one f the least known, Checker Cab Mfg. Corp. of Kalamazoo, Mich.

To most folks the name is iden-ified with cab operation rather han manufacturing. Founded in 922 to build cabs for Co-op Check-r Taxi Co. in Chicago, the firm ook over the Kalamazoo plants of eparted Dort and Handley-Knight year later. It maintains today, s it did then, that taxicabs have pecial requirements not met by he normal passenger vehicle.

Checker is in a good position to now. It owns 62 per cent of armelee Transportation Corp., hicago, which controls operating ubsidiaries in four cities and urned in three times as much rofit last year as the parent com-any. The Checker name is spread vider than the scope of company wnership however, since its use as never been restrained.

Live Tests — As an operating ompany, Checker uses its fleets s a proving ground for its prod-ucts and those of the competition. It hangs its whole sales pitch on low operating and maintenance costs and has uncovered some amazing statistics in support of its cause. A Checker-built cab can be operated for about 1 to 1¼-cents a mile. The conventional passenger-car cab costs about 3 cents a mile, according to Checker records gathered under comparable circumstances.

Normal life of a Checker cab is figured at 150,000 miles or 30 months, whichever comes first. It's unusual if the head has to come off during that period. Usual top overhaul time on conventional vehicles is about 70,000 miles.

Nobody knows how far you can drive a Checker cab. During the war, a fleet of them put on over 500,000 miles each, but they were sold for further operation in smaller communities.

Available — If you're thinking about now that you'd like to buy a Checker, the factory (the company has no dealers) will be happy to sell you one. But before you place your order, here's a rundown on some of the factors in Checker's taxi-designed vehicle. Horsepower is about 85, and can be hiked to around 100 with the power pack. But peak torque (180 foot pounds) is reached at only 1200 to 1400 rpm. Top speed is in the vicinity of 65 mph, with a vehicle weight of about 3700 lb. The vehicles are available in standard and Driv-Er-Matic models.

The Driv-Er-Matic offers such plus features as automatic transmission, power brakes, power steering, four-way seat, auxiliary folding seats in the rear and an exclusive, power rear window. Less taxes, this model sells for $2206, features optional low-compression cylinder heads of 5.43 to 1, compared with the 6.7 to 1 standard. This ratio for low-speed operation permits the use of low-grade fuel.

What's more, Checker offers one of the few all-new vehicles for 1956 and is selling this Driv-Er-Matic version for more than $200 less than last year's standard job. This year's standard will go for $1805, a cut of over $600, as most automakers up prices. From that you might conclude that the taxi business is getting competitive. Indeed, it is.

Sales Race—On the basis of figures alone it might be difficult to justify the interest of big manufacturers in the taxi field. There are only about 77,000 cars in the country licensed as cabs—though it's estimated about 140,000 are in service when communities that don't require licensing are included. Plymouth, which claims about 70 per cent of the 45,000 new cabs sold annually, has just introduced a new model reported to be the first in the industry by a major manufacturer. A new Dodge taxi is making a bid, and, of course, Chevrolet and Ford are looking with increased affection on the hack field.

One Detroit spokesman explains that selling cars in every market,

(Material in this department is protected by copyright, and its use in any form without permission is prohibited.)

no matter how limited, is important. But he cites a second reason of perhaps greater significance: People who ride in cars which can take the punishment of taxi service are likely to think that they are rugged vehicles and will be swayed accordingly in their purchase.

Checker feels ready for the competition, expects to double 1955 sales and top the 9900 units sold in 1929, its best prior year. One reason is its all-new cab, shortened to comply with recent ordinance changes in New York City. Offering a 120-in. wheelbase, the cab is only 200 in. long and sports more room in the back than anything competing from Detroit. All four fenders are removable in minutes, getting the cab back on the road in lube-job time while a damaged fender is repaired at leisure.

Under the Hood—The engine is distinctly visible when the hood is lifted, including such forgotten items as distributor, spark plugs, fuel pump, carburetor and oil dip stick. Design is such that any item under the hood may be reached and serviced from the front, including complete removal of the engine—thus avoiding the need for service room along the sides of the cabs to reduce garage space.

The Plant—The second major factor in Checker's bid for more of the cab market in 1956 is its revamped manufacturing facility. Retooling cost about $4 million, a hefty sum for a company that netted only $721,000 last year. Some of its ideas probably will get attention in Detroit.

Checker believes it is using the biggest plastic die ever produced for its roof panel. Also being made on plastic dies are floor pans, doors, hood and rear deck panels. Until this year, it bought its large stampings outside, but with plastic tooling and 40 presses ranging up to a new 750-ton Clearing double-action toggle job, the firm figures it can do the job itself. The pressroom runs about 1000 parts with each die for stock, then changes to another part. The cycle runs about four weeks between runs on a given part, and the only improvement Checker feels might be made in its plastic tooling is the use of steel draw rings on some of the larger parts to reduce abrading.

Production — Completely revamped, and perhaps most interesting, is the new assembly line. It starts logically but uniquely with the assembly of the frame. Box sections are welded in a conventional fixture and then placed in straightening jig. Most taxi collisions are of the front-end type. Indicative of the ruggedness of the frame which features double channels at the front is the fact that air pressure of 2600 psi is required to bend the channels to bring the frame within 0.015 in. of perfect alignment.

The frame is hung on an overhead conveyor and is suspended at the center on each end. This permits workmen to turn the frame to any desired position as front and rear suspension, muffler and tailpipe, brake lines, etc., are added (these parts are purchased outside). Next, the frame enters a spray booth. Dollies are located on each end of the frame as it leaves the booth. They automatically engage a floor conveyor.

The Continental engine (Continental Motors Corp., that is) is dropped into the chassis after th transmission and engine acce sories (purchased from suppliers have been added. The torque co verter, incidentally, is located b two dial indicators within 0.004 i perfect alignment with the cran shaft to insure long and qui operation.

Then—Metal finishing include the interior as well as the exteri of the car due to Checker's she steel interior. After welding an soldering, the unit enters the lea grinding booth and emerges fo final metal finishing, hanging o doors and rear decks. The body chassis unit then transfers to an other conveyor automatically (al together, there are eight in the sys tem) which takes it upstairs. O the way, it passes over an under coating booth and then transfer to a three-speed conveyor, whic indexes rapidly into and out o booths, dwells during the time th bodies are in the booth.

A plastic hood is placed over th engine for protection, and th bodies are washed, rinsed, bonded dried, prime sprayed, dried an then given two color coats, with dry following each. The interior are sprayed with a system i which the body is its own spra booth. A cover is placed over eac window, one being fitted with suction tube to remove excess par ticles.

Even more significant, there i no sanding between coats. Checke persuaded a supplier to develop prime coat as well as lacquer fin ish coats which dry to a hig luster without the need for sand ing or polishing of any kind. It likely that Detroit will show mor than the usual interest in that de velopment.

Finale — The bodies are the trimmed, fenders and hood ar added and the bodies return to th first floor. On the way dow wheels are added and the dollie drop off automatically as a flo conveyor takes over putting th car on its own wheels. After fin servicing, alignment of fron wheels and a trip around a sma test track, another Checker ready to begin its long battle wit traffic.

U. S. Auto Output

Passenger Only

	1955	1954
January	659,719	456,765
February	675,769	443,257
March	794,188	526,076
April	754,007	533,470
May	724,891	494,250
June	649,372	504,811
July	659,979	441,451
August	614,392	436,650
September	461,337†	285,860
October		236,635
November		508,466
December		641,971
Total		5,518,662

Week Ended	1955	1954
Oct. 1	115,723	64,115
Oct. 8	80,271	63,925
Oct. 15	101,581	44,882
Oct. 22	137,425	45,649
Oct. 29	156,377†	68,649
Nov. 5	165,000*	92,766

†Preliminary *Estimated by STEEL
Source: *Ward's Automotive Reports*



*Week ended Oct. 29. Based upon and weighted as follows: Steel Output, 35%; Electric Power Output, 32%; Freight Car Loadings, 22%; and Auto Assemblies, 11%

Confidence: Do Businessmen Have It?

YOU HEAR a lot of talk about *Business Confidence*. About how continuing good business depends on it.

Here are recent statements by metalworking executives:

Near Record — B. E. Estes, director of commercial research, U.S. Steel Corp., predicts: "The steel industry will produce in 1956 very close to the record of about 115 million ingot tons anticipated for 1955. In terms of current capacity this is an operating rate of better than 90 per cent. We expect that the industry will average better than 95 per cent in the first half of 1956 and 85 per cent plus for the rest of the year."

The top men at General Motors, Harlow H. Curtice, president, and Alfred P. Sloan Jr., chairman, say: "Confidence in the progress of the national economy is widespread, and the public has the desire and ability to buy."

Strong Appetite—H. A. Roemer Jr., president, Sharon Steel Corp., states it this way: "Operations at present are at capacity. Customer demand for our products continues strong. The backlog of orders assures capacity operations throughout the balance of the year, and indications are that a good demand for steel products will continue in 1956."

Clevite Corp.'s bearing and bushing business is enjoying one of the largest peacetime years on record; sales in the electronics field have also improved over last year's. "We believe that our business will continue at high levels into 1956," report James L. Myers (chairman) and William G. Laffer (president).

Favorable Outlook—Kawneer Co. fabricates aluminum for the building, aircraft and appliance industries. President Lawrence J. Plym sees this: "The construction of retail, business, office, industrial, educational and hospital structures is creating a growing demand for our building products. Use of our appliance products by the major manufacturers continues to spread. Kawneer's outlook for the final

BAROMETERS OF BUSINESS

	LATEST PERIOD*	PRIOR WEEK	YEAR AGO
INDUSTRY			
Steel Ingot Production (1000 net tons)[2]	2,368[1]	2,413	1,822
Electric Power Distributed (million kw-hr)	10,630[1]	10,644	9,033
Bitum. Coal Output (1000 tons)	9,815	9,760	9,033
Petroleum Production (daily avg—1000 bbl)	6,680[1]	6,753	6,174
Construction Volume (*ENR*—millions)	$295	$420	$220
Automobile, Truck Output (*Ward's*—units)	188,110[1]	169,197	90,662
TRADE			
Freight Car Loadings (1000 cars)	830[1]	834	756
Business Failures (Dun & Bradstreet, no.)	215[1]	239	229
Currency in Circulation (millions)[3]	$30,498	$30,621	$29,970
Dept. Store Sales (changes from year ago)[3]	+8%	+8%	+9%
FINANCE			
Bank Clearings (Dun & Bradstreet, millions)	$21,076	$24,116	$19,337
Federal Gross Debt (billions)	$280,033	$280,008	$278,741
Bond Volume, NYSE (millions)	$18,766	$15,910	$16,550
Stocks Sales, NYSE (thousands of shares)	8,992	8,666	10,489
Loans and Investments (billions)[4]	$85,542	$86,102	$84,675
U. S. Govt. Obligations Held (billions)[4]	$30,941	$31,419	$37,403
PRICES			
STEEL's Finished Steel Price Index[5]	208.90	208.90	194.53
STEEL's Nonferrous Metal Price Index[6]	264.1	263.9	218.4
All Commodities[7]	111.1	111.2	109.6
Commodities Other than Farm & Foods[7]	118.7	118.6	114.6

*Dates on request. [1]Preliminary. [2]Weekly capacities, net tons: 1955, 2,413,278; 1954, 2,384,549. [3]Federal Reserve Board. [4]Member banks, Federal Reserve System. [5]1935-1939=100. [6]1936-1939=100. [7]Bureau of Labor Statistics Index, 1947-1949=100



TOUGHER!

Allen

LEADER POINT CAP SCREWS

Dropping, knocking against metal surfaces and faulty line-up are major causes of damaged threads. Allen's new unthreaded leader point substantially reduces the causes of screw thread injury, or damage to threaded holes. Grip Heads, precision fit sockets that adhere to the key, *plus* the new leader points, make Allens the world's easiest starting cap screws, particularly in inaccessible spots. Sold *only* thru leading Industrial Distributors.



ALLEN

MANUFACTURING COMPANY

Hartford 2, Connecticut, U.S.A.

ALLEN HEAD



	Shipments 1955	Shipments 1954	Unfilled Orders* 1955	Unfilled Orders* 1954
Jan.	1,092	932	783	872
Feb.	1,106	936	852	865
Mar.	1,315	1,047	842	842
Apr.	1,294	995	966	826
May	1,310	943	938	775
June	1,296	987	982	804
July	1,070	821	1,050	829
Aug.	...	935	...	830
Sept.	...	921	...	811
Oct.	...	942	...	789
Nov.	...	997	...	760
Dec.	...	1,074	...	745
Total	...	11,530		

*For sale. U. S. Bureau of the Census



	Shipments 1955	Shipments 1954	Unfilled Orders* 1955	Unfilled Orders* 1954
Jan.	82.0	70.3	99.8	85.6
Feb.	86.0	69.1	101.8	81.6
Mar.	102.4	84.3	99.7	74.2
Apr.	101.2	74.5	104.1	69.1
May	98.4	67.9	106.4	67.0
June	99.5	72.8	107.6	60.2
July	76.0†	50.9	115.0	63.7
Aug.	....	59.3	....	62.5
Sept.	....	58.0	....	66.7
Oct.	....	64.3	....	71.1
Nov.	....	70.0	....	80.7
Dec.	....	87.9	....	85.1
Total	....	829.3		

*For sale. U. S. Bureau of the Census
†Preliminary

Charts copyrighted, 1955, STEEL

quarter of 1955 and on into 1956 is favorable. Unless there are economic or other unpredictable developments that are not now apparent, the company should continue to progress."

Charles C. Jarchow, president, American Steel Foundries, states that prospects for both shipments and earnings are good for the quarters ending Dec. 31, 1955, and Mar. 31, 1956. The 1956 fiscal year should show improvement over the year just ended (Sept. 30).

Shareholders of Townsend Co., producer of rivets, fasteners and cold formed parts, were told by President F. R. Dickenson that the company expects: "Demands for products in the coming 12 months will continue at a high level, particularly in the automotive and aircraft fields."

What Do You Think? . . .

President George Spatta of Clark Equipment Co. says: "We expect the present high activity to continue for the balance of the year. On the whole we believe our prospects continue favorable and that the company and its employees will have a very good year."

Gardner-Denver Co. serves a diversified group of customers in oilfields, mining, construction and manufacturing. G. V. Leece, president, expresses this outlook: "The volume of incoming orders suggests that business for the remainder of the year will continue on the present high level. Our plans call for the purchase of additional machine tools and some manufacturing facilities in 1956 to handle increased volume."

Railroad Plans To Buy . . .

Translating confidence into action: The board of directors of the C&O Railway has authorized $28.4 million for improvements, new facilities and equipment. Included are 1000 coal hopper cars and 1000 gondolas for steel, ore and coal ($15.3 million worth). Also on the agenda are freight yard improvements and centralized traffic control. O.K.'d was construction of a $3.2 million coal dumping facility authorized earlier by the board's executive committee.

Those freight cars just authorized are in addition to other equipment costing $49.9 million, including 1500 coal hopper cars already ordered for delivery next year, 1000 boxcars and 80 locomotives now being received and another 80 locomotives to be received next year.



	1955	1954	1953
Jan.	81.0	173.8	99.6
Feb.	90.4	99.9	97.5
Mar.	163.6	82.7	132.2
Apr.	178.6	125.3	111.8
May	145.7	80.8	182.1
June	186.8	86.4	156.4
July	213.4	68.8	158.9
Aug.	134.0	75.6	235.5
Sept.	....	68.3	127.7
Oct.	....	147.5	87.1
Nov.	....	61.4	149.4
Dec.	....	113.9	160.8

Foundry Equipment Mfrs. Assn.



	1955	1954	1953
Jan.	140.9	167.4	161.4
Feb.	148.5	165.1	188.1
Mar.	172.8	128.6	158.9
Apr.	179.8	158.2	217.1
May	205.2	132.5	189.8
June	193.5	127.4	146.5
July	201.7	141.3	120.7
Aug.	217.6	154.7	121.6
Sept.	246.5	135.1	135.6
Oct.	....	152.3	211.1
Nov.	....	116.7	144.9
Dec.	....	182.2	194.0

American Gear Mfrs. Assn.

Industry Turns On the Heat . . .

The Industrial Heating Equipment Association indicates the industry is continuing to boom. September orders for industrial furnaces were well over three times those of a year ago. To date, 1955 business is almost double that of 1954, announces Carl L. Ipsen, IHEA executive vice president.

Induction heating equipment sales continue at a lively pace, too. September's business was two and one-half times last year's. To date, orders are 173 per cent ahead of those at this time last year.

Full Speed Ahead, Say PAs . . .

Purchasing agents find conditions in October indicate good business well into 1956. At the end of October, 95 per cent of the Business Survey Committee of the National Association of Purchasing Agents reported: Production as high or higher than September's. Almost as many (93 per cent) said new order position was the same or better.

Employment is highest since mid-1950. PAs indicate: Needs high, workers scarce, with a great shortage of trained engineers and skilled workmen.

A fourth report higher inventories—protection against raw material shortages, forward buying of scarce items and an acceleration to match increased sales and production are reasons.

Buying policy: About half are in the 90-day-and-over range. For capital goods, 77 per cent are in that category.

The consensus shows any inclination to resist inflationary price trends in some scarce items is tempered by the realism of having to purchase for highly expanded business needs.

Trends Fore and Aft . . .

Contracts for heavy construction let so far in 1955 are practically equal to the total for all of the record year, 1952, reports *Engineering News-Record* . . . Volume in the gearing industry increased 13.3 per cent in September over August, notes the American Gear Manufacturers Association . . . Sales of GM passenger cars set another all-time record in the second ten days of October . . . Consumers are still expanding their purchases, says the Commerce department . . . Resistance Welder Manufacturers' Association reports new orders up 36 per cent in first nine months over a year ago.



HERE'S PROOF OF VERSATILITY



NITRALLOY-G STEEL



416 STAINLESS



STEEL PIPE NIPPLE



ALUMINUM



SAE 4130

SUN DEVELOPS VERSATILE NEW CUTTING OIL FOR SCREW MACHINES AND JOB SHOPS

New cutting oil, Sunicut 5534, is moderately priced... gives excellent machining results on wide range of steels

New Sunicut 5534 is a non-emulsifying, transparent cutting oil specially compounded to give above-average machining results to operators who want a single oil to machine a large variety of ferrous metals.

Tests have proved that new Sunicut 5534 meets this demand for an all-purpose cutting oil. It is ideal for general screw machine and turret lathe work. It is also excellent for tapping, drilling, threading, and light stamping operations. In addition, new Sunicut 5534 can be used on many special machining jobs, both high and low speed, with metals ranging from B1112 to 4130 as well as free-machining stainless steels.

For complete information about new Sunicut 5534 and how it can help you reduce your oil inventories...lower your production costs...see your Sun representative. Or write SUN OIL COMPANY, Phila. 3, Pa., Dept. S-11.

SUNOCO®

INDUSTRIAL PRODUCTS DEPARTMENT

SUN OIL COMPANY, PHILADELPHIA 3, PA.

IN CANADA: SUN OIL COMPANY, LTD., TORONTO AND MONTREAL



LEON WEINTRAUB
. . . Eastern Brass & Copper works mgr.

Leon Weintraub was appointed works manager, **Eastern Brass & Copper Co. Inc.**, New York. He is in charge of the production program as well as quality control and methods systems. Mr. Weintraub was works manager of National Silver Co.

United States Steel Corp., Pittsburgh, appointed **R. Conrad Cooper** vice president, administration planning, to assist in development and application of over-all programs and policies. **John E. Angle**, general superintendent at the Gary, Ind., sheet and tin mill, succeeds Mr. Cooper as vice president, industrial engineering.

Andrew L. Pontius was made general manager of Illinois Tool Works' **Shakeproof Division** operations at Elgin, Ill.; **Silas S. Cathcart** assumes the same post at Shakeproof's special products division in Des Plaines, Ill. The Shakeproof Division, to be consolidated at the St. Charles Road plant at Elgin, will include engineering, manufacturing and sales of standard parts.

Goff Smith was elected president of **Griffin Wheel Co.**, Chicago, a subsidiary of American Steel Foundries. He was executive vice president and succeeds **Edmund Q. Sylvester** who resigned to establish a wheel manufacturing business in South Africa.

ARTHUR G. BIGNALL
. . . president of Lasalco Inc.

Arthur G. Bignall was elected president of **Lasalco Inc.**, St. Louis. Formerly vice president, he succeeds **Herman Struckhoff** who resigned to establish a metal finishing supply company on the West Coast and will represent Lasalco's line of electroplating equipment. **Norman K. House**, former chief engineer, was elected vice president.

D. M. Hallier was appointed manager of cutting tools, **Motch & Merryweather Machinery Co.**, Cleveland. He will direct operations of both the cutting tool distributor division and the cutting tool manufacturing division. He has been manager of the latter division since 1949.

Sidney E. Leese was appointed chief engineer of **Houdaille-Hershey Corp.'s** automotive division in Buffalo. He was with Bendix Aviation Corp.

Donald E. Stoops was made manager of distributor sales, transmission division, **Clark Equipment Co.**, Jackson, Mich.

Reginald Whitson was made West Coast regional manager at Pasadena, Calif., for **Warner Electric Brake & Clutch Co.** He succeeds **Vernon D. Enwald**, now midwestern regional manager. **Wesley E. Timmcke** was made southern regional manager, Atlanta.



DAVID S. JENNINGS
. . . Central Screw president-treasurer

Central Screw Co., Chicago, elected **David S. Jennings** president and treasurer; **Ross B. Warren**, executive vice president and assistant treasurer; **Ernest Payne**, vice president-sales; **Ray E. Nelson**, secretary; and **Walter E. Grandstrand**, assistant secretary.

George F. Haback was elected vice president - engineering, **Worthington Corp.**, Harrison, N. J. His responsibility for the engineering activity includes research and development. **Harry A. Feldbush**, former vice president-engineering, will continue as consultant on special engineering problems.

Charles S. Beshore, director of system and procedures for **Automatic Transportation Co.**, Chicago, was promoted to director of purchases. He succeeds **Carle J. Blakeslee**, retired.

John W. Rogers, in addition to duties as sales manager, was made director of sales and engineering for **Wean Equipment Corp.**, Cleveland. **Albert J. Sarka** was named chief development engineer, **Kenneth R. Keska** chief engineer.

International Resistance Co., Philadelphia, appointed **Guy B. Entrekin** manager of its new plant at Burlington, Iowa. He was chief product engineer.

Harold G. Leibold was made sales

EVERETT N. SIEDER
. . . marketing mgr., Alco thermal products



ROBERT G. WINGERTER
. . . gen. mgr., Timken automotive div.

HARVEY B. WILGUS
. . . Electric Products gen. sales mgr.

manager of refractories for **Cleveland Quarries Co.**, Amherst, O.

Everett N. Sieder was made marketing manager of thermal products, **Alco Products Inc.**, Schenectady, N. Y. He was manager of thermal product planning.

T. Coolidge Sherman succeeds the late **Harold N. Arbuthnot** as Washington representative for **Allegheny Ludlum Steel Corp.**

Leonard H. Glasgow, William A. Hattman and **J. B. G. Roberts** head production planning units at **Pittsburgh Steel Co.** Mr. Glasgow becomes superintendent, schedules and service, Monessen, Pa., Works; Mr. Hattman, superintendent, sheet mill schedules and service, Allenport, Pa., Works; Mr. Roberts, superintendent, tube mill schedules and service, Allenport.

Southern Peru Copper Corp., New York, elected **Edward Tittmann** president and chief executive officer. He was general manager, western department, American Smelting & Refining Co.

Northrop Aircraft Inc., Hawthorne, Calif., named **Frank W. McNab** chief of quality control and **Don L. Vivrette** manager of contract administration.

Cutler-Hammer Inc., Milwaukee, appointed **E. B. Fitzgerald** division manager, responsible for the sale of mill and heavy industry controls.

Robert G. Wingerter was made general manager, automotive division, **Timken Roller Bearing Co.**, at Detroit. He succeeds **Edgerly W. Austin**, who retires from that position but will serve as consultant at the Detroit office.

Louis S. Foulkes Jr. was elected president of **Vogt Mfg. Co.**, Rochester, N. Y. He succeeds **Raymond A. Lander**, now chairman.

Warren Carhart was made sales manager, **Texas Alloy Products Co.**, Houston. He was general manager of the southwestern gear division of Western Gear Co.

In the Danville, Ill., plant, central foundry division, **General Motors Corp.**, **Dale Wonus** was made superintendent of the malleable shell department.

Col. Charles A. Reif was elected chairman and **Robert C. Sanderson** president and general manager of **Reif-Rexoil Inc.**, Buffalo.

J. D. Harmison is now manager, parts sales, for the tractor group of **Allis-Chalmers Mfg. Co.**, Milwaukee.

William L. Pelz was made Cincinnati district sales manager, steel and tubes division, **Republic Steel Corp.**

Walter Kassebohm was elected president of **Marchant Research Inc.**, subsidiary of Marchant Calculators Inc. at Oakland, Calif.

Harvey B. Wilgus was appointed general sales manager, **Electric Products Co.**, Cleveland. He was general sales manager, Redmond Co. Inc.

Named to a new executive management committee of **Prudential Industries Inc.**, Philadelphia, are: **Oliver J. R. Troup**, president; **Edward Rexer**, executive vice president-operations; and **Jack Troup**, vice president-treasurer. **Oliver J. R. Troup Jr.** was made vice president-general manager of Atlas Chain & Mfg. Co., a subsidiary. **John A. Troup II** was made vice president-general manager of Atlas Precision Products Co., a division.

Robert McC. Maxwell was elected executive vice president of **Chandler Boyd Co.**, Pittsburgh, jobber of mill supplies. **James L. Perrott** was made sales manager.

M. E. Young succeeds **A. A. Piper**, resigned, as Chicago district manager, **Electric Controller & Mfg. Co.** Mr. Piper will act as consultant in the Chicago area.

Vincent Barreca, president of Canadian Admiral Corp., was appointed to the new post of vice president-operations of the parent company, **Admiral Corp.** He will have headquarters in Chicago and retains his Canadian affiliation.

Allen S. Johnson joined the electronics division of **Thompson Products Inc.**, Cleveland, as assistant to the division manager, a new

Mills, Drills, Bores, Turns Differential Gear Carriers

Another Transfer-matic by Cross



- ★ Rough and semi-finish bores pinion bores and cross bores; rough and finish faces and turns pilot diameter of torque tube flange; mills faces of cross bore bosses; spotfaces flange mounting holes; drills, chamfers, reams and taps all other holes except flange holes.
- ★ 115 pieces per hour at 100% efficiency.
- ★ 73 operations: 8 milling, 8 boring, 2 crossfacing, 1 turning, 18 drilling, 10 spotfacing, 7 chamfering, 2 reaming, 9 tapping, 8 probing.
- ★ Complete interchangeability of all standard and special parts for easy maintenance.
- ★ Palletized work holding fixtures with hydraulically operated torque wrenches for clamping and unclamping parts.
- ★ Washing and drying unit for cleaning fixtures between last cutting station and loading station.
- ★ Other features: Construction to J.I.C. standards; hardened and ground ways; hydraulic feed and rapid traverse; automatic lubrication system.



Established 1898

THE **CROSS** CO.

DETROIT 7, MICHIGAN

Special MACHINE TOOLS



WILLIAM F. WOLF
. . . Harron, Rickard & McCrone v. p.

JACK WHITESIDE
. . . heads Simpson Electric Division

CALVIN H. COREY
. . . Brooks & Perkins v. p.

post. For the last 12 years he was with Webster-Chicago Corp.

William F. Wolf was elected vice president and manager, machine tool division, **Harron, Rickard & McCone of Southern California,** Los Angeles. He is former owner of W. F. Wolf Machinery Co., machine tool distributing firm.

Elbert M. Foudray was made manager of sales in charge of the Portland, Oreg., office of **Columbia-Geneva Steel Division,** U. S. Steel Corp.

Vincent V. Tivy was appointed chief application engineer for **Foxboro Co.,** Foxboro, Mass.

Ralph E. Campbell was made Pittsburgh district manager, **SKF Industries Inc.** He was field engineer in the same office.

Jack Whiteside, general manager, **Simpson Electric Co.,** Chicago, was promoted to vice president of the parent company, American Gage & Machine Co., in charge of the Simpson Electric Division.

John T. Obrig was named eastern regional sales manager, heating and cooling division, **Union Asbestos & Rubber Co.** He has headquarters in New York.

Walter E. Nolan heads a new aluminum sales division of **Hawkridge Bros. Co.,** Boston, a distributor of Kaiser Aluminum & Chemical Corp.

J. E. Zollinger, director of defense contracts, **International Business Machines Corp.,** New York, was promoted to executive assistant to the vice president-sales, in charge of sales research and planning.

Brooks & Perkins Inc., Detroit, elected **Calvin H. Corey** vice president, responsible for liaison work between the company and atomic industry. For the last eight years he has been manager of B&P's Washington office, a position he retains.

George W. Porter, manager at Seattle for the reinforcing products department of **Joseph T. Ryerson & Son Inc.,** transfers to Spokane, Wash., in a similar capacity. He is replaced at Seattle by **Claude V. Baker.**

Henry C. Curtis was made director of domestic industrial engineering and production control for **Burroughs Corp.,** Detroit. He succeeds **Robert A. Atkins** who was appointed director of overseas manufacturing, a newly created staff position.

OBITUARIES . . .

George W. Duncan, 56, sales manager, **Ohio Electric Mfg. Co.,** Cleveland, died Oct. 25.

Harold H. Cheney, 56, former plant manager, **Logan Gear Co.,** Toledo, O., died Oct. 17.

Louis C. Hyatt, 64, former works manager, **Consolidated Car Heating Co.,** Albany, N. Y., died Oct. 20.

Frederick E. Munschauer, 70, president and general manager, **Niagara Machine & Tool Works,** Buffalo, died Oct. 22.

William B. Fageol, 75, retired executive vice president, **Twin Coach Co.,** Kent, O., died Oct. 24.

Wilbur C. DeGraff, 57, for the last 30 years a sales engineer for **Warner & Swasey Co.,** Cleveland, died Oct. 24.

Otto Paschkes, 70, president, **Astron Mfg. Corp.,** East Newark, N. J., died Oct. 25.

David Loveman, president, **D. Loveman & Son Inc.,** Cleveland, died Oct. 26.

Dr. Aaron B. Bagsar, 58, retired chief metallurgical engineer, **Sun Oil Co.,** Philadelphia, died Oct. 7.

Blaine S. Smith, retired president, **Universal Atlas Cement Co.,** U. S. Steel Corp., died Oct. 27.

Martin A. Fisher, executive vice president, **Standard Buffalo Foundry Inc.,** Buffalo, died Oct. 25.

Wide Flange Beams Roll from New Mill

Inland Steel enters new field as its Indiana Harbor facility begins production of sections which are in strong demand from builders of a wide variety of structures

WIDE FLANGE beams are being rolled on Inland Steel Co.'s new semiautomatic mill at its Indiana Harbor Works.

Current production is limited to trial runs on 8, 10 and 12-in. sections. The size range is 8 to 24 in.

Electronic devices include automatic controls which can be preset to adjust the position of the rolls. The operator is freed from some of the manual operations required by older mills.

The new facilities were built by revamping the plant's 28-in. structural mill, which had a rolling record spanning two world wars. New machinery and equipment were installed, some facilities were relocated and several building extensions were built.

One-Man Operation — Heart of the operation is a 44-in. universal beam mill and a 34-in. edging mill, operated in tandem by one operator. A new 6000-hp electric motor was installed to drive them.

Other new equipment includes a 40-in. finishing mill, a 175-ton crane, a 66-in. hot saw and a 66-in. cold saw, a gag press and a roller straightener.

A 220-ft building extension was erected to store wide flange beam rolls; another building was extended 220 ft; and a 640-ft warehouse building was built to house the finishing processes.

Varied Products — The new equipment makes the 28-in. structural mill one of the most versatile in the country, company officials claim. A variety of products is possible mainly because interchangeable roll housings can be made up in advance of rolling schedules. The new wide flange beam mill housing can be picked up by the 175-ton crane and transported out of the way when other products are scheduled for rolling.

Wide flange beams are used extensively in all types of structures and are in growing demand by builders because of their greater strength in relation to weight. Advantages stem from uniform flange thickness from center to edge. Strength, rigidity and resistance to twisting are increased. Longer spans are possible, so greater floor areas can be planned without intermediate support. The product is used widely in highway bridges and overpasses, in one-story industrial buildings, schools and hospitals.

Ford To Build Parts Plant

Ford Motor Co., Dearborn, Mich., will build a 600,000-sq-ft parts manufacturing plant 4 miles southeast of Ypsilanti, Mich. John S. French, general manager of the Parts & Equipment Mfg. Division, says the new facility will be known as the Rawsonville plant. Production will start in a portion of the plant by late 1956.

Buys Hufford Machine Works

Hufford Machine Works Inc., El Segundo, Calif., has been purchased by a group organized by William Husted, New York. Hufford Machine Works makes machines and equipment for the aviation and electronic industries. President of the West Coast company is M. L. Bengtson; vice president in charge of sales is K. M. Crawford. All former officers remain with the company.

Warehouse Changes Hands

Federated Steel Corp., Pittsburgh, sold its Fort Duquesne Steel Co. division to a corporation headed by J. F. Lott, president of Fort Duquesne Steel. Mr. Lott is president and treasurer of the new company, which retains the same name; E. G. Sheasby is vice president-sales; G. A. Krebs, assistant treasurer.

Federated will change its name to Lott Co. and will diversify its interests. It will continue its activities in the steel and aluminum warehouse business through its ownership of Morrison-Drabner Steel Co., Cincinnati, and a minor-

(*Please turn to page* 118)

tough sprayed metal

well-known maintenance method now profitable production process

equipment fabricators find tough, high-quality sprayed metals build big bonus pay-offs

Modern metallizing—metal spraying—which for many years has saved millions of maintenance dollars by restoring worn machine parts for thousands of companies, is now helping many others improve their products, cut production costs.

In the production of new equipment, tough sprayed metal coatings provide highly desirable mechanical or electrical characteristics at low cost, in high speed, semi-automatic production.

General Electric, for example, a long-time user of metallizing to provide superior wearing qualities on critical areas of large turbine shafting, now applies sprayed metals to a wide range of its products. Many forward-looking companies have instituted investigative programs in their research and design labs to explore the use of metallizing as a means of giving their products competitive advantages in quality, or performance or price—or all three.

Metallizing may be able to help your company improve its products, economically, reduce machine maintenance costs, cut your bills for corrosion protection. It may pay you well to look into it. In any event you will find it a fascinating subject. Bulletin 51 illustrates and describes "Metallizing—its practical applications"—shows actual work being done in users' shops. We shall be happy to send you a copy.

METCO®

Metallizing Engineering Co., Inc.

1167 Prospect Ave., Westbury, L. I., New York
Telephone: EDGEWOOD 4-1300 • Cable: METCO
In Great Britain: METALLIZING EQUIPMENT COMPANY, LTD. — Chobham near Woking, England



FLAME HARDENED MEEHANITE PRODUCE JET ENGINE PARTS

Cockshutt Aircraft Limited, Renfrew, Ont manufacturers of jet engine components, found the use of flame hardened Meehanite are the all-'round answer to better perform in service in the production of pressed parts a superior finished product.

Flame hardening set-up for hardening Meehanite dies prior to chrome plating.

Meehanite punch-draw and pressure rings; chrome-plated for second draw on 600-ton Dominion Hydraulic Press. Flame tube center section.

Builder says:

"In producing parts for jet engine combustion systems, we have found that flame hardened Meehanite metal dies are far superior to those made from ordinary gray iron castings when used on hydraulic or mechanical presses.

The rings and punches made from flame hardened Meehanite metal for use on our Cincinnati Hydroform Presses are equal in performance to those made from far more costly materials.

For further improvement and to avoid scores and scratches during drawing operations, it is found beneficial to hard chrome plate the work surfaces of the die, but it is important that the die is hardened before plating to reduce peeling or chipping of the chrome to a minimum."



J&B "PANTO-MILLER"

Another Precision Tool Specifying Meehanite Components

Johnson & Bassett, Inc., Worcester, Massachusetts, build a 2-dimensional pantograph engraver known as the "Panto-Miller". Designed for versatility, precision and efficient production, this unit incorporates Meehanite castings for all major, vital parts.



J & B — "Panto-Miller" showing Meehanite pa

Builder says:

"Our use of Meehanite castings in general is due to the excellent machinability, tensile strength and rigidity. It is important to our Panto-Miller that we have these three features, plus the important feature of vibration absorption. Our machine is a duplicating machine and, of course, must be extremely accurate and we require the best materials available as insurance against blow holes, distortion, etc."

dustries report what Meehanite Castings have done for them



Meehanite drive gear.

RUGGED HARDINGE GRINDING MILLS BUILT WITH MEEHANITE CASTINGS

The name "Hardinge" has long been famous in those fields where the grinding or pulverizing of all types of materials is a basic requirement. As manufacturers of the highly successful Conical Grinding Mill, the Hardinge Manufacturing Company, York, Pennsylvania, materials specifications call for maximum properties and service life and Meehanite castings are used for important basic components. These include:

1. Mill Shell • 2. Trunnions • 3. Gear Ring and Gear • Main Bearings

Builder says: "We undertook the manufacture of Meehanite castings in our foundry some years ago, not only as a means of improving foundry efficiency and quality of castings, but in order to produce cast components such as these which will provide maximum wear resistance, high strength and toughness and the uniformity of these properties which enables us to assure our customers that they are buying a *better* product when they buy from Hardinge."

Meehanite grinding mill shell.

Mill bearings are Meehanite castings.

ONLY A MEEHANITE FOUNDRY CAN MAKE MEEHANITE CASTINGS

The American Laundry Machinery Co. . Rochester, New York
Atlas Foundry Co. . . . . Detroit, Michigan
Banner Iron Works . . . . . St. Louis, Missouri
Barnett Foundry & Machine Co. Irvington and Dover, New Jersey
Blackmer Pump Company . . . . . Grand Rapids, Michigan
Compton Foundry . . . . . Compton, Calif.
Continental Gin Co. . . . . Birmingham, Alabama
The Cooper-Bessemer Corp. Mt. Vernon, Ohio & Grove City, Pa.
Crawford & Doherty Foundry Co. . . . . Portland, Oregon
DeLaval Steam Turbine Co. . . . . Trenton, New Jersey
M. H. Detrick Co. . . . . Newark, N. J. and Peoria, Ill.
Empire Pattern & Foundry Co. . . . . Tulsa, Oklahoma
Farrel-Birmingham Co., Inc. . . . . Ansonia, Connecticut
Florence Pipe Foundry & Machine Co. . Florence, New Jersey
Fulton Foundry & Machine Co., Inc. . . . Cleveland, Ohio
General Foundry & Manufacturing Co. . . . Flint, Michigan
Georgia Iron Works Co. . . . . Augusta, Ga.
Greenlee Foundry Co. . . . . Chicago, Illinois
The Hamilton Foundry & Machine Co. . . Hamilton, Ohio
Hardinge Company, Inc. . . . . New York, New York
Hardinge Manufacturing Co. . . . . York, Pennsylvania
Johnstone Foundries, Inc. . . . . Grove City, Pennsylvania
Koehring Co. . . . . Milwaukee, Wisconsin
Lincoln Foundry Corp. . . . . Los Angeles, California
Palmyra Foundry Co., Inc. . . . . Palmyra, New Jersey
The Henry Perkins Co. . . . . Bridgewater, Massachusetts
Pohlman Foundry Co., Inc. . . . . Buffalo, New York
Rosedale Foundry & Machine Co. . . Pittsburgh, Pennsylvania
Ross-Meehan Foundries . . . . . Chattanooga, Tennessee
Shenango-Penn Mold Co. . . . . Dover, Ohio
Sonith Industries, Inc. . . . . Indianapolis, Ind.
Standard Foundry Co. . . . . Worcester, Massachusetts
The Stearns-Roger Manufacturing Co. . . Denver, Colorado
Traylor Engineering & Mfg. Co. . . Allentown, Pennsylvania
Valley Iron Works, Inc. . . . . St. Paul, Minnesota
Vulcan Foundry Company . . . . . Oakland, California
Washington Iron Works . . . . . Seattle, Washington

CANADA

Hartley Foundry Division—
London Concrete Machinery Co., Ltd. . Brantford, Ontario
E. Long Ltd. . . . . Orillia, Ontario
Otis Elevator Co., Ltd. . . . . Hamilton, Ontario

Write for your copy of **"The Handbook of Meehanite Metals"**

This Advertisement Sponsored by Foundries listed above

MEEHANITE METAL® CORP.

714 North Ave., New Rochelle, N. Y.

EASY-FLO brazed construction

the ☆EASY... ☆FAST... ☆LOW-COST WAY...

...TO MAKE PARTS LIKE THESE...

Thousands of small parts are now made of stampings and screw machine parts joined with the low-temperature silver brazing alloy EASY-FLO. This construction provides one-piece strength and is surprisingly economical – especially when a production setup is used that *automationizes* the actual brazing.

Victor Adding Machine Co., Chicago, makes quite a few parts the EASY-FLO brazed construction way. Here you see some typical examples.



Bushing is induction brazed to case hardened stamping on turntable fixture with EASY-FLO 45 wire automatically fed and positioned at joints. Operator merely loads parts. Time per assembly—3½ seconds—500 per hour.



Frame above is made by brazing side pieces to rods on induction coil setup shown. Output of 120 frames (480 joints) per hour is easily maintained. At left – a few other parts similarly produced.



Expert brazing production know-how at your call

To users of EASY-FLO and SIL-FOS silver brazing alloys, and to designers and production men considering their use, we offer full cooperation in working out joint designs and fast production procedures. Ask for a field engineer to call.

For full EASY-FLO and SIL-FOS facts in print write today for Bulletin 20.



HANDY & HARMAN

HANDY & HARMAN

General Offices: 82 Fulton St., New York 38, N. Y.

DISTRIBUTORS IN PRINCIPAL CITIES

OFFICES and PLANTS
BRIDGEPORT, CONN
PROVIDENCE, R. I.
CHICAGO, ILL.
CLEVELAND, OHIO
DETROIT, MICH.
LOS ANGELES, CALIF.
TORONTO, CANADA
MONTREAL, CANADA

Die Handler Lifts Truck

Lifting a giant fork truck is child's play for this mammoth die handler. Designed and built by Automatic Transportation Co., Chicago, it can lift up to 110,000 lb. It is equipped with two winches for handling 55-ton dies into and out of metalworking presses

(*Concluded from page* 115)

ity interest in Fort Duquesne Steel Co.

J&L Dedicates Texas Plant

Jones & Laughlin Steel Corp., Pittsburgh, dedicated its Container Division plant at Port Arthur, Tex., on Nov. 5.

Watson Industries Formed

Ervin J. Wilee and Clifford W. Hoye organized Watson Industries Inc.—moldings, stampings and wire products. Headquarters are at 7405 Lyndon Ave., Detroit 38, Mich.

Kyle & Co. Changes Hands

Pittsburgh - Des Moines Co., Pittsburgh, purchased Kyle & Co., Fresno, Calif., steel fabricator and distributor. Kyle has plants in Fresno, Stockton, Sacramento and El Monte, Calif.

Koppers Enters New Field

Koppers Co. Inc., Pittsburgh, purchased Turner & Haws Engineering Co. Inc., West Roxbury, Mass., maker of a special line of

"Maybe we'd better scrap some of our ideas about scrap?"

DO YOU think of your scrap in terms of material costs only? Actually it's the time and labor that have been wasted upon it that is really costly.

Accepting an arbitrary rejection rate as inevitable, is expensive and usually unnecessary. The solution is often so simple it can be easily overlooked.

This may be the solution

Cracks in parts are one main cause for scrapping. When these cracks are not discovered until after machining or at final inspection, time spent in processing the parts is a dead loss!

Inspection with Magnaflux' Methods finds all cracks—from whatever cause—at any stage of manufacture. By finding cracks early you can correct the cause before parts are run in quantity. Result: almost no time or money is wasted on defective parts.

Inspection with Magnaflux is fast and cheap—saves many times its trifling cost. Ask to have a Magnaflux engineer show you how it can cut *your* costs—or write for new booklet on LOWER MANUFACTURING COST.



MAGNAFLUX

MAGNAFLUX CORPORATION

MAGNAFLUX CORPORATION

7312 W. LAWRENCE AVENUE, CHICAGO 31, ILLINOIS

New York 36 • Pittsburgh 36 • Cleveland 15

Detroit 11 • Dallas 19 Los Angeles 58

MACHINABILITY INDEX 80-90*

PEARLITIC MALLEABLE CASTINGS

*B1112 STEEL = 100

Low machinability index of 80-90 (B1112 steel = 100) is probably reason enough to warrant serious consideration for your product.

But pearlitic malleable castings—from National—don't stop there. They have great ultimate strength . . . resist wear under heavy loads at high speeds . . . make excellent non-seizing bearings . . . can be air or liquid-quenched . . . can be smooth-finished.

Don't overlook the advantages of pearlitic malleable. For pearlitic malleable castings—from National—can often reduce manufacturing costs, weight and assembly time . . . can increase the sales potential of your product.

AA-1806

NATIONAL MALLEABLE AND STEEL CASTINGS COMPANY

Cleveland 6, Ohio

The Nation's largest independent producer of malleable and pearlitic malleable

filters for cleaning industrial g and gas. Operation of the pro erty will be under Koppers' Met Products Division at Baltimor manufacturer of electrostatic pr cipitators for cleaning industri gas.

Fruehauf Gets Mobilvan Right

Fruehauf Trailer Co., Detro has been granted exclusive man facturing and distribution righ for Clark Equipment Co.'s Mob van system, a method for tran porting large container shipmen of merchandise. The system based on the use of Clark fork li trucks designed to automatical lock a van or container secure to the bed of a railroad flatcar the chassis or flatbed of a trail or truck.

Union Malleable Expanding

Union Malleable Mfg. Co. cor pleted its new foundry at Ashlan O., the first phase of its planne $8-million plant expansion pr gram. The next step: A 55,000-s ft section to house the electr annealing and automatic galvani ing operations and machine sh facilities. It will be started ne year.

Topp Industries Builds

Topp Industries Inc., maker aircraft instrumentation, air-bor and ground-support systems, bu two plants at 5200 E. 102nd S Los Angeles, to triple productio capacity.

Yale & Towne Buys Plant

Yale & Towne Mfg. Co., Ne York, purchased a plant at Add son, Ill., to be added to the faci ties of its Powdered Metal Pro ucts Division, Franklin Park, I It will be devoted principally to t production of ferrite componen used by the manufacturers of r dio, television and other electron equipment. Transfer of Yale Towne's ferrite operations to t new plant will make available t greater production capacity nee ed to meet increasing demands the electronics industry.

The company opened a new sal and service center at its branch

66 Woodward Ave., Detroit 1, ch.

ys Columbite Property

Kennecott Copper Corp., New rk, has obtained 52 per cent terest in Tin & Associated Min- ls Ltd., a Nigerian company, the ner of a columbium mine and ncentrating plant. It has been oducing about 600,000 lb of co- mbite annually.

eem Expands on West Coast

U. S. Spring & Bumper Co., Los geles, changed its name to eem Automotive Co., a division Rheem Mfg. Co. The company ll continue to make parts for tomobile assembly plants and ll produce cultivator tools, high- y guard rails and allied lines. G. Fisher is vice president and neral manager of the division; M. Diltz, vice president-sales; W. Carrico, vice president- nufacturing.

ens West Coast Office

Robertshaw-Fulton Controls Co., eensburg, Pa., opened a western gional sales engineering office its Fielden Instrument Division 3101 Imperial Highway, Lyn- od, Calif. C. J. O'Lone will su- rvise the office.

airie Pipe To Build Plant

A $3.5-million plant to manu- cture steel pipe (from 4½ to 16) will be built on the outskirts Regina, Saskatchewan, by airie Pipe Co. Ltd., newly formed iliate of Fluor Corp. Ltd., Los geles. The plant, scheduled to in operation Apr. 1, 1956, will ve an annual capacity of more an 100,000 tons. Cal-Metal rp., Torrance, Calif., has been arded a contract to furnish all achinery and equipment.

ax Gets Furnace Rights

Ajax Engineering Corp., Tren- , N. J., has concluded an agree- nt with Otto Junger GmbH., mmersdorf, Germany, and Birlec d., Birmingham, England, for e development and marketing of

(*Please turn to page* 126)

pre-design
for product beauty
with NICKELOID
METALS
For functional parts and trim . . . pre-design planning with Nickeloid Metals pays off for sales-minded, cost-conscious manufacturers.
THESE FINE PRODUCTS WERE DESIGNED AROUND NICKELOID METALS
In the pre-design stage . . . before investing in tools and dies . . . consider pre-plated Nickeloid Metals. Take full advantage of their inspiring design potential and basic production savings, too. PRE-plated in uniform, quality-controlled finishes of chrome, nickel, copper or brass on base metals of steel, zinc, copper, brass and aluminum — Nickeloid Metals require no cleaning, plating, polishing. Just fabricate the parts and assemble. Eliminate 3 out of 5 basic manufacturing steps; save time, reduce costs, increase output.
MAR-NOT PROTECTION
To protect the brilliantly finished surface during drawing and forming operations, and in handling, Nickeloid Metals are available with MAR-NOT — a protective covering that affords absolute protection until final assembly; then may be peeled off. Write for full details.
SHEETS • COILS • STRIPS
NICKELOID METALS
SINCE 1898
AMERICAN NICKELOID CO.
PERU 1, ILLINOIS

extremely difficult job???



Hy-Draulic

Reg. U.S. Pat. Off.

. . . not for a hydraulic

planer and duplicator

Here's another complex machining job solved by using a Hydraulic Kopy-Kat, with a rotor generating Hydraulic Shaper-Planer.

The part is a blower and consists of two sections — a two lobe rotor and a four lobe gate. The helix angle of the rotor is approximately 32 degrees.

Hydraulic Drive is a natural for extremely difficult shaping, planing, slotting and duplicating. It produces accurate work with substantial savings in production time — often several hundred percent over other methods.

Ask a Rockford Machine Tool Co. representative for the latest facts on modern Hydraulic Shapers, Planers, Slotters, Shaper-Planers and Kopy-Kats.



ROCKFORD MACHINE TOOL CO.

2500 KISHWAUKEE STREET • ROCKFORD, ILLINOIS

Naturals
for materials handling should be engineered . . .

just as Mother Nature "engineered" the kangaroo . . .

and BUSCHMAN has pre-engineered conveyors to meet your every need

OVERHEAD CABLE CONVEYORS

ROLLER CONVEYORS

PORTABLE WHEEL CONVEYORS

PORTABLE POWERED BELT CONVEYORS

In conveyors there's a "natural" for every job . . . a type that is most efficient and economical for any given application.

The fact that Buschman designs and manufactures a *complete* line is your assurance of getting the one that will do *your* job best.

Portable wheel and roller . . . live roller . . . powered belt . . . apron . . . slat . . . overhead and table cable . . . as well as special conveyors are available from Buschman. Each type has been pre-engineered for minimum initial cost and to provide long, efficient service life.

Buschman materials handling specialists will assist in surveying your plant and will recommend the most economical and efficient conveyor for each operation. No obligation, of course.

Produce more . . . handle more . . . at lower cost . . . with an efficient conveyor system that meets your exact needs . . . a system "Better Built" by Buschman.

Write today for literature.

PRODUCE MORE . . . FOR LESS with Buschman Conveyors

C-222-EWB

THE E. W. BUSCHMAN COMPANY
4496 Clifton Avenue • Cincinnati 32, Ohio

Representatives in Principal Cities

Complete Conveyor Systems For All Types of Industries • Engineered • Manufactured • Installed

(*Concluded from page* 123)

the line frequency (60 cycle) co less induction melting furna Ajax officials say the furnace w be of particular interest to foun ries melting high-quality cast ir — in particular nodular cast ir chips and turnings of ferrous a nonferrous metals, including ma nesium.

Empire Steel Opens Plant

Empire Steel Corp. opened steel warehousing and fabricati plant at 4305 E. 60th Ave., Denve Officers of the firm are Alex En lander, president, and Mike Rubal vice president. Mr. Englander h been executive vice president a treasurer of Fabricators Steel Mfg. Corp., New York, affiliate Builders Structural Steel Cor Cleveland.

Fafnir Building Plant

Fafnir Bearing Co., New Britai Conn., is building a machining a heat-treating plant at Newingto Conn. The building will conta 160,000 sq ft of space, bringi Fafnir's manufacturing space the New Britain-Newington ar to 1.1 million sq ft. The buildi was designed and is being erect by Austin Co., Cleveland.

Walworth Buys Pipe Fabricato

Walworth Co., New York, a quired Southwest Fabricating Welding Co. Inc., Houston, pi fabricator, and will operate t property as a subsidiary. Wa worth makes valves and pipe f tings.

Union Metal To Expand

Union Metal Mfg. Co., Canto O., will spend more than $1 milli on plant expansion. A new buil ing will add 51,400 sq ft of man facturing floor space. Addition machinery and equipment will pr vide a 100 per cent increase steel tube manufacturing capaci More space will be devoted to t manufacture of aluminum pc products, which have become i creasingly important in the co pany's business. A new boil plant will be built and power f cilities will be expanded.

Technical Outlook

WATCHDOG TV—A television camera mounted in the foundation of Alcoa's 35,000-ton forging press at its Cleveland Works keeps an eye on off-center loads that might ruin the machine. The picture: A hydraulic mechanism which indicates eccentric loading, so the press operator can take prompt action.

VACUUM DEGASSING—National Research Corp. has acquired U. S. rights to the Bochumer Verein steel degassing process. It's adaptable to degassing in the ladle, or while pouring into the ingot molds. American steel companies are intrigued by its high-volume capabilities, and the low-hydrogen, more uniform metal it produces.

METAL POWDER FACTS—Sources for information on metal powders are contained in Data Sheet No. 4, "Standards, Specifications and References for Metal Powders and Metal Powder Products," published by the Metal Powder Association, New York.

GROWING INTEREST—Each month sees more companies asking for access to restricted data related to industrial uses of atomic energy. The AEC says there were 83 in September—highest since the permit program started in April. Holders of access permits need an "L" clearance to get restricted data classified as confidential, a "Q" clearance for that classified secret.

OLD TIMER—It's easy to forget the early plastics—vulcanized fiber, for instance. It weighs half as much as aluminum, is tough and resilient, can be machined and formed on typical metalworking equipment, can be had with a tensile strength of 12,000 psi. In case you've forgotten, it's the tough stuff so familiar in football helmets, shop containers and the salesman's sample case. Typical metalworking applications: Gears, washers, electrical insulation.

NEW PROCESS—Linde Air Products says a major project at its Speedway Laboratory will involve the discovery and development of new ways to make acetylene. The gas is used in the oxyacetylene flame for heating, cutting and welding metals.

TITANIUM PROGRESS—Conical dies are better than flat dies to extrude titanium bars, says Battelle Memorial Institute. A 130 degree die angle improves metal flow and surface finish. Best temperatures are the alpha-phase region for straight titanum and alpha-beta for Ti-3Mn; best lubricants contain graphite, moly-disulphide and mica. Promising die materials are titanium carbide, chromium carbide and cobalt-base alloys.

HELP—A Naval Research Laboratory report states that the high temperature, strength and ductility of cobalt-base alloys are increased by the addition of rare earths. Both as-cast and aged material are improved at all temperatures, with greatest benefit at 1500° F.

GREAT VERSATILITY—"In recognition of his great versatility in applying science to the metal industry," Alfred L. Boegehold was named the winner of the 1955 ASM gold medal. Among many contributions cited: The development of malleable and pearlitic malleable iron for heavy sections like crankshafts. Mr. Boegehold is assistant to the vice president in charge of the General Motors research staff.

alworking Outlook—p. 81 Market Outlook—p. 183



What Quality Control Did for Aero Supply

1. Tightened manufacturing, from incoming stock to outgoing product.
2. Reorganized plant maintenance.
3. Sparked the development of new tooling and inspection instruments.
4. Altered manufacturing methods and routing procedures.
5. Sharpened methods planning.
6. Revised accounting and budgeting procedures.
7. Gave the personnel department a new basis for promotions.
8. Provided the purchasing department with a guide for evaluating supplie
9. Induced suppliers to adopt quality control based on the Aero pattern.
10. Inspired a continuing educational program that has boosted company mora
11. Turned into a valuable sales promotion force.

QUALITY CONTROL:

Everybody in the Act

"WE STARTED with a better bolt, but we ended up with a better way of company life."

Strong words about a quality control program, but as you study the picture at Aero Supply Mfg. Co. Inc., you get the feeling that they ring true.

The Corry, Pa., producer of aircraft hardware began a quality control program for the most obvious of reasons: To reduce rejects. But the program refused to stay tied down. In three short years it has spread into almost every department.

Background—Even before 1952, the company had to conform to rigid quality standards set down by its prime customers, (aircraft manufacturers) and the ultimate user (in almost every case the military). To meet requirements, the company used only certified or approved processes in its heat treating, anodizing and plating steps and certified all employees working on Magnaflux or Zyglo inspections.

That wasn't enough. "What we wanted to do," says Walter Wotus, quality control supervisor, "was to implement these sporadic testings and inspections with an over-all quality control operation that would pinpoint and prevent defects, from reception of raw material all the way to final packing and shipping. To save time and money, we sought to integrate quality control right into the manufacturing process."

Stock Control — The procedure works out like this: Incoming shipments of coil stock are checked to insure absolute conformance with specifications and requirements. Physical and chemical reports accompany every supplier shipment, and, periodically, Aero double checks these through an independent laboratory.

Two samples are taken from each incoming coil and assigned to the inspection metallurgical laboratory. Here, they are rechecked for physical characteristics to make sure that tensile, hardness, shear, bend, decarburization and seam qualities meet specifications. Imperfect specimens are rejected at the beginning and returned to the manufacturer, so that the cannot bog down production sche ules.

Records — Information fro these checks is recorded on co trol forms and keyed to the co trol number which appears every carton of bolts Aero ship It provides a detailed history every lot produced and is used a running check to avoid reject

Once the laboratory-accept bolt stock begins moving throu the plant, other phases of the pr gram come into play. In the bo heading division, for example, fo kinds of inspection maintain co stant control over men, materia machines. They are:

1. First-piece inspection: T operator gets approval by patr inspectors for grain flow, crack dimensional characteristics befo production can begin.

2. Process inspection: To dete mine whether anything is amis the operator makes a dimension inspection every 15 minutes.

3. Patrol inspection: Quali control inspectors make a che once or twice an hour.

Control Chart—Results of the hree inspections are recorded by he operator and inspector on a rocess control chart attached to very machine. It lists 80 major easons for quality failure, includng oversize, off center, defective naterial, broken tool, burning and xposed winding.

4. Gateway Inspection. A final ampling of about 20 per cent of ll bolts by full-time inspectors sing Dodge and Roming double ampling tables takes place before naterial can leave one department or another.

Other Checks—This kind of conrol within a single department oes on through trimming, drillng, threading, heat treating, elecroplating and Magnaflux operaions. There also are special inpections and tests along the way. Juring electroplating, for example, very barrel or tank is checked by rop testing for plating thickness, nd threads for form and pitch iameter, using ring and roll nread gages.

When specifications require 100 er cent Magnaflux inspection, olt heads are dyed for identificaon. When there are more than n average number of defects, the ompany Magnafluxes each bolt.

Final inspection checks are ade for dimensional accuracy, lating thickness and finish. In ddition, control numbers and ockwell cards are co-ordinated to make sure nothing has gone astray during manufacture.

Branchout — So much for the quality control program itself. Equally important are the directions in which it has traveled. "We knew from the beginning," says the quality control foreman, "that this would work only if supervisors, foremen and the operators understood and approved their roles."

As of 1952, this was hardly the case. Foremen considered quality control an extra and unnecessary duty to be squeezed into already overcrowded schedules. Some operators found it complicated, confusing and impractical. Others thought it was a gestapo scheme to weed out inefficient workers.

Education — To disprove these charges, quality control launched a full-scale training program featuring courses, slide films, discussions, practice sessions and a pin ball machine that visually brought home to employees the twin concepts of probability and frequency distribution.

Every educational weapon was designed to prove four facts about quality control:

1. It creates a better product at a reduced cost.
2. It reduces inspection and maintenance costs.
3. It helps meet competition.
4. It aids the operator by showing him how to get more efficiency out of his machine, more money and responsibility out of his job.

"Once we proved that quality control helps, not hurts the worker," Mr. Wotus sums up, "half the battle was won."

Maintenance—But quality control still had a number of other objectives. Machines had to be repaired and maintained as well as inspected. Maintenance men were brought into the quality control act with discussions and visual aids.

Today, new maintenance employees are briefed on the importance of quality control. They are shown how operation of any machine they service affects over-all rejection rates. Like the machine operator and plant foreman, they attend regular training and refresher courses to improve their daily equipment inspections and repair techniques.

Instruments—From better machine maintenance to better inspection instruments was only one short step. This brought into the quality control picture a whole new covey of specialists, including instrument designers, machine designers, process and industrial engineers and a number of shop inspectors.

Together, they developed universal indicating-type gages that have saved thousands of dollars by eliminating product bottlenecks owing to the long delivery time of special gages.

Handling — With emphasis on the whole productive process, quality control people began to look at the steps between manufacturing procedures. This led to increased awareness of materials handling, since the precision of the company's products makes them especially susceptible to mutilation during movement.

Aero uses stacking containers for moves from one department to another. They allow full use of vertical storage space and protect partly finished or completed lots from damage.

Into Everything — Quality control procedures and attitudes have found a place in other departments. In methods, for instance, where new steps and routing procedures are planned, manufacturing processes were altered to meet quality requirements. In accounting, exhaustive defect prevention budgets were prepared and analyzed. In personnel, exceptional quality control records have been rewarded by rapid promotions. The effects are felt in purchasing and sales.

Quality control summaries are an excellent record of the performance of suppliers. Not only can the best vendors be selected by the purchasing agent, but the company can work with vendors on improving their methods and products. A number of suppliers have incorporated quality control steps of their own, built upon the Aero Supply model. Even the sales promotion department has used it to cement old client relationships and open up new sales avenues.



Oldsmobile bumper plating line

Three Ways To Plate a Bumper

Pontiac: Copper strike, copper plate, nickel strike, nickel plate, chromium plate with no intermediate polishing. (STEEL, Dec. 20, 1954, p. 78)

Chevrolet: Nickel strike, copper plate, nickel plate, buff, chromium plate. (STEEL, Oct. 3, 1955, p. 76)

Oldsmobile: Copper strike, copper plate, buff, copper flash, bright nickel plate, chromium plate, stress relieve (see below).

DIVERSITY is the rule for bumper plating in the GM family. Pontiac, Chevrolet and Oldsmobile go about it in different ways (see box).

Oldsmobile has added an unusual step: Heat treatment for stress relief. It is the last lap of a tremendous new plating line in the Saginaw street plant in Lansing, Mich.

To go back to the beginning, you have to look at bumper design.

Cell Type — Until the wrap-around style became popular, bumpers could be plated successfully while moving through a long tank. The wrap-around made conforming anodes necessary to get an even distribution of plate. In the long tanks, that didn't work out well.

The answer was selective cell-type plating. The bumpers could be racked horizontally. The anodes could be arranged on the sides of the tank where they wouldn't have to be bagged and wouldn't be affected by material settling to the bottom of the tank.

But a tremendous problem was posed. In the last two years, Oldsmobile's bumper requirements have jumped 90 per cent. How could slow-motion, cell-type plating and doubled production be made compatible?

Solution — Automation to the eyeballs was the answer. Hanson-VanWinkle-Munning Co., Matawan, N. J., came up with a plating system automatic from start to finish. It ties in with a mile-long conveyor system built by Jervis B. Webb Co., Detroit, to operate between the plating steps.

The handling system had to be unusually rugged. Each loaded plating rack weighs close to 1000 lb and holds 10 front or 14 rear bumpers. One rack moves through the system every 163 seconds.

Selective — Few cell-type systems have been designed which



Touchup and loading racks. From this point it's no-hands operation

will handle this sort of volume. Racks to be plated have to be deposited in an empty cell, by-passing others. Then each rack has to be picked up after a predetermined time, again by-passing. Such a system is complicated by the differing times racks remain in the plating cells (in this case, 1 hour in copper, 24½-minutes in nickel, 2½-minutes in chromium).

To get the production it wanted, Oldsmobile set up three plating machines. One has 24 copper plating cells; one has 10 nickel; the other, 3 chromium. Each machine has precleaning, plating and rinsing sections.

Load and Lift—Each section has its own elevator mechanism. Racks over the pretreatment and rinsing sections are raised and advanced simultaneously. Over the plating cells, they are individually and selectively handled.

Mechanical handling devices transfer the racks between conveyors and the plating machines. Even the buffing cycle between copper and nickel plating is completely automatic. There's no manual handling from the time the racks enter the copper line until they emerge from heat treating furnace.

Heat and Power—Heat treatment is primarily to prevent hydrogen embrittlement in the chromium layer. Bumpers are in the 550 °F oven for 30 minutes.

Each electrified cell in the line is supplied by an individual motor generator set. It takes well over 30 sets to supply the copper plating section of the line alone.

All controls for the conveyor system are housed in a room where a graphic panel shows traffic conditions. With the full picture in front of him, the operator can prevent jamups and keep all parts of the line busy.

How Oldsmobile Plates a Bumper

Polish	Cathodic clean
Inspect	Cold rinse
Load racks	Cold rinse
	Cathodic cyanide dip
Alkali wash	Cyanide copper flash
Cathodic clean	Cold rinse
Cold rinse	Bright nickel plate (24 minutes)
Hot rinse	Reclaim rinse
Acid etch	Cold rinse
Cold rinse	Hot rinse
Cold rinse	
Anodic clean	Cathodic clean
Cold rinse	Cold rinse
Acid dip	Cathodic acid dip
Cold rinse	Cold rinse
Cathodic cyanide dip	Warm rinse
Cyanide copper strike	Chromium plate (2½-minutes)
Reclaim rinse	Reclaim rinse
Copper plate (1 hour)	Reclaim rinse
Reclaim rinse	Cold rinse
Hot rinse	Hot rinse
Automatic buff	Stress relieve
Wash	

No. 19 in STEEL's Modern Heat Treating Series

Heat Treating Gray Iron

PART III

PEOPLE WHO USE castings have a bag of tricks to get the most in hardness and strength out of gray iron. In addition to the methods of surface hardening described last week (STEEL, Oct. 31, p. 76), there are through hardening and hot quenching techniques.

Through Hardening—It is possible to harden a casting throughout by oil or water quenching, if it is not too great in section. In castings of heavy cross section, only the outer layer may cool fast enough to produce a martensitic structure; the core cools to a pearlitic or similar structure.

Rate of cooling rather than temperature becomes the controlling factor in obtaining the right martensitic structure by quench hardening.

Range—Through hardening can be applied to a wider variety of gray irons than either flame or induction hardening. Even an iron containing no combined carbon may be hardened. In fact, castings may be rendered carbide free or ferritic by annealing for maximum machinability and then quenching to a martensitic structure to promote maximum wear resistance.

Although gray iron of almost any composition can be through hardened, low-silicon gray iron (under a maximum of 2 per cent) is best.

Austenizing—The first step is to heat the casting to 1550-1650°F, to form austenite, and to hold it at that temperature until the maximum amount of carbon has been dissolved. This may be done in a salt bath or other furnace.

The higher the casting is heated above the transformation range, the greater will be the amount of carbon absorbed in the austenite and the higher will be the hardness after quenching. In practice, temperatures from 50 to 100° F higher than the calculated transformation range are used to assure full austenization. Avoid excessively high temperatures; they increase the danger of distortion and cracking.

Speed—Heating should be slow through the lower temperature ranges. Above 1100 to 1200° F it may be as rapid as desired.

A good way to save time is to heat the casting slowly to about 1200° F in one furnace and then transfer it to a second furnace to bring it up to the hardening temperature rapidly. It should be held there long enough for it to be heated uniformly throughout. As little as 20 minutes per inch of section may prove sufficient.

Quenching—Choose a quenching medium which provides the critical cooling rate to the desired depth but does not extract heat too rapidly from the casting. Water is generally not satisfactory.

The usual medium is oil of high flame point. The least drastic is air. Unalloyed or low-alloy castings cannot usually be air-quenched, because the cooling rate is not sufficiently high to promote the formation of martensite. With irons of high alloy content, air quenching is frequently the most desirable method.

Castings of nonuniform section should be quenched so that the heavier section enters the bath first. Stirring the bath improves quenching efficiency. The casting should be removed as soon as it reaches temperatures between 300

and 500°F and immediately tempered.

Tempering—Tempering temperatures vary from 300 to 1020°F, depending on the composition of the gray iron and the final properties desired. Choose a tempering temperature higher than the service temperature. The casting should be held at the tempering temperature for about 1 hour per inch of thickest section.

Maximum hardness is obtained by tempering between 300 and 400° F for an unalloyed, low-silicon gray iron.

Improvement—Gray irons that have been quenched and tempered usually show wear resistance about five times as great as that of pearlitic gray irons. With temperatures of over 700°F, the wear resistance of unalloyed irons decreases more sharply than that of alloyed irons. Gray irons with low carbon equivalent, after quenching and tempering, show more wear resistance than irons containing higher percentages of carbon and silicon.

Tempering also improves tensile strength. For unalloyed gray iron, maximum strength is obtained by tempering in the range of 570 to 700°F; for alloyed irons temperatures of 750 to 930°F are necessary. A through hardened and tempered gray iron also tends to have improved usable strength and dimensional stability.

Alloy Effects—Tempering temperatures in the neighborhood of 700°F increase the impact resistance of hardened, low-silicon, unalloyed gray iron. If alloying elements are present in any quantity, higher temperatures may be necessary.

High tempering temperatures, such as 1020°F, improve the machinability of quenched gray iron, but with comparable loss in wear resistance and hardness. It is better to machine castings in the as-cast condition before heat treating, if practical.

More Effects—Carbon and silicon in amounts over those necessary to keep the iron gray tend to decrease the apparent hardness but not the microhardness. Manganese in excessive amounts tends to decrease tensile strength of quenched gray iron (but less than the decrease in strength in as-cast gray irons of similar composition). Tempering of manganese irons reduces hardness but increases tensile strength.

Chromium increases the hardness of quench-hardened gray irons, especially if the higher tempering temperatures are employed. Molybdenum as an alloying element can also produce quench-hardened gray irons of high tensile strength and hardness. In one commercial molybdenum gray iron, minimum hardness of 550 Brinell is regular.

Applications — Applications of quench-hardened gray iron have been numerous, particularly where high wear resistance and strength, combined with machinability and castability, are required. Typical are: Cams and cam rollers, cylinder liners, dies and punches, electric motor frames, gages, gears, machine tool parts, pump bodies and parts, rim and ram tips, rolls, textile machine parts, valve guides and seats, worms and shafts.

Hot Quenching—Isothermal heat treatment, or hot quenching, is a process of quenching from a temperature above the critical range into a bath of salt, oil or molten lead held well above room temperature.

Hardness, wear resistance and toughness of the gray iron may be improved considerably over the as-cast condition. This method is particularly suited to gray iron. It minimizes the drastic stresses set up by conventional quenching.

Hot quenching can be subdivided into two different operations, austempering and martempering.

Austempering — In austempering, the microstructure of the gray iron matrix is essentially



Effect of heat treatment on a low-silicon gray iron

Effect of structure on hardness of a hot quenched gray iron





Typical austempering cycle for gray iron



Typical martempering cycle for gray iron

bainite. The iron is quenched from a temperature above the transformation range into a salt, lead or oil bath and held there at constant temperature until transformation to bainite is complete.

In all hot quenching, temperatures to which the casting must be heated, and holding times at that temperature prior to quenching, correspond to the temperatures and times used in hardening. (Between 1400 and 1650° F, held for 20 minutes per inch of thickness after reaching temperature.)

Temperature — The salt bath should be held between 450 to 800°F, depending on the alloy content and the desired mechanical properties. When high hardness and wear resistance are the ultimate aims, quench temperatures are usually held within the lower portion of the range, between 450 to 550°F.

The factors that determine the holding time for maximum transformation to bainite are the temperature and the composition of the iron. The influence of austenite grain size is usually small, but under certain conditions may become significant. The influence of iron composition on the holding time may be considerable.

Alloys — Additions, such as nickel, chromium and molybdenum, increase the time required for transformation. Good procedure to determine the holding time in a practical case would be: 1. Determine approximate quench bath temperature on the basis of the desired final hardness. 2. Test some specimens at different holding times and select the minimum time required for obtaining the desired properties.

Section size influences holding time in the quench bath: Large sections must be held for longer periods than small ones. Thickness of the section and the shape of the piece may limit the use of austempering, as speed of cooling must be fast enough to avoid any transformation until the casting reaches the temperature of the bath.

Martempering — Martempering is used to produce martensite without developing the high stresses that usually accompany its formation. It is similar to conventional quench hardening, but distortion is virtually eliminated. Nevertheless, a considerable portion of the innate brittleness of the martensite remains, and if this must be removed, the casting can be tempered.

The casting is quenched from above the transformation range into a salt, oil or lead bath; held at a temperature slightly above the martensite formation range (about 400-500°F for most unalloyed irons) only until the casting has reached the temperature of the bath; and cooled to room temperature.

Results—If a wholly martensitic structure is desired, the casting should be held only long enough in the hot quench bath to let it adjust to nearly uniform temperature through the section. Thus, the size and shape of the casting control results.

In most cases, isothermal heat treatment gives castings higher toughness than those quenched in oil or water and tempered to equal hardness. Wear resistance of hot-quenched castings also compares favorably with those quenched and tempered. In most irons, the hardness obtained by isothermal transformation is somewhat less than that obtained by quenching and tempering at the same temperature.

Benefits — Maximum hardness obtained by austempering is usually less than that obtained by martempering, although this difference may be mostly canceled during the tempering often specified after martempering.

Isothermal heat treatment of gray cast iron may improve the physical properties of such products as piston rings, brake drums, brake shoes and crankshafts. Hot quenching of gray iron holds considerable promise for those cases in which structural parts of intricate design require high wear resistance and strength.

• *Extra copies of this article are available in quantities from one to three until supply is exhausted. Write Editorial Service,* STEEL, *Penton Bldg., Cleveland 13, O.*

Office with concealed piping, only the heads showing

REVERE Extruded Shapes

in dry pendent sprinkler heads lessen machining, save money

Some 16 years ago the Viking Corporation, Hastings, Michigan, decided to find a way to put sprinkler piping for dry pipe systems above the finished ceiling, leaving only the sprinkler heads visible. This meant designing a sprinkler head which would be free of water except when in use. Thus there would be no drainage problem, and no chance of freezing. The dry pendent sprinkler head as finally developed extends into the sprinkler pipe, where a bronze cap keeps the entire valve waterless. When a fire occurs the usual fusible element melts, two struts drop, releasing the cap and permitting water to flow.

In the original experimental work, the two struts were machined out of solid brass bar. This took time and involved the generation of a considerable amount of scrap, since each strut has four deep fins. Once the idea had proved itself, Viking came to Revere for extruded shapes, in order to save both machining and metal. So much time has elapsed since the original machining of the bar that comparative cost figures would be meaningless, but it is evident to Viking, and to everybody familiar with extruded shapes, that the saving is substantial.

Cross section of Viking Dry Pendent Sprinkler Head, and cutaway view



Outline of the two shapes supplied by Revere

"The Revere Four-Way Service" is a 16mm. sound motion picture in color, educational and informative. If you haven't seen it, write nearest Revere Sales Office.

REVERE

COPPER AND BRASS INCORPORATED

Founded by Paul Revere in 1801

230 Park Avenue, New York 17, N. Y.

• • •

Mills: Baltimore, Md.; Brooklyn, N. Y.; Chicago, Clinton and Joliet, Ill.; Detroit, Mich.; Los Angeles and Riverside Calif.; New Bedford, Mass.; Newport, Ark.; Rome, N. Y. Sales Offices in Principal Cities, Distributors Everywhere.



Fig. 1. Structure diagram for 0.00 per cent nickel, 0.40 per cent nitrogen steel after heating for 1 hour at temperature and water quenching

New austenitic stainless can be made without nickel. Details of the process and application were revealed at Cleveland meeting of American Iron & Steel Institute

By Dr. D. J. CARNEY
Superintendent, No. 2 Electric Furnace Dept.
South Works, U. S. Steel Corp.
Chicago

High-Nitrogen Steels: New Stainless Family

ALTHOUGH it contains little or no nickel, a new chromium-manganese steel is completely austenitic at temperatures to 2300° F. The key to its stability at high temperatures is a nitrogen content more than double previous limits.

The Cr-Mn-N steel is a new stainless steel with special applications, not merely a substitute for presently used grades during periods of nickel shortage.

Objective — High-nitrogen steel is the result of a U. S. Steel study aimed at conserving nickel. The objective was to produce a nickel-free, austenitic steel with mechanical properties similar to those of AISI type 301 at a minimum chromium content of 17 per cent.

Because of past rolling difficulties with other substitute alloys which contained delta ferrite at rolling temperatures, it was necessary that the new alloy be free of ferrite at temperatures as high as 2300° F.

Effect of Nitrogen — We knew that nitrogen was a powerful austenite stabilizer, but its use in stainless steel has been limited to 0.25 per cent or less. Greater nitrogen content was supposed to result in bleeding ingots.

We found that by adjusting the chemical composition, particularly the combined chromium and manganese contents, we could produce sound ingots with nitrogen contents as high as 0.65 per cent.

First Phase — This opened the door to an unexplored area for reducing nickel content. The first step was to vary the chromium, manganese and nitrogen contents of the steel at low carbon and nickel levels to establish the de-

Corrosion Resistance to Nitric Acid*

Grade	Penetration In. per month
17-7	0.0010
Cr-Mn-N	0.0034
17 per cent Cr	0.0040
16-1-17	0.0050

*Boiling 65 per cent nitric acid. All steels were annealed for 30 minutes at 1950° F

STEEL FORGINGS by MESTA

for HIGH PRESSURE and HIGH TEMPERATURE PIPING

custom made to your echanical and metallurgical pecifications

PIPE

TEES

Y'S

LVE BODIES

LATERALS

CROSSES

ELLS



Chrome Molybdenum Alloy
ipe forged, machined, rigidly
ted and tested to comply with
er and code specifications.

Ultrasonic Testing with a Reflectoscope is one phase of quality control which provides confident service in High Pressure and High Temperature Piping Systems using Mesta Forged Steel Pipe and Fittings.

MESTA FACILITIES *for Forged Steel Piping*

Electric Steel and Open Hearth Furnaces
Forging Presses • Heavy Duty Machine Tools
Chemical • Metallurgical • Physical Laboratories
Complete Testing Equipment

ROLLING MILLS • ROLLS • FORGINGS • HEAVY DUTY TOOLS

MESTA MACHINE COMPANY

PITTSBURGH, PENNSYLVANIA



Fig. 2. Structure diagram for 0.00 per cent nickel, 0.25-0.45 per cent nitrogen steels after heating for 1 hour at 2300°F and water quenching



Fig. 3. Structure diagram for 1.00 per cent nickel, 0.25-0.45 per cent nitrogen steels after heating for 1 hour at 2300°F and water quenching



Fig. 4. Structure diagram for 2.00 per cent nickel, 0.25-0.45 per cent nitrogen steels after heating for 1 hour at 2300°F and water quenching



Fig. 5. Structure diagram for 3.00 per cent nickel, 0.25-0.45 per cent nitrogen steels after heating for 1 hour at 2300°F and water quenching

gree of the austenite stability at common rolling temperatures.

This was done at 0, 1, 2 and 3 per cent nickel levels. We concentrated on the zero nickel level to determine if it were feasible to produce a completely austenitic stainless steel with 17 per cent chromium by varying the manganese and nitrogen contents. For good corrosion resistance, the carbon content was established at 0.12 per cent maximum.

Results—Fig. 1 illustrates some of the important findings. The base chemical composition used in this study is listed on the chart. The chromium content varied from 15 to 21 per cent and the manganese from 12 to 19 per cent.

The figure reveals that it is possible to produce a structure, which is completely austenitic at temperatures as high as 2300° F, with a chromium level of 17 per cent and a residual nickel content, by use of 0.40 per cent nitrogen and 15 per cent manganese.

The austenite field decreases and ferrite forms as the temperature is raised. For all steels studied, we found that increased manganese contents above a certain minimum level tended to promote ferrite rather than austenite at high temperatures.

Nickel Level—Figs. 2, 3, 4 and 5 show the austenite phase boundary at 0, 1, 2 and 3 per cent nicke levels, with nitrogen content varying from 0.25 to 0.45 per cent These figures show the powerfu influence of nitrogen and the rel ative influence of nickel on aus tenite stability at 2300° F. Fo example, at the 3 per cent nicke level, the chromium content coul be raised to over 20 per cent b using 0.45 per cent nitrogen an still retain a completely austeniti structure at 2300° F.

At each nickel level there was minimum manganese level for given chromium and nitrogen con tent. Below this point, nitroge evolution occurred during solidifi cation. Example: At the 0 per cen


10 cold-finished
JALCASE
grades
J&L STEEL
MEMORANDUM
Here's another new book by J&L...you'll want it for your reference material
NOTE:
Data on J&L's Jalcase include information on the superior machinability of this cold finished steel. Both speed of machining and the amount of metal removed per revolution can be substantially higher than with other steels of approximately the same mechanical properties.
Jalcase also gives longer tool life between grindings. In many cases the machined surface of a Jalcase part requires no subsequent finishing operation.

J&L STEEL

ou can help us place a copy of this *new* book in your ands. Please give us your name and address. We'll o the rest. It will be *mailed* without cost to you—no trusion on your time.

Jones & Laughlin Steel Corp., Dept. 404
3 Gateway Center, Pittsburgh 30, Pa.

Please send me a copy of your new Booklet, "10 Cold Finished JALCASE Grades."

NAME_____

TITLE_____

COMPANY_____

ADDRESS_____

CITY _____ ZONE_____ STATE_____

Jones & Laughlin
STEEL CORPORATION — *Pittsburgh*

(Advertisement)

3 tests show butyl rubber

Extra protection against

OZONE RESISTANCE



In standard ozone-chamber test, Type AB insulat showed no injury after 72 hours in 0.025-0.030% oz concentration . . . 24 times longer than required by oil b and butyl specifications.

MOISTURE ABSORPTION



For the mechanical moisture absorption test, the in dustry has regarded 15 milligrams increase in weigh per square inch of exposed surface, after 7 days immersion at 70C, as a criterion for satisfactor moisture resistance. Type AB easily meets tha requirement—in fact, after 28 days of immersio it is only a fraction above the 7-day requirement

OPERATING TEMPERATURE



Anaconda recommends Type AB fo operation at 85C maximum operating temperature. Industry standards rec ommend 70C for oil base. That means, as the graph shows, Type AB's cur rent-carrying capacity exceeds oil base specifications by 22%.

nsulated Durasheath* Cable has

ozone, heat and moisture

naconda exclusive Type AB butyl rubber insulation resists

zone far longer than needed to prove its high ozone

esistance . . . absorbs far less moisture . . . has 22%

ore current-carrying capacity.

Standards are set up for your protection—but most standards state minimum requirements.

Anaconda's Type AB butyl-insulated cable performance exceeds its own specification requirements and goes far beyond industry requirements—gives you an extra margin of protection against the major enemies of long cable life.

Butyl rubber has *inherent* resistance to ozone, heat and moisture. Thus Anaconda has been able to concentrate on the development and improvement of other desirable properties.

The pay-off is in your operations—in longer cable life . . . in less maintenance . . . in lower over-all operating costs. The Man from Anaconda will be glad to give you full details about Type AB-insulated Durasheath and other Type AB-insulated high-voltage cable. Why not call him today? Or for more information, write Anaconda Wire & Cable Company, 25 Broadway, New York 4, New York.

*Reg. U. S. Pat. Off.

55363

PIONEER IN BUTYL INSULATION **ANACONDA®**



Fig. 6. Effect of cold reduction on the mechanical properties of sheet product of a commercial 7-ton heat of 0.00 per cent nickel, Cr-Mn-N steel compared with a typical AISI type 301 stainless steel

nickel, 15 per cent chromium, 0.45 per cent nitrogen level, bleeding began to occur at 14.5 to 15.0 per cent manganese.

The increase in ferrite generally was gradual as the composition passed below the austenite phase boundary lines shown in the figures. Thus, in some cases, the rollability may be satisfactory with a chemical composition somewhat below the phase boundary lines shown in the accompanying chart

Microstructure—Tests were ma on 26-lb induction furnace hea cast into ingots 3½-in. in diamet and 18-in. tall. Sections we sliced from the top to investiga gas porosity and to determine t microstructure of cast ingots. T balance of each ingot was heat and hammer forged to roun about 1 in. in diameter, or to ¼ 3-in. flats.

Samples were cut from t forged sections to determine t microstructure, primarily t amount of ferrite, in the as-forg and in the heat-treated condition

Test Temperatures—The sampl were heated in a laboratory fu nace to temperatures within t 1900-2400° F range for 1 to hours and water quenched. Aft quenching, samples were section and polished metallographically.

The amount of ferrite was d termined for each sample eith magnetically or microscopicall The correlation between the micr scopic and magnetic ratings f ferrite was good (±0.5 per ce at a 5 per cent ferrite level).

Most of the steels nitrided rapi ly when heated in air above 200 F. Nitrided areas were eliminate in rating samples for ferrit About 300 laboratory heats wit varying chemical compositio were produced and tested.

Use-Properties of Cr-Mn-N Steels

HIGH-NITROGEN STEELS combine high yield strength with high ductility.

Yield-tensile ratio, although much higher than type 301, increases with increasing cold reduction at a rate similar to 301 (Fig. 6). Annealed Cr-Mn-N steel has a yield strength double that of the 17-7 type steels with the same elongation value.

Cold Working—A 10 per cent cold reduction of the Cr-Mn-N steels gives physical properties equal to that of type 301 after a 25 per cent cold reduction. The resultant ductility is markedly higher in the new steels. Bending and cold forming properties are good.

These properties can be produced over a wide range of manganese and nickel contents as long as the nitrogen is maintained at a relatively high level.

Test—One 7-ton, basic arc furnace heat, which contained no added nickel, was poured into a 75 x 35 x 20-in. ingot and rolled into 4 x 30-in. slabs.

The degree of chemical segregation observed in the as-rolled was not excessive or harmful for most applications. The macroetch quality of the slabs was satisfactory and microscopic examination revealed a completely austenitic structure in the as-rolled condition.

The slabs were rolled on a continuous 80-in. ho strip mill into 0.125-in. thick strip. This strip (i the form of coils) was annealed, pickled and cold re duced to develop mechanical property data.

Other Properties—Corrosion and high-temperatur properties appear to be satisfactory.

Small sheet samples of the steels were welded an tested for corrosion resistance in dilute sulphuri acid after severe bending. As long as the carbo content was below 0.12 per cent, no evidence of in tergranular corrosion was found in the heat-affecte weld zones.

Nitric Acid Test—In a concentrated nitric acid at mosphere, the new steels are not as satisfactory a the high-nickel steels (see table on page 138). The are better than 16-1-17 (15.5 per cent Cr, 16 per cen Mn, 1 per cent Ni and 0.15 per cent N) and the 1 per cent Cr steels.

Welding tests demonstrate that the new steels ma be welded as satisfactorily as 18-8 although weldin conditions may have to be modified. High tempera ture strength at 1200°F may be as good or bette than AISI type 347 for high-temperature service.

ars are broached two at a time. Gage check (right) keeps part within tolerance of 008 in. on the involute form. Next operation is shaving

Broaching with a Twist

Broaches are pulled up through idler gear to cut internal teeth. Guide bars control broach twist to cut the helical involute form. Tolerance is 0.0008 in. on the involute

DETROIT automotive supplier broaching internal gear teeth in reverse idler gear at the rate of pieces an hour. The operation is automatic; all the operator to do is keep the magazines ded.

The helical internal involute r is 14 pitch. Broaching fines the ID concentric with the ch diameter of the involute th and maintains pitch diamr concentric with the OD with limits. After broaching, the th are shaved, removing 0.001 on a side.

Cycle—The operator loads workces in two magazines and starts machine cycle. Two parts feed the slide and are transferred broaching position. The aches move up through the parts, engaging the broach pullers, which pull them through, cutting the helical involute teeth from the solid stock.

When the stroke is finished, the slide moves the parts out and ejects them below. After the broaches return, the slide moves two more parts up from the magazines and the cycle repeats.

Machine—The job is done on a vertical hydraulic internal pull-up broaching machine with two-station helical drive. Two lead bars, 3¾-in. in diameter, drive the broach pullers through a gear train. The bars operate independently, so it's possible to use the machine for broaching two parts of different leads.

The hydraulically operated retriever unit, engaging the broach rear pilot is designed to follow up throughout the entire broaching stroke, so the broaches are supported at the rear pilot until the last broaching tooth has passed through the workpiece. The unit remains in the up position after the broach rear pilot is disengaged at the end of the broaching stroke. It stays in this position ready to receive the broach pilot for the return stroke of the slide.

In normal production, the machine, built by American Broach & Machine Co., division of Sundstrand Machine Tool Co., Ann Arbor, Mich., produces 140 pieces an hour at 100 per cent efficiency, using a broaching speed of 17 fpm. At full speed (22 fpm), the machine turns out about 200 pieces an hour.



Left: Reciprocating air compressor

Below: Garlock 809 Floating Metal Packing split-case design

For air compressors, users report

GARLOCK SPLIT-CASE METAL PACKINGS

have 2 big advantages



1. **LONG, TROUBLE-FREE LIFE.** Minimum of 7 years with proper lubrication.

2. **CAN BE INSTALLED *WITHOUT* DISCONNECTING THE ROD.** Downtime is reduced to a minimum.

You can eliminate the cost of frequent packing replacements and unnecessary downtime by installing Garlock split-case metal packings on your reciprocating air compressors. Service reports show that these Garlock metal packings have given 15 years and more of trouble free service with a minimum of rod wear.

For complete information, call your Garlock representative or write today for Brochure 3889.

THE GARLOCK PACKING COMPANY, PALMYRA, N. Y.

Sales Offices and Warehouses: Baltimore, Birmingham, Boston, Buffalo, Chicago, Cincinnati, Cleveland, Denver, Detroit, Houston, Los Angeles, New Orleans, New York City, Palmyra (N.Y.), Philadelphia, Pittsburgh, Portland (Ore.), Salt Lake City, San Francisco, St. Louis, Seattle, Spokane, Tulsa

In Canada: The Garlock Packing Company of Canada Ltd., Toronto, Ont.

GARLOCK

PACKINGS, GASKETS, OIL SEALS,

MECHANICAL SEALS, RUBBER EXPANSION JOINTS

Watchdog Televisio

It's on lookout for off-cen loads which might mass 35,000-ton forging press

A TELEVISION CAMERA is third eye of the operator who c trols the 35,000-ton forging pr in the Air Force's heavy pr plant at Alcoa's Cleveland wor

The camera is on the lookout off-center loads which might w against the accuracy of the m sive press or even ruin it.

Deflection — The complica shape of a forging sometim causes eccentric loading of up and lower platens. A limit amount of eccentricity has b compensated for. The degree of flection must be measured by stretching of huge tie rods, whi hold the press within safe op ating limits. Such distortion is flected in the four hydraulic c inders at each corner.

Small hydraulic lines conn each cylinder to the mechani viewed by the TV camera. It plicates in miniature the observ differences.

DIAMOND GAGE AND CAMERA
. . . receiver is at control station

What Operator Sees—When t press is centrally loaded, a bea of light is focused in the center a diamond-shaped gage viewed the camera. If loading is off ce ter, the beam moves from the ce ter toward a border of the diamon disclosing the location of the lo center. Noting this movement, t press operator can take correcti action.

Should he fail to act quick enough, the light touching t boundary of the diamond sha automatically takes control fro the operator, stopping all mov ment before the press can be da aged.

Heavy-Duty Tire

Of one-piece forged steel, this concrete mixer drum tire gets weighty service

A CRITICAL COMPONENT of truck concrete mixers is the steel tire on which the drum rotates. Mounted at the rear of the mixer unit, the tire has to withstand shifting weights of up to 40,000 lb without cracking loose from the drum shell, losing concentricity or developing flat spots.

Functions — The tire performs three vital functions on the mixer. It stabilizes the drum; it transmits the drum load to the supporting rollers; and it provides the support for one end of the drum.

Tires for mixers made by Blaw-Knox Co., Pittsburgh, are forged under closely controlled conditions at the Standard Steel Works Division of Baldwin-Lima-Hamilton Corp., Burnham, Pa. The high-carbon steel rings are 51½-in. in diameter, 3 in. wide, 1½-in. thick and weigh over 200 lb. They are hot roll forged to impart tough physical properties and then rough machined.

FORGED STEEL TIRE
. . . is welded to cone section of drum

Fabrication—The tires are assembled to the mixer drums in a special welding fixture (see photo). First, the tire is slipped over the cone of the drum and tack welded. It is finish welded by hand, using a low-hydrogen electrode. The roller track is finish machined on a 5-ft boring mill.

The drum itself is high-strength, low-alloy steel, which is abrasion resistant to withstand the punishment meted out by sand and gravel. The rollers on which the tire and drum rotate are of SAE 1045 steel, machined and flame hardened.

Whatever your problem is in **Wire...**

Thousands of wire applications in over a half century—involving virtually every kind of a wire problem—that's the experience and background we offer you in solving *your* special wire problems. We can supply wire from almost the size of a human hair, through 9/16" diameter for metal fasteners . . . round wire or wire in special shapes, practically any size, temper, finish and analysis in low carbon and medium low carbon steels. We may have a valuable case history that parallels your own special problem. Fill out and return the coupon for full details of Continental's Wire Service. We are eager to work with you.


Coil Binding Wire


Preformed Staple Wire

Wire for Milk Bottle Carriers

Florist Wire

Wire Bales for Buckets, Pails, etc.

Wire for Toy Wheels

Standard and Special Wire Shapes

Fill out and mail today

Gentlemen: Please give us without obligation complete details of your special wire service.

NAME_____ TITLE_____

FIRM_____

ADDRESS_____

CITY_____ STATE_____

CONTINENTAL
STEEL CORPORATION · KOKOMO, INDIANA

PRODUCERS OF: Manufacturer's Wire in many sizes, shapes, tempers, and finishes, including Galvanized, KOKOTE, Flame-Sealed, Coppered, Tinned, Annealed, Liquor Finished, Bright, and special wire. ALSO Coated and Uncoated Steel Sheets, Nails, Continental Chain Link Fence, and other products.

SHARE IN

GEORGIA'S GOLDEN AGE



ARE YOU IN THE STEEL BUSINESS?

Whatever You Make...Whatever You Sell...

...you, too, will find that it's good business to produce in Georgia. Over 7100 manufacturers, including many of America's greatest industrial names, have already staked their claims to share in Georgia's Golden Age. Georgia—scene of America's first gold rush in 1828, today offers many nearby, growing consumer markets to sales-minded industries...

Open For Business Every Day In The Year

Even the weather is on your side in Georgia, where every day is production day. Industry is on the move to Georgia... with an amazing array of natural and physical resources, readily accessible and in abundant supply. Superb transportation—plus a liberal pool of intelligent workers make it easy to produce and move goods *fast!*

Get the facts from Scott Candler, Secretary—Dept. 20

GEORGIA DEPT. OF COMMERCE

SCOTT CANDLER, SECRETARY • 100 STATE CAPITOL • ATLANTA, GEORGIA



Schematic crane layout at Danly Machine Specialties Inc.

Precision Handling Speeds Press Building

OVERHEAD CRANES work three shifts a day, six days a week, moving king-size press components at Danly Machine Specialties Inc., Chicago.

Danly presses, even the largest ones, are completely assembled and tested before shipment. This saves valuable installation and adjustment time for buyers, but it adds to the press builder's handling problem.

Coverage—Weldments and subassemblies weighing many tons constantly move between the fabricating and machining areas of the big plant (five connected buildings). Backbone of the materials handling system, which covers the entire plant, are nine Whiting cranes.

These cranes are responsible for almost all inter-building handling. Crane runways extend from one building into another, making it possible to transfer lifts from building to building without intermediate handling.

Setup—In building 1, heavy steel plate is cut and welded. Shot-blast cleaning and stress-relieving of weldments are done in building 2. Buildings 4 and 5 are machining areas. All weldments and subassemblies go to buildings 2 and 3 for final assembly and testing.

Because its press building is so dependent upon the handling system, Danly takes good care of its cranes. They are inspected each week. Necessary cleaning and lubrication are done, and electrical parts and contacts are replaced according to schedule.

A 50-ton crane in building 2 carries press to building 3. At crane transfer point, where two buildings connect, another 50-ton crane will pick up press and take it to final assembly area



A 45-ton weldment on crane in building 2. Another crane is standing by in building 1 to pick up the part. Note how crane rails in building 1 extend into building 2



A 19½-ton weldment is turned over with a 50-ton crane and a 10-ton auxiliary hoist

REPUBLIC MAKES IT EASY TO

One call to your Republic Bolt and Nut Distributor gets all the fasteners you need for assembly and maintenance work. There's no shopping around to get the types and sizes you need. There's no time lost. Paper work is reduced. One order, one invoice, one shipment covers everything.

And even though your distributor might be temporarily out of a particular item you require, he can get it for you in a hurry. Republic's Bolt and Nut Division backs him with one of industry's largest stocks of headed and threaded products. More than 20,000 standard types and sizes of fasteners are made and stocked by Republic. Everything from machine bolts, cap screws, hot and cold punched nuts to rivets, track bolts, alloy studs, sheet metal screws.

In addition, Republic produces over 8,000 special types and sizes of fasteners—like "Nylok" Nuts, high-strength bolts, mine roof bolts.

You're getting quality in every sense of the word when you buy Republic Fasteners. Republic controls quality at every stage of production—from raw materials to finished fastener. Republic uses its own ore, makes its own steel (over 50 analyses of carbon, alloy and stainless), employs the most modern machines and procedures.

You can depend on Republic Fasteners for uniformity, ease of application, long service life, quality. Quick delivery, too.

Contact your industrial distributor. Or mail the coupon for additional information.

REPUBLIC STEEL

World's Widest Range of Standard Steels and Steel Products

Republic also makes it easy to get...



CHAIN FOR EVERY INDUSTRIAL REQUIREMENT. Republic's Round Chain Division offers a complete line of welded and weldless chain, chain slings—plus every type of fitting, attachment and accessory. Strategic location of Republic Chain plants and warehouses assures you of prompt delivery through your Republic Distributor.

COLD FINISHED STEEL BARS AND SHAFTING for steel parts production. Republic's Union Drawn Division, leading producer of cold drawn steels, supplies rounds, squares, hexes, flats, special sections and precision shafting in all standard and special carbon, alloy and stainless analyses. Your Union Drawn Distributor will deliver one foot, one bar or a truckload.

MATERIALS HANDLING EQUIPMENT to meet you specific requirements. The PB-120-T Box and Skid Units, shown above, are only one of many types manufactured by Republic's Pressed Steel Division. They can be adapted to the needs of any industry. Republic Materials Handling Equipment is sold through dealers located in principal cities from coast to coast.

GET THE FASTENERS YOU NEED

REPUBLIC STEEL CORPORATION
3120 East 45th Street,
Cleveland 27, Ohio

REPUBLIC STEEL

Please send more information on:

- ☐ Fasteners
- ☐ Chain
- ☐ Cold Finished Bars and Shafting
- ☐ Materials Handling Equipment

Name_____ Title_____

Company_____

Address_____

City_____ Zone____ State_____

K-3542


FOR ECONOMY IN MANY SEVERE SERVICES . . . it's hard to beat Shenango centrifugally cast parts of Meehanite Metal. These assembled rolls with steel journals are typical, long-lived examples. The combination of Shenango centrifugal casting and Meehanite Metal means pressure-dense grain for a smoother finish, less waste, greater strength and superior wear resistance. Porosity, sand inclusions, blow holes and other troublesome defects are a problem of the past. For informative bulletins on Shenango centrifugally cast parts—rough, semi- or finish-machined, ferrous or non-ferrous — write to: Shenango-Penn Mold Company, Centrifugal Castings Division, Dover, Ohio (Executive Offices: Pittsburgh, Pa.).
SHENANGO
CENTRIFUGAL CASTINGS
COPPER, TIN, LEAD, ZINC BRONZES • MONEL METAL
ALUMINUM AND MANGANESE BRONZES • NI-RESIST • MEEHANITE METAL

Tip for Diecasting

Made of beryllium-copper, a plunger tip has outlasted 10 previously used tips

A BERYLLIUM-COPPER plunger tip on a B & T, 450-ton, cold-chamber diecasting machine is still in good condition after more than 51,000 cycles.

Ohio Die Casting Co., Columbus, O., is using the tip for such jobs as forming locknuts for the plumbing industry from molten aluminum (1200°F) at the rate of 150 to 160 cycles an hour.

Dimensions—The tip is 4 in. long and 2 in. in diameter. It is made of Berylco No. 10, supplied by the Beryllium Corp., Reading, Pa. The tip was hot rolled, annealed, turned and heat treated.

The beryllium-copper tip permits the Columbus firm to use 0.0005-in. clearance between tip and sleeve. Close tolerances, in turn, increase the life of the tip.

MUCH-USED TIP
. . . shows slight scoring and feathering

Alloy Properties—Beryllium-copper combines good thermal conductivity with high tensile strength and endurance. It has wear resistance comparable to steel.

These are definite advantages in plunger tip operation. As the tip moves in to feed the aluminum to the die, the impact tends to peen the edges of the tip outward against the sleeve. This is a desirable effect, since it tends to preserve close tolerances.

As the tip wears, it feathers at the inlet end around the plug. When feathering becomes excessive, the tip is removed, the edges pounded out, and the tip is turned down so it will fit the sleeve.

Will Vacuum Melted Metals do for YOUR Product what they do for Jet Planes?

A Vacuum Furnace will help you get the Answer

The roaring gas turbines of 1000 mph jet planes use vacuum melted metal parts to withstand temperatures and stresses that would ruin conventional metal. If you use metal under severe conditions in your product . . . or require "cleaner" metals for smoother surfaces, you should be testing vacuum melted metals today. A high vacuum furnace will help you speed up these tests by supplying your researchers with a ready supply of varying alloys. We have made and operated more high vacuum furnaces than anyone in the world. Can we help you, too? Send coupon below today.



NRC Model 2555 Vacuum Furnaces are now being used by leading aircraft companies, engine manufacturers, investment casters, specialty steel producers to speed up the development of new materials that will meet ever more severe operating requirements.

NRC
NARESCO
EQUIPMENT
CORPORATION

SALES OFFICES:
Boston, Chicago, Cleveland, Houston, Los Angeles, New York, Palo Alto, Philadelphia; in Canada: Toronto, Arnprior

NARESCO EQUIPMENT CORPORATION
Subsidiary of NATIONAL RESEARCH CORPORATION
Dept.-1211, Charlemont St., Newton Highlands 61, Mass.

Send me your Vacuum Furnace Bulletin ☐ Have your representative call ☐

Name.....Title.....
Company.....
Address.....
City.....Zone....State.....

Why four pieces of metal?



. . . with necessary cutting, punching, forming and welding!

. . . How about

Malleable?

Stronger one piece malleable iron casting with better appearance

Better material selection exemplified by this trailer hitch is an everyday development in the malleable iron foundry industry.

The improved design, and therefore *appearance,* is quickly apparent. The big advantages are greater uniformity and dependability, and increased strength—*at lower cost* (in this case, 25% lower cost to the customer). The unit is completely stress relieved and benefits from a better distribution of metal than its fabricated predecessor. Improved damping properties and corrosion resistance are additional gains.

If you are not using malleable iron's remarkable properties, it will pay you to call a malleable foundry and go over your products with their engineers. Skilled in casting design, they show you how to save money and improve your products with Malleable Iron Castings.



1800 Union Commerce Building Cleveland 14, Ohio

Seal for Castings

Polyester resin sealant cuts costs and cycle time in processing aircraft engine parts

THE SHRINKAGE in molten metal as it cools opens up tiny pores in castings through which oil can leak. When the castings are for aircraft engines, this becomes a major fire hazard. Pores must be sealed.

Lycoming Division, Avco Mfg. Corp., Stratford, Conn., found that by using Impco RC-2, a compound based on Bakelite polyester resins, it could cut sealing costs by 20 per cent and cycle time by 40 per cent.

Before — Previously, it took 8 hours or more to seal magnesium alloy castings of engine parts. Frequently, castings were cycled two or three times.

Castings now are sealed in less than 5 hours in one cycle.

Procedure—Parts are placed in a pressure vessel. A vacuum is drawn to remove all air from the pores, and then air pressure is applied to thoroughly impregnate the casting.



IMPREGNATED CASTING
. . . shows no leakage under water

Castings are rinsed with warm water and a mild detergent to remove excess resin. Previous sealants required flammable solvents to remove excess film. Cleaned castings are put in a tank of hot oil at 270°F to cure the resin.

The polyester sealant gels quickly and forms a hard solid in 60 to 90 minutes. Each casting is tested for leakage under water at 180 to 200°F at pressures to 70 psi.

An 80-Mile Train of New Sulfuric Acid Production!



Map shows General Chemical's coast-to-coast network of Sulfuric Acid plants and supply points. Stars indicate locations where additional capacity is being made available.

General Chemical Expands Capacity from Coast to Coast!

In an expansion that extends to all points of the compass, General Chemical is providing an additional 600,000 tons of Sulfuric Acid annually, with increased production facilities . . .

- ★ West at El Segundo and Richmond, Calif.
- ★ South at Baton Rouge, La.
- ★ North at Valleyfield, Que.*
- ★ East at Buffalo, New York
- ★ In the Mid-west at Detroit, Mich., Painesville, Ohio and E. St. Louis, Ill.

This means approximately 12,000 more tank cars of Sulfuric Acid available to meet growing requirements of industry . . . a train load 80 miles long! Some of these new facilities are already in production, and the others are scheduled for completion in 1956.

As America's foremost producer of Sulfuric Acid, General Chemical recognizes a responsibility to keep pace with industry's need for this vital basic chemical. No matter where you are located, you are within a short, low-cost haul of a primary producing center of General Chemical Sulfuric Acid. Remember . . . in emergencies and at all times . . . General Chemical is your dependable source of Sulfuric.

Basic Chemicals for American Industry

Allied Chemical

GENERAL CHEMICAL DIVISION
ALLIED CHEMICAL & DYE CORPORATION
40 Rector Street, New York 6, N. Y.

Offices: Albany • Atlanta • Baltimore • Birmingham • Boston • Bridgeport • Buffalo • Charlotte Chicago • Cleveland • Denver • Detroit • Greenville (Miss.) • Houston • Jacksonville Kalamazoo • Los Angeles • Minneapolis • New York • Philadelphia • Pittsburgh • Providence San Francisco • Seattle • St. Louis • Yakima (Wash.)
In Wisconsin: General Chemical Company, Inc., Milwaukee.
*In Canada: The Nichols Chemical Company, Limited • Montreal • Toronto • Vancouver



PRESSURIZED WATER REACTOR—Circulates pressurized water or heavy water through vessel containing solid uranium fuel elements. Water passes through boiler where steam is made to drive turbogenerator



BOILING WATER REACTOR—Water boils within vessel containing fuel elements. No heat exchanger is used. Fairly high fuel enrichment is required and condenser and turbine must be shielded because the water is radioactive

ATOMS MEAN BUSINESS II

The New Materials Market

By DR. ALLEN G. GRAY
Technical Editor

ALTHOUGH uranium is the Cinderella metal of the atomic age, many others will be needed in increasing amounts.

Each component of a nuclear reactor poses its own materials problem. All must meet these basic requirements: Strength, corrosion resistance and dimensional stability. In addition, they must have nuclear properties—because of them, a number of metals, unknown commercially a few years ago, are in the limelight. Among them are zirconium and hafnium.

Zirconium is important because it absorbs only a few of the neutrons generated in the fission process and does not interfere with the reaction. Hafnium is valuable for the opposite reason. It absorbs many neutrons and is used in control rods to quench atomic fires.

Complex—The core of a nuclear reactor contains many structural components: Supports or containers for fuel and moderator; ductwork, piping, valves, and fittings; control-rod sleeves and mechanisms; shells, baffle plates, header chambers and closures. Part I of this article (STEEL, Oct. 31, p. 66) discussed the market for components that could be made in metalworking plants.

Requirements for materials in these applications are in general: Adequate strength, fabricability, thermal and radiation stability, corrosion resistance and satisfactory nuclear properties.

Nuclear requirements cut the list of metals for thermal reactors to four: Zirconium, beryllium, aluminum and magnesium. They are the only ones that have low neutron absorption (less than 0.5 barn/atom).

Preferred—High melting point, excellent fabricability and good corrosion resistance give zirconium a top spot as structural metal for the core of a thermal reactor. But the pure metal is still difficult to produce, is expensive and creeps more than is desirable. Corrosion resistance to hot water and hot strength are improved by alloying it with tin (a few per cent).

Beryllium has good moderating characteristics as well as a high melting point. But the supply is limited; it's toxic, difficult to fabricate and its corrosion resistance is not so good as zirconium's.

The two low neutron absorption metals left are aluminum and magnesium. They are not high temperature metals. Aluminum is used a great deal in low temperature research and production reactors.

The future may see more attention to magnesium because of its low neutron absorption and abundance. Poor corrosion resistance is one stumbling block.

More Metals—If higher neutron absorption can be tolerated, the list of metals for structural uses grows. Many of these can be used in small quantities in a thermal reactor—more extensively in the intermediate or fast reactor.

Metals with moderate absorption and high melting points are: Columbium (niobium), iron, molybdenum, chromium, copper, nickel, vanadium and titanium.

Columbium has good mechanical properties, but the supply is short. Pure chromium metal is not suitable for structural use. Stainless



SODIUM GRAPHITE REACTOR—Sodium pumped through graphite moderated reactor extracts heat to make steam to drive turbine. Liquid metal allows high temperature operation, gives high thermal efficiency



SODIUM COOLED FAST REACTOR—Sodium extracts heat from unmoderated plutonium core which is converted to steam. Uranium blanket surrounds core to utilize escape neutrons and breed new fissionable materials

steels combine good corrosion resistance with good mechanical properties at moderately high temperatures.

Looks Good—Ductile vanadium, now commercial, is promising from strength and corrosion standpoints. Molybdenum is the best candidate for high temperature use. Refractory properties and unusually high thermal conductivity are points in its favor.

Titanium stands a good chance for use in intermediate reactors because of its high strength-weight ratio, good corrosion resistance and other good physical properties.

As temperatures go up, nickel alloys, such as Nichrome, Illium, Hastalloy and Inconel, will come into the picture.

Beyond the Metals — Ceramics are the only good prospects for structural elements for ultrahigh temperature use. Oxides—beryllia, magnesia, silica, alumina and zirconia—are candidates. Carbides of beryllium, silicon and zirconium are possibilities.

Toughest problems: Overcoming the tension weakness and generally poor thermal shock resistance of the nonmetallics. Almost an endless number of combinations are possible—carbides with oxides, for example. The field of metal-ceramic combinations shows promise of adding strength and better thermal conductivity.

CONTROL MATERIALS

The best way to control the heat produced by thermal and low level intermediate reactors is to introduce material that absorbs neutrons. Absorbing controls may be introduced in a number of ways. The AEC's *Reactor Handbook* says they should have these properties:

NEED INFORMATION?

More facts on materials for atomic applications can be found in the Atomic Energy Commission's new 610 page *Reactor Handbook* Vol. 3, section 1. Official number of the book is AECD-3647. It's for sale by Superintendent of Documents, U. S. Government Printing Office, Washington 25, D.C. Price: $3.50

1. High ability to absorb neutrons.
2. Adequate strength for solid rods.
3. Light weight, so rapid movement will give only slight inertia.
4. Resistance to corrosion by coolant.
5. Stability under heat and radiation.
6. Good heat transfer properties.
7. Fabricability, availability and reasonable cost.

Top Spot—Boron and cadmium are the most widely used control materials. Hafnium, removed as an impurity from zirconium, is looking up because of availability and good corrosion resistance.

Mercury might find use as a liquid control material. Its high vapor pressure and reactivity with most metals is discouraging, especially for high temperature reactors.

Some of the heavier rare earth elements have a property that makes them especially well suited for control materials: Their neutron absorption does not fall off so rapidly as most materials when neutron energy is increased. If the demand grows, some of these metals may come on the market at reasonable cost for atomic use.

MODERATORS

Moderating materials are used to reduce neutron energy rapidly. This slowing-down power requires a material with low atomic weight and a high scattering cross section, meaning that particles which collide are deflected. For efficiency, low absorption for thermal neutrons is needed.

Beryllium and carbon are the only good solid moderators. Even though it's expensive, beryllium's low neutron absorption and its high moderating ratio have led to its use in a number of reactors. Its compounds—carbides and oxides—are refractory and make



AQUEOUS HOMOGENEOUS THORIUM BREEDER REACTOR—Uses a solution of uranium in heavy water as fuel. It circulates through a tank surrounded by larger vessel that contains a thorium blanket to utilize neutrons that escape from core. This breeds new fissionable material

good moderators for power reactors that must operate at high temperatures.

REFLECTORS

Since the function of a reflector is to reflect back into the reactor neutrons that leak out, the materials used must meet about the same nuclear requirements as the moderator: Good scattering characteristics and low neutron capture.

Others, Too—But the main job of a reflector is scattering. Many materials which have a high scattering property for fast neutrons but are not considered good thermal pile moderators are usable. These include metals with high atomic densities, such as iron; those in the upper end of the periodic table which are noted for high scattering ability, such as bismuth and lead; and breeder materials which also have high fast scattering properties, such as uranium and thorium.

Metals for moderator and reflector use must have all the qualities of a good structural material in addition to nuclear requirements. They include strength, fabricability, thermal and radiation stability and corrosion resistance. Needed also are good heat transfer properties to dissipate the energy given up by the neutrons hitting it.

SHIELDING MATERIALS

No one material meets all the demands of an ideal radiation shield around a nuclear reactor. This means that shields will be constructed of several materials, each having at least one of these properties: 1. A good moderating material to slow down neutrons. 2. A good absorber to take neutrons out of the field. 3. A dense heavy material to stop gamma rays.

The AEC's *Reactor Handbook* gives this list of materials that are useful in shields:

1. Amalgams. 2. Cement and concretes of special aggregates. 3. Ceramics and cermets. 4. Glasses and fused salts. 5. Metal ores. 6. Metals, alloys and sintered powders. 7. Organics—plastics, metal-loaded resins, silicones. 8. Silica and gels formed from boron-loaded solutions. 9. Water, hydrides, hydroxides, etc.

Useful—A great deal of work is being done on special concretes for shields. Points that favor concrete: It's a good structural material, can be handled easily and has enough hydrogen to moderate fast neutrons. But its density is low. This means an all-concrete shield will be thick.

Boron finds use in neutron shielding because it has an unusually high neutron absorption value.

Lead, tungsten and tantalum are heavy metals useful for shields. Gold, iridium, osmium, uranium and the rare earths might be employed if cost and availability were better. Lead and tantalum can be fabricated easily. Tungsten is shaped by powder metallurgy methods.

FUEL ELEMENTS

Reactor fuel elements are made up of a core, consisting of fissionable material in some diluent, and a cladding to protect the core from corrosion and to prevent fission-product contamination of the coolant.

Considerations—Selection of a material for fuel elements depends on many factors: Whether the reactor produces power alone or is to breed; whether it is thermal, intermediate or fast; temperature of operation; and corrosiveness of coolant.

Reactors being built use natural or slightly enriched uranium. They use slug-type fuel elements. Canned uranium slugs are being replaced by clad plates with uranium alloy core and a bonded coating of an alloy, such as aluminum-tin, zirconium-tin or stainless.

Limits—Aluminum clad fuel elements can be used only up to 400°F with water. Zirconium goes higher—up to 1000°F. Stainless steels have good strength and corrosion resistance at higher temperatures. Molybdenum looks promising for use up to 2500°F. But both molybdenum and stainless have the disadvantage of high neutron absorption and require a more enriched fuel.

Materials used in fuel element assemblies must stand up under the most difficult operating conditions. They must keep their strength under adverse conditions of temperature, irradiation, external loading and weakening caused by burnup. They must be stable dimensionally and resist many kinds of corrosion. Good heat transfer is important. This means: High thermal conductivity, large surface area, thin sections and no dead spots.

Canning materials should have good bonding characteristics and not react chemically with the core. Also, there must be minimum diffusion between core and cladding.

Extra copies of this article and Part I (components for atomic plants) are available in quantities from one to three until the supply is exhausted. Write Editorial Service, STEEL, Penton Bldg., Cleveland 13, O.

BUILDS EXTRA SELLING POWER INTO YOUR PRODUCTS



...hot or cold rolled...
A. W. STRIP STEEL is a salesman
...for your products

Invisible . . . yes—but there, nevertheless . . . adding the superior qualities of strip steel produced precisely to your specifications of temper, finish and uniformity under the most rigid metallurgical control—qualities that help give your product the strength and dependability which build reputation and sales.

If your products require hot or cold rolled strip or sheets . . . call upon the services of an integrated steelmaster with modern, up-to-date continuous mills—where "custom-production" is standard practice. Call upon ALAN WOOD STEEL COMPANY.

IRON PRODUCTS
"Swede" *pig iron*
STEEL PRODUCTS
Plates (sheared)
Hot rolled sheets
Hot rolled strip
Cold rolled sheets
Cold rolled strip
ROLLED STEEL FLOOR PLATE
A.W. ALGRIP *abrasive*
A.W. SUPER-DIAMOND *pattern*
A.W. CUT NAILS
MINE PRODUCTS
COKE
COAL CHEMICALS

ALAN WOOD STEEL COMPANY

steelmasters for 129 years • CONSHOHOCKEN, PENNA.

DISTRICT OFFICES AND REPRESENTATIVES: Philadelphia • New York • Houston
Los Angeles • Atlanta • Boston • Buffalo • Cincinnati • Cleveland • Detroit • Pittsburgh
Richmond • St. Paul • San Francisco • Seattle • Montreal and Toronto—
A. C. Leslie & Co., Limited

SM-39

HEVI DUTY BELLIS SALT BATH FURNACES



Temperatures from 300° F. to 2400° F.

Built to any size or capacity with either a ceramic, welded steel, or alloy pot whichever the particular process requires.

SPECIAL FEATURES of the HEVI DUTY BELLIS FURNACES

- Immersed alloy electrodes with the patented water-cooled terminals prevents the conduction of heat to the transformer.
- Self-contained ceramic pot quickly removable. Ceramic, steel, or alloy pots are interchangeable — thus one furnace can be used for a variety of operations by merely changing to the pot best suited for the process.
- Electric starting coil quickly and easily remelts the salt after a shut-down.
- Recessed electrodes permit a rolling cover, thus minimizing heat radiation from the bath surface.
- Sturdy construction means years of dependable service.
- Low operating voltage eliminates shock danger.

These features along with the many other advantages of salt bath furnaces such as versatility, economy, exact temperature control, mean to you savings in time, money, and material.

Send for complete information in Bulletin 655.

HEVI DUTY ELECTRIC COMPANY

MILWAUKEE 1, WISCONSIN

Heat Treating Furnaces... Electric Exclusively

Dry Type Transformers ***Constant Current Regulators***

Chips Get a Ride

Loaded in conveyor pans, the travel up four floors and di charge into gondola cars

A CONTINUOUS chip conveyo system dumps 35 tons of machir ing chips daily into waiting gor dola cars at the New Process Gea Co., Syracuse, N. Y. Except fo manual loading, the operation i automatic.

Chips are collected from the ma chines on each floor by han trucks and emptied into hopper in the basement where the o drains off. From the bins, work ers shovel them into flat-bottome pans, mounted at 10-ft spacing on a 4-in. trolley conveyor.

Route—Each pan carries abou 40 lb of chips. Pans travel u through the fourth floor and ou over the railroad siding to the lin of gondola cars.

Pans pivot on bushings whic are below the center of gravit and slightly off center to facili tate tipping. A spring-loaded latch and-pin arrangement keeps th pans upright.

CHIP-LADEN PANS
. . . automatically dump their load

Dumping — At the dumpin point, the latch extension strike a hinged plate mounted beside th track. The impact disengages th pin, allowing the pan to tip to on side.

The chips pour out and fall int the gondola car below. Empt pans are returned to the upright a few feet beyond the dumpin point by a cam rail acting on th low side of the pan.

Stop-and-start controls are a the dumping platform and th chip bins. The conveyor was in stalled by Lamson Corp., Syracus N. Y.

Fully Packed

age area at Cleveland (O.) Divi- Midland Steel Products Co., is ked solid with auto frame parts. one aisle is needed since the e, 15-ton capacity Whiting crane s the entire 95-ft width of the floor

e Cloth Blankets Industry

Vire cloth covers the whole of stry with its many and varied ducts. It is woven in a variety patterns and metals to meet requirements. Gages are some- s so fine they are measured in thousandths of an inch.

o make wire cloth, producers as Reynolds Wire Division, ional-Standard Co., Dixon, Ill., draw the metal rod into wire. wire is put on bobbins. These ly warp and filler wire to ns which convert the wire into n. Special machines split the n for particular uses.

Vire cloth has unique as well general uses. It can insulate eate instrumentation from y currents, combining excel- conductivity for shielding with ngth for permanence.

can be used successfully as ning mill cloth, because of its ensional stability and accurate ling. Another unusual use is a carrier of "wet lap" which prises the woody fluid com- nd used to form hardboard.

s filter and strainer material, cloth serves the auto indus- aviation, railroads, the home all manufacturing. It is made radio grilles and auto brake gs; even the cream separator he farm uses it as a basic ele- t. As shaker screens, it les rock, ore, abrasives, pow- and coal.



Moves Big, Heavy Loads . . . faster!

Lifting heavy loads, like this unwieldy 78 foot steel beam, is an easy operation for a UNIT Model 1020 Crane. The LIFT and CONTROL ability of UNIT permits loading and unloading with speed and accuracy.

The Safety-promoting FULL VISION CAB enables the operator to see what he is doing at all times. If you have a material handling job that must be performed quickly, efficiently and with SAFETY . . . look into UNIT.

Send for Bulletin Now

UNIT CRANE & SHOVEL CORP.
6521 W. Burnham St. • Milwaukee 14, Wis., U.S.A.

Geared to boost your earnings!

A 8484-⅔-C

...the Miracle Metal ... LITHIUM

Lithium, like metallurgy, has come a long way. Once a laboratory curiosity, lithium is now the "catalyst of industry." Once the art of separating metals from their ores, metallurgy now embraces a whole new industry devoted to the manufacture and treatment of the alloys of these metals. And now—still another new field within a field—Lithium Metallurgy.

Lithium Ingots are used in the degasification of copper. Lithium Cartridges are used in the refinement of high temperature copper, and in brass, bronze and nickel-silver castings. Even the salts of lithium (Carbonate and Chloride, specifically) hold great promise for heat treating.

Lithium metal and its compounds could hold the same hope for *you*. We will be happy to discuss it at your convenience.



... trends ahead in industrial applications for lithium

LCA LITHIUM CORPORATION OF AMERICA, INC.
2545 RAND TOWER
MINNEAPOLIS 2, MINN.

MINES: Keystone, Custer, Hill City, South Dakota • Bessemer City, North Carolina • Cat Lake, Manitoba • Amos Area, Quebec • BRANCH SALES OFFICES: New Yo
Pittsburgh • Chicago • CHEMICAL PLANTS: St. Louis Park, Minnesota • Bessemer City, North Carolina • RESEARCH LABORATORY: St. Louis Park, Minnesot

brasive Wheels Combine High Speed with High Strength

A special web backing of spiral-wound, rayon, to-tire cord makes these grinding wheels extra fe.

The lightweight, rigid-type, reinforced resinoid nded wheels are used on portable disc and right gle grinders. They are made in 7 and 9-in. di-eters and are 3/16 or ¼-in. thick. Centers are pressed.

Fast abrasive cutting action gives heavy stock moval; the wheels are used for rough, tough pro-ction grinding — grinding welds, removing flash d bead, cleaning up rough ragged surfaces and ges and for stainless steel.

The wheel is made of abrasive cutting particles d synthetic resin bonding agents, reinforced with pha cellulose fibers crisscrossed and knitted to-ther throughout the wheel mass. *Write*: Simonds rasive Co., Tacony & Fraley Sts., Philadelphia 37. . *Phone*: Jefferson 5-6100

niversal Testing Machine Prints Test Results

Testing is reduced to pushbutton simplicity by this ,000-lb-capacity unit. The operator merely inserts e specimen and starts the machine. Everything e is automatic, although the machine can be oper-ed manually.

All phases of production tensile tests are controlled a built-in programmer. Preset controls minimize e time needed to make successive tests and also sure uniformity of testing.

A separate electric typewriter automatically prints e yield strength for the selected percentage of set, plus an identifying test number as each speci-en is tested. Yield strength or other test data e determined immediately without time-consuming erpolation of a stress-strain curve.

The testing machine can be set to apply a uniform ading speed of from 0 to 3.5 in. a minute until the ecimen fractures. Then the machine automatically turns to zero load and is ready for another sample be inserted.

For high-speed testing, a predetermined control int and a yield speed time are set on separate dials. fast approach speed, plus a slow yield speed and fast tensile speed, are also selected.

When the machine is started, it loads rapidly at e approach speed to take up the slack in the spec-en. When the control point is reached (just short the expected yield), the loading rate is cut down the slow speed specified for the material being ted. This speed continues for the preselected time rough the yield determination, and then the speci-en is loaded at a fast speed until it fractures.



The electric typewriter and a data converter make up the data printer. To operate it, the desired percentage of offset is selected on the converter control unit and the machine is started.

When the electronic stress-strain curve intersects with the desired offset, the electric typewriter automatically prints the load in pounds applied to the specimen at that instant.

The printing unit can be located any distance from the testing area.

Other new machines are a semiautomatic, air-operated Brinell hardness tester made of cast aluminum and an impact tester for making Charpy tests. *Write*: Tinius Olsen Testing Machine Co., Willow Grove, Pa. *Phone*: Osborn 5-7100

Another of the Reasons Behind Brad Foote Quality—

DEBURRING

• Deburring of gears isn't normally included in specs or drawings. And we don't get paid for it. But here at BRAD FOOTE we take pains and expend many man hours on deburring—for we know that one tiny burr can ruin a $100,000 machine.

• Examine your next shipment of gears. See whether your present supplier is painstakingly removing all the burrs. Find out how many hours your assembly department has had to charge against deburring. See another way in which BRAD FOOTE quality and extra attention to details saves you money.

• Prove to yourself the savings that BRAD FOOTE quality can mean. Let us quote on the gear requirements for your next program—whether it be radar equipment, diesel engines, etc. BRAD FOOTE has experience in providing gears for almost every specialized application and would welcome the opportunity of discussing your gear problems.

BRAD FOOTE MAKES ALL TYPES OF GEARS—IN A COMPLETE RANGE OF STYLES AND SIZES

BRAD FOOTE GEAR WORKS, INC.
1309 South Cicero Avenue • Cicero 50, Illinois
Bishop 2-1070 • OLympic 2-7700 • TWX CIC-2856-U

subsidiaries | AMERICAN GEAR & MFG. CO. Lemont, Illinois Phone Lemont 920 | PITTSBURGH GEAR COMPANY Phone SPalding 1-4600 Pittsburgh 25, Penn.

for **QUALITY CONTROL**
when it counts—choose a

PRICE BENCH CENTER and SURFACE PLATE!



Model 400
$87.50
F.O.B. Van Nuys
(Carrying case available at extra cost)

Completely illustrated PRICE Bench Center and Surface Plate folder sent on request.

For tool room, inspection and at-the-machine quality control procedures, only PRICE gives you on-center and surface accuracy to .0002—plenty of table area for blocks and gauges—fast, hand adjusting setups and unmatched versatility and quality!

PRICE ENGINEERING COMPANY, INC.
14348 Bessemer Street • Van Nuys, California

NEW PRODUCTS and equipment

Tractor Shovel

Pry-out bucket action is fe tured by this tractor. Capacity the bucket is ¾-cu yd struck, cu yd heaped. Carrying capaci is 3000 lb at 4 mph.

A short turning radius and rea wheel power steering give fa maneuverability. A high lift 7 ft 9 in. makes it easy to lo trucks or elevated hoppers.

A 57-hp gasoline engine gives top speed of 14 mph forward a 23 mph in reverse. *Write*: Fra G. Hough Co., 876 Seventh S Libertyville, Ill. *Phone*: Libert ville 2-4000

Tube Expanding Control

This electric control assures t same expansion of each tube aft metal-to-metal contact regardle of small variations in size of tu and tube sheets. The control is torque-limiting divice that can used with any standard tappi motor.

A voltage regulator balances o outside variables that influen control calibration. *Write*: La onda Division, Elliott Co., Sprin field, O. *Phone*: Fairfax 3-4695

Vibrating Screens

Scalping and rough sizing a done by these pulsating magn vibrating screens. Powered b dust-sealed electromagnetic drive



ALLIS-CHALMERS
(BUDA)

OFFERS YOU A CHOICE OF ENGINES
DIESEL, GASOLINE OR L-P GAS
ALL BUILT BY BUDA

Send for
Free Buda Booklet
Here's all the information you need in 36 fact-packed pages of lift truck illustrations and statistics. Write for free copy!

Whatever fuel you prefer — Gasoline, Diesel or L.P. Gas — Buda offers you an engine that is built heavier, built stronger, and built for longer, trouble-free service. Only Buda makes its own! This means the engine is specially designed, for the type of fuel to be used, by industrial engine experts for the Buda Fork Lift Truck — designed to do heavy jobs. Buda engines have 85% parts interchangeability, provide 30% longer life, have proven fuel savings of up to $500 a year. So, regardless of fuel — Gasoline, Diesel or L.P. Gas — Buda is a better buy.
Buda Division, Harvey, Illinois

ALLIS-CHALMERS

FORK LIFT TRUCKS

INDUSTRIAL TRACTORS

PLATFORM TRUCKS



STOOLS

- weighing 10,000 pounds each
- alloyed 25% Cr—12% Ni
- for 1750°F. temperatures

DURALOY

These stools should offer a very pertinent tie-in with your casting requirements. Essentially, they are alloyed to resist heat. They're typical of the heavy high alloy castings we are equipped to turn out.

They will serve also to indicate what we can do in the way of producing castings to resist not only high temperatures but severe corrosion or combinations of heat and corrosion, as well.

Today, we can offer several distinctly different types of castings in the high alloy field including static, centrifugal and shell-molded.

Many in both the metal working and processing fields have come to look upon Duraloy as the leading producer of exclusively high alloy castings. This reputation has been built on many years production of sound castings properly alloyed. We'll be glad to discuss your high alloy casting requirements.

THE DURALOY COMPANY
OFFICE AND PLANT: Scottdale, Pa.
EASTERN OFFICE: 12 East 41st Street, New York 17, N. Y.
DETROIT OFFICE: 23906 Woodward Avenue, Pleasant Ridge, Mich.
CHICAGO OFFICE: 332 South Michigan Avenue

the new models have replaceab screening surfaces and rigid ste frames.

A tap switch in a separate ele tric controller adjusts to contr the amplitude of the screen's v bration. *Write*: Syntron Co., 37 Lexington Ave., Homer City, P

Precision Duplicator

This electronic duplicator is f lathes up to 16-in. in capacity.

The single-motion unit operat with a stylus pressure of 8 oz ar is accurate to ±0.0015 in.

Standard tool bits are used gages and form tools are elimina ed; and the possibility of error reduced. The duplicator is easil attached or removed. *Write*: Ray theon Mfg. Co., Waltham 54, Mas *Phone*: Waltham 5-5860

Dust Control

This scrubber removes 99 pe cent of microscopic solids, fume and odors. When particles are be low 5-microns, efficiency is 70 pe cent.

Dust is collected by hydrocom pressing exhaust gases through system of tubes into a water cham ber. This gives a highly efficien scrubbing action. The violent wa ter agitation causes secondary pres sure turbulence and additiona scrubbing action in the tube cham ber.

The scrubber comes in 15 size ranging from 500 to 40,000 cfm Sludge can be removed constantl



or intermittently by manual, hydraulic or mechanical means.

Dust-laden gases can be wetted and cooled in the entry chamber. Flushing prevents build-up of solids on the inside. *Write*: Johnson-March Corp., Philadelphia, Pa. *Phone*: Regent 9-3389

Press Brake Control

Electronic controls (they can be installed on any press brake) make for faster and safer operation. They have four parts: 1. A limit switch box tied in with the stroke of the ram. 2. A solenoid. 3. A foot switch or hand button. 4. A control panel.

Features include a preset stop, a self-return and a nonrepeat.

Kinking and whipping of even the largest sheets are eliminated. *Write*: American Actuator Corp., 219 E. 44th St., New York 17, N. Y. *Phone*: Oxford 7-2989

Gripper Feed Unit

Stock can be fed into a press from any direction by the self-contained feed unit. It feeds stock of any width up to 20 in. It can



The over-all job in

Production Lines and Special Automatic Machines by CONTINENTAL

for military production . . .



Continental Automatic Strip Production Line consisting of annealer, pickling machine, dryer, and coiler.



Continental Special Automatic Pig Molding Machine complete with automatic charging, melting, and pouring.

Continental Automatic Production Line operating from raw materials to completely finished and packed product. This production line consists of fifteen integrated, synchronized, special automatic machines.



Continental Special Automatic Glazing Machine complete with automatic press synchronizer and fire polisher.

For maximum production of military items manual operations must be eliminated. With CONTINENTAL Special Automatic Machines and Integrated Production Lines production goes on in a continuous flow with better, more uniform products with a minimum of man hours.

CONTINENTAL jobs begin with analysis of the requirements, then the selection and development of proper methods for greatest results. Finally follows the design, the building, and the installation of the machines—delivering a COMPLETE UNITIZED PRODUCING PACKAGE with results guaranteed.

The broad experience of CONTINENTAL offers you a prompt, sure solution to your change-over program.

CONTINENTAL INDUSTRIAL ENGINEERS, INC.
176 W. Adams Street, Chicago 3, Illinois
District Representatives:
Ridgewood, N. J. • St. Louis • Cincinnati • Detroit
Milwaukee • Indianapolis • Cleveland • Pittsburgh



Write for Booklet No. 135

FURNACES PRODUCTION LINES CONTINENTAL SPECIAL MACHINES COMPLETE PLANTS

MANUFACTURERS—ENGINEERS—CONTRACTORS FOR OVER A QUARTER OF A CENTURY

be designed to feed up to 48 in.

Stock feeds are within 0.003 in. of the selected setting. The unit is timed by the stroke of the press ram.

The unit comes equipped with a front stock guide and a rear stock assembly, a scuff-free gripper assembly, a stock retainer, a motor and pump assembly, four adjustable legs and a conveniently positioned control panel.

The front stock guide keeps stock at the proper level and in line for the desired positioning in the press die. Adjustable stock guide rolls make it easy to run various stock widths.

The rear stock guide assembly adjusts to handle stock from ½ to 48 in. A hand knob at the end of the cylinder adjusts the feed length.

The gripper assembly has special gripper pads that feed stock without scratching or scuffing.

An opposed-roller stock retainer prevents stock from slipping backward on the return stroke of the gripper.

A stock oiler oils the stock on top and bottom. Optional is a stock straightener that removes coil bend. *Write*: Sesco Inc., 8881 Central Ave., Detroit 4, Mich.

Drilling Machine

This unit drills, chamfers and taps holes automatically.

Here is a typical feed cycle:

Position No. 1, drill: Locate part, rapid traverse, feed forward, rapid reverse, index.

Position No. 2, chamfer: Rapid traverse, feed forward, rapid reverse, index.



Position No. 3, tap: Rapid reverse, feed forward, feed reverse, rapid reverse, index to position No. 1.

The machine has a three-position automatic fixture slide. *Write*: National Automatic Tool Co., Richmond, Ind. *Phone*: 2-1183

Cold Setting Core Binder

A new formulation of oils, when added to sands in amounts up to 2 per cent, produces hard, nondeforming, finished cores and mold surfaces. The sand-binder mixture is poured into the corebox.

No ramming of sand is needed; 50 to 60 per cent of the rodding is eliminated; core surfaces have uniform hardness; accurate core sizes are maintained; rough cleaning

SPECIFICALLY ENGINEERED . . . NEVER MERELY ADAPTED . . .
FOR EACH PARTICULAR TYPE OF APPLICATION

HANSEN
QUICK-CONNECTIVE
COUPLINGS

ONE-WAY SHUT-OFF
Shuts off one side of line

Gives quick connection and disconnection, with instant automatic flow or shut-off. To connect Coupling, and open line to flow of fluid, merely push Plug into Socket. To disconnect, a slight pull on sleeve releases Plug and shuts off supply end of line.





TWO-WAY SHUT-OFF
Shuts off both sides of line

To connect, pull back sleeve and push Plug into Socket. Identical torpedo type valves permit free flow of gas or liquid through Coupling. To disconnect, pull back sleeve . . . Coupling immediately disconnects, valves automatically seal both ends of line. Female pipe thread connections from ⅛" to 1". Available in brass or steel.

STRAIGHT-THROUGH COUPLING

Provides quick connection and disconnection, but does not have shut-off feature. Sizes, ranging from ¼" to 2½", carried in stock. Two special types of straight-through steam Couplings also available—one for low pressures, and one for high pressures.

REPRESENTATIVES IN PRINCIPAL CITIES

Quick-Connective Fluid Line Couplings for
Oil • Hydraulic Fluids
Grease • Steam • Water
Refrigerants • Acetylene
Air • Oxygen • Vacuum
Gasoline • Coolants
Write for Catalog

SINCE 1915 QUICK-CONNECTIVE FLUID LINE COUPLINGS

THE HANSEN MANUFACTURING COMPANY
4031 WEST 150th STREET • CLEVELAND 11, OHIO



31 experts collaborated

Greatest book ever written about making iron and steel

440 pages 8½" × 11"

An illustration on every page

ORDER YOUR COPY OF THIS AMAZING BOOK TODAY!

Everyone in your plant—from top executive to apprentice—will benefit from the use of this book.

It represents years and years of constant "on-the-job" experience in every branch of iron and steel making—every statement in it rings with the authority of actual, first hand experience.

No *one* man could have written this book. It required the combined skills of 31 of the nation's foremost experts. . . men like Charles L. McGranahan on hot and cold-rolled strips and sheets; Waldemar Naujoks on forgings; Alfred E. Kadell on tin plate, and 28 others of equal stature.

Although this book is the work of skilful, highly trained specialists, it is written in simple, non-technical language that the youngest apprentice can understand. To make things even more clear, photographs, charts and other visual aids are employed throughout.

Here's how to order the number of copies you need—

10 DAY FREE TRIAL

THE PENTON PUBLISHING CO.
Book Department
1213 West Third Street, Cleveland 13, Ohio

send me a copy of "the ABC of Iron and Steel"

☐ On ten days trial for free examination, following which I will pay for the book at $10, plus postage, or return it in good condition.
☐ Remittance enclosed* in which case the book will be sent prepaid.
☐ C.O.D.

SIGNED_____ TITLE_____

COMPANY _____

ADDRESS _____

CITY_____ ZONE____ STATE_____

*Add 30 cents to cover state sales tax on orders for delivery in Ohio.

This 25-TON Hannifin Straightening Press Sells For

$4,179 FULLY EQUIPPED AS SHOWN

Price F.O.B. our press plant at St. Marys, Ohio, subject to change without notice



The ideal press for straightening heat-treated parts up to 60" between centers. Exclusive Hannifin Sensitive Pressure Control for speed and accuracy. Ram block, two table blocks and center-type fixture complete with rails included.

STRAIGHTENING PRESSES FROM 5 TO 150 TONS

Hannifin offers longer tables and rails, roller-type fixtures, larger or smaller capacities (5 to 150 tons)—all at prices that are easily justified by savings on the job. Bring us your straightening problems.

HANNIFIN

HANNIFIN CORPORATION, 523 S. WOLF ROAD, DES PLAINES, ILLINOIS



STYLE AND SIZES FOR ALL MACHINES ON WHICH THREADS ARE CUT

This die head is unique

THERE IS NO OTHER LIKE IT

It cuts threads with insert chasers. These are, in reality, small sections of the business end of large and expensive chasers, but with this important difference: *their cost is so low they can be even thrown away when dull.* For example, for less than $40 you can get a dozen sets of insert chasers, each set ground ready to go. Change now to insert chaser die heads and watch your performance improve.

"Unified and American Screw Thread Digest," sent free on request.

THE EASTERN MACHINE SCREW CORPORATION 22-42 Barclay St., New Haven, Conn.

NEW PRODUCTS and equipment

time is eliminated; sand life is co trolled; and sand handling is si plified. *Write*: G. E. Smith In 246-C, Washington Rd., Pittsburg 16, Pa. *Phone*: Locust 1-2962.

Cutoff Wheel

Faster cutting in foundry appl cations is the claim made for th wheel. New bonds and bondi processes permit an increase in a rasive grain content and allo grains to be bonded in a poro construction.

Rough abrasive sides provi clearance to maintain wheel spe at best operating efficiency.

Reinforcing layers give the hig tensile strength needed for rugg use. *Write*: Bay State Abrasi Products Co., Westboro, Mas *Phone*: Westboro 433

Full Socket Setscrew

A new setscrew has a sock that extends the full length of t screw. Wire sizes range from No.



A new dimension in motors!

SHORTER Century Performance Rated© MOTORS

SAVE SPACE...
SAVE WEIGHT

This new line of shorter, round-frame, end-mounted motors by Century can give you greater freedom in design and engineering. They meet modern demands for compactness and weight-saving ... with even better performance.

No special mountings are required! These shorter Century motors have full-size NEMA "D" flanges. They are interchangeable with all other popular makes of standard end-mounted motors. The shorter motors are available in sizes from 1 to 15 H.P... in open or totally enclosed fan-cooled frames . . . for vertical or horizontal applications.

For full data, call your nearest Century Sales Office.



Performance Rated© MOTORS
⅛ to 400 H. P.

CENTURY ELECTRIC COMPANY

1806 PINE ST., ST. LOUIS 3, MO. • Offices and Stock Points in Principal Cities

When contamination of products cannot be tolerated



Courtesy of the Patterson-Kelley Co., Inc.

WELD WITH ARCOS

STAINLESS ELECTRODES

This precision blender is used for uniform mixing of vitamins and potent drugs with inactive materials. The same high standard of performance is provided by the Arcos Electrodes used to weld the twin-cones. They provide smooth unbroken joints whose uniform *stainless* and sound mechanical properties are the result of conscientious quality control in their manufacture. When you want stainless welds with properties equal to the material being welded, specify Arcos Electrodes. ARCOS CORPORATION, 1500 South 50th Street, Philadelphia 43, Pa.



NEW PRODUCTS and equipment

to 1 in. in diameter. Hexagonal c multiple spline sockets are avai able.

The through-broached socket a lows the screw to be wrenche from either end. Holding powe equals that of conventional socke setscrews. *Write*: Socket Scre Division, Bristol Co., Waterbur 20, Conn. *Phone*: Plaza 6-4451

High-Lift Pallet Truck

This nesting fork truck is avail able in 2000, 3000 and 4000 lb ca pacities. Lifts go up to 130 in.



The truck has roller-type mast and a low-pressure hydraulic sy tem. Its low-amperage draw give longer battery life. *Write*: Li Trucks Inc., Cincinnati 14, *Phone*: Main 1-4054

Welding Rod and Wire

Braze-welding of 16 and 18-gag mild steel by the metal-arc proce is speeded by Ampco-Trode 10 ele trodes (diameter, 5/64-in.). The give exceptional arc action, leav practically no spatter to clean, hav good penetration, provide stron joints and excellent appearance.

Phos-Trode wire is available 0.045, 1/16, 5/64 and 3/32-in. d ameters. It contains 8 per cent t and is recommended for many bea ing and corrosion-resistant applic tions. It's also used for joinin copper, tin bronzes, brasses, ga vanized iron, cast iron and dissi ilar metals. *Write*: Ampco Met Inc., 1745 S. 38th St., Milwauk 46, Wis. *Phone*: Mitchell 5-3750

NEW Literature

Write directly to the company for a copy

Fastener Catalog

All types of stainless steel fasteners are covered. Specifications and corrosion tables are included—catalog 55A, 24 pages. Star Stainless Screw Co., 655 Union Blvd., Paterson 2, N. J.

Fork Lift Truck

Advantages and specifications of 5000-lb capacity truck are given—pages. Towmotor Corp., 1226 E. 152nd St., Cleveland 10, O.

Can Machinery

A complete line of flanging, beading and thread rolling machinery for medium and high-speed canmaking described—catalog 36B section 4, 0 pages. E. W. Bliss Co., 50 Church St., New York 7, N. Y.

Gamma Ray Projector

Radioactivity is discussed and the advantages of a portable gamma ray unit are given—24 pages. Metal & Thermit Corp., 100 E. 42nd St., New York 17, N. Y.

Surface Grinders

Described are two, high-production, automatic rotary machines—bulletin 147-2, 12 pages. Mattison Machine Works, Rockford, Ill.

Hydraulic Tables

This reference work is for engineers interested in pumping and piping problems—bulletin 50, 28 pages. Aldrich Pump Co., 25 Pine St., Allentown, Pa.

Power Positioners

Performance and construction specifications are given for pneumatic positioners used to control flow, pressure or temperature by operating valves, gates or dampeners—bulletin TP-MFI, 20 pages. Hagan Corp., 323 Fourth Ave., Pittsburgh, Pa.

Strip Coil Annealing

Described are installations for the high convection annealing of strip steel coils—bulletin LW-855, 8 pages. Lee Wilson Engineering Co. Inc., 20005 W. Lake, Cleveland, O.

Multiple-Way Machine Tools

Described are automatic machines built to meet specific production needs of drilling, reaming, tapping,

How to *guarantee* yourself the positive benefits of submerged arc welding



Courtesy of Byron Jackson, Division Borg-Warner, Los Angeles, Calif.

WELD WITH ARCOS

STAINLESS WELDING RODS

To save time and money, submerged arc welding was used to overlay type 308 stainless weld metal on the inside of this barrel of a boiler pump. Arcos Chromar Coiled Wire helped guarantee these savings through fast, easy deposition with minimum dilution. On your own jobs, Chromar Coiled Wire . . . *quality controlled* . . . teamed with the time-saving advantages of submerged arc welding will keep your welding costs down and the quality of your welds high. ARCOS CORPORATION, 1500 South 50th Street, Philadelphia 43, Pa.



When you have "tough-to-make" cold heading jobs on your production schedule, it will pay you to consider the outstanding advantages offered by Keystone "Special Processed" Wire.

The superior grain flow characteristics of this wire provides the necessary upsetting and die forming qualities to withstand the terrific displacement of metal during the most difficult cold heading process. The structural soundness and uniformity of "Special Processed" Wire further proves itself through trouble-free machine operation, longer die life, and finished products of the highest quality.

If you have a special wire problem . . . large or small . . . let us help you solve it. Contact your Keystone representative or write.

Keystone Steel & Wire Company
Peoria 7, Illinois
Industrial Wire Specialists

NEW LITERATURE

facing and milling—8 pages. Dept M-W, W. F. & John Barnes Co., 301 S. Water St., Rockford, Ill.

Industrial Cleaning

Here is information to help you find the proper method, machine and material for cleaning, decarbonizing, bonderizing, stripping, blackening, pickling and processing of metal parts—bulletin 10,000-G, 34 pages. Dept. S, Equipment Division, Magnus Chemical Co. Inc., Garwood, N. J.

Clay Guns

Clay pressure up to 600 psi is provided by guns for plugging tapping holes of blast furnaces and large electrical furnaces—4 pages. William M. Bailey Co., 1221 Banksville Rd., Pittsburgh, Pa.

Pneumatic Regulators

Filters, regulators, relays, purge assemblies and control panels are described—bulletin H-2, 8 pages. Conoflow Corp., 2100 Arch St., Philadelphia 3, Pa.

Vibration Control

Spring and pad mountings for vibration control are illustrated in typical installations—catalog G-55, 8 pages. Vibration Mountings Inc., 76-17 Queens Blvd., Elmhurst, N. Y.

Ferrous Chart

Represented are the chief characteristics of steel up to 2900° F. Tempil° Corp., 132 W. 22nd St., New York 11, N. Y.

Pivoted Hook Carrier

Here is information on a 20,000-lb capacity carrier—4 pages. Ross Carrier Division, Clark Equipment Co., Benton Harbor, Mich.

NEW BOOKS

Lessons in Arc Welding, Hobart Trade School Inc., Hobart Square, Troy, O. 200 pages, $1. A series of practical exercises and instructions for developing and improving the technique of arc welders; includes information of value to those designing parts for fabrication.

Principles of Metal Casting, Richard W. Heine and Philip C. Rosenthal, McGraw-Hill Book Co., 330 W. 42nd St., New York 36, N. Y. 639 pages, $7.50.
A comprehensive treatment of metal casting that covers molding and metallurgical processes.

Market Outlook

TIGHT steel supply right through the first half of 1956 appears increasingly certain.

Heavy carry-over tonnage, indicated for the year end in all the major products, will take up a substantial part of first quarter output—four to six weeks of production, at least. This means considerable business will be shoved into second quarter schedules, resulting in a much heavier mill order load during that period.

BULLISH VIEW—Commenting on the 1956 outlook, Bay Estes, commercial research director, U. S. Steel Corp., says: "The general accumulation of inventory, which began in first quarter of 1955, is expected to continue at a substantial level through midyear of 1956 and taper off in the last half of the year."

He predicts a decline in automobile production next year to a possible 7 million units. Expected declines in residential construction will be offset by increases in other classes of building.

CONSOLATION—For what consolation it may afford steel buyers, supply conditions in the first and second quarters next year promise to be no worse than they are now. With most producers, they should be much better than they were in the third quarter this year.

During the third quarter, mills were heavily oversold because expected cutbacks in automotive requirements failed to materialize. As far back as late first quarter, producers began booking extra tonnage as insurance against a summer lull in automobiles and a lag in demand attending vacations and hot weather. As things turned out, there was scarcely any letdown in demand for any reason. Mills have been trying to dig themselves out ever since—a job made difficult by uninterrupted high demand.

STILL OVERLOADED—Mills still have a long way to go before demand and supply are brought into balance. This is true not only of sheets but also of bars and in varying degrees of other steel products. Automotive requirements are reflected in continued strong demand for sheets and bars. Heavy demand for plates and shapes is due to a constant building up of needs in construction and equipment industries.

TO FARE BETTER—In plates, any slackening that might have been experienced the last several months would have been more than offset by the sudden sharp expansion in the railroad equipment program. Carbuilders have not been able to get anything like the tonnage they would like for the reason they were late in placing orders with the mills. They will fare better in first half of next year.

PRICES—Except for a revision in size extras on hot-rolled carbon steel wire rods in sizes 35/64-in. and smaller (announced by operating divisions of U. S. Steel Corp.), prices are firm. This change resulted in increases of $1 to $4 per ton. STEEL's arithmetical price composite on steelmaking grades of scrap advanced 17 cents last week to $45.17.

PRODUCTION—The steel mills have been producing at an all-time record rate, operating at 100 per cent of capacity and producing 2,413,000 net tons of ingots in the week ended Oct. 30, according to the American Iron & Steel Institute. Last week STEEL estimated the national ingot rate at 98 per cent of capacity.

NATIONAL STEELWORKS OPERATIONS



DISTRICT INGOT RATES

(Percentage of Capacity Engaged)

	Week Ended Nov. 6	Change	Same Week 1954	Same Week 1953
Pittsburgh	103	— 1*	73.5	93
Chicago	98.5	0	79	100.5
Mid-Atlantic	97.5	— 0.5	70	96
Youngstown	97	— 3	74	97
Wheeling	98.5	— 1.5	81	98
Cleveland	101	— 2.5*	87	100.5
Buffalo	105	0	90	106.5
Birmingham	94	0	64	96.5
New England	91	+ 1	59	80
Cincinnati	90	0	76.5	67
St. Louis	106	+ 9	91	89.5
Detroit	97	— 3.5	80	97.5
Western	98	+ 7	86	104
National Rate	98	0	75.5	93.5

INGOT PRODUCTION‡

	Week Ended Nov. 6	Week Ago	Month Ago	Year Ago
INDEX (1947-1949=100)	147.4†	150.2	145.3	113.4
NET TONS (In thousands)	2,368†	2,413	2,334	1,822

*Change from preceding week's revised rate. †Estimated. ‡Amer. Iron & Steel Institute. Weekly capacity (net tons): 2,413,278 in 1955; 2,384,549 in 1954; 2,254,459 in 1953.

Fabricating Outlook—p. 81 Technical Outlook—p. 129

Price Indexes and Composites

FINISHED STEEL PRICE INDEX (Bureau of Labor Statistics)

	Nov. 1 1955	Oct. 25 1955	Month Ago	Oct. Average
(1947-1949=100)	154.5	154.5	154.5	154.5

AVERAGE PRICES OF STEEL (Bureau of Labor Statistics)

Week Ended Nov. 1

Prices include mill base prices and typical extras and deductions. Units are 100 lb except where otherwise noted in parenthesis. For complete description of the following products and extras and deductions applicable to them write to STEEL.

Rails, Standard, No. 1	$4.800	Sheets, Electrical	$10.200
Rails, Light, 40 lb	6.217	Strip, C.R., Carbon	7.993
Tie Plates	5.625	Strip, C.R., Stainless, 430 (lb)	0.444
Axles, Railway	8.000	Strip, H.R., Carbon	5.350
Wheels, Freight Car, 33 in. (per wheel)	52.50	Pipe, Black, Buttweld (100 ft)	16.366
Plates, Carbon	4.950	Pipe, Galv., Buttweld (100 ft)	19.971
Structural Shapes	4.867	Pipe, Line (100 ft)	158.925
Bars, Tool Steel, Carbon (lb)	0.460	Casing, Oil Well, Carbon (100 ft)	165.120
Bars, Tool Steel Alloy, Oil Hardening Die (lb)	0.560	Casing, Oil Well, Alloy (100 ft)	244.670
Bars, Tool Steel, H.R., Alloy, High Speed W 6.75, Cr 4.5, V 2.1, Mo 5.5, C 0.60 (lb)	1.185	Tubes, Boiler (100 ft)	39.470
Bars, Tool Steel, H.R. Alloy, High Speed W-18, Cr 4, V 1 (lb)	1.680	Tubing, Mechanical, Carbon	20.980
Bars, H.R., Alloy	9.375	Tubing, Mechanical, Stainless, 304 (100 ft)	178.897
Bars, H.R., Stainless, 303 (lb)	0.450	Tin Plate, Hot-dipped, 1.25 lb	8.933
Bars, H.R., Carbon	5.350	Tin Plate, Electrolytic, 0.25 lb	7.633
Bars, Reinforcing	5.313	Black Plate, Canmaking Quality	6.733
Bars, C.F., Carbon	8.660	Wire, Drawn, Carbon	8.575
Bars, C.F., Alloy	12.175	Wire, Drawn, Stainless 430 (lb)	0.578
Bars, C.F., Stainless, 302 (lb)	0.468	Bale ties (bundle)	6.473
Sheets, H.R. Carbon	5.145	Nails, Wire, 8d Common	8.618
Sheets, C.R., Carbon	6.239	Wire, Barbed (80-rod spool)	7.847
Sheets, Galvanized	7.690	Woven Wire Fence (20-rod roll)	18.635
Sheets, C.R., Stainless, 302 (lb)	0.588		

STEEL's FINISHED STEEL PRICE INDEX*

	Nov. 2 1955	Week Ago	Month Ago	Year Ago	5 Yrs. Ago
Index (1935-39 av.=100)	208.90	208.90	208.90	194.53	157.76
Index in cents per lb	5.659	5.659	5.659	5.270	4.274

STEEL's ARITHMETICAL PRICE COMPOSITES

Finished Steel, NT*	$128.14	$128.14	$128.14	$117.95	$95.09
No. 2 Fdry, Pig Iron, GT	58.99	58.99	58.99	56.64	49.35
Basic Pig Iron, GT	58.49	58.49	58.49	56.04	48.28
Malleable Pig Iron, GT	59.77	59.77	59.77	57.27	49.63
Steelmaking Scrap, GT	45.17	45.00	45.33	33.67	41.67

*For explanation of weighted index see STEEL, Sept. 19, 1949, p. 54; of arithmetical price composite, STEEL, Sept. 1, 1952, p. 130.

Comparison of Prices

Comparative prices by districts, in cents per pound except as o wise noted. Delivered prices based on nearest production point.

FINISHED STEEL	Nov. 2 1955	Week Ago	Month Ago	Year Ago	5
Bars, H.R., Pittsburgh	4.65	4.65	4.65	4.30	
Bars, H.R., Chicago	4.65	4.65	4.65	4.30	
Bars, H.R., deld. Philadelphia	4.90	4.90	4.90	4.55	
Bars, C.F., Pittsburgh	5.90	5.90	5.90	5.40	
Shapes Std., Pittsburgh	4.60	4.60	4.60	4.25	
Shapes, Std., Chicago	4.60	4.60	4.60	4.25	
Shapes, deld., Philadelphia	4.88	4.88	4.88	4.53	
Plates, Pittsburgh	4.50	4.50	4.50	4.225	
Plates, Chicago	4.50	4.50	4.50	4.225	
Plates, Coatesville, Pa.	4.80	4.80	4.50	4.225	
Plates, Sparrows Point, Md.	4.50	4.50	4.50	4.225	
Plates, Claymont, Del.	4.80	4.80	4.50	4.225	
Sheets, H.R., Pittsburgh	4.325	4.325	4.325	4.05	
Sheets, H.R., Chicago	4.325	4.325	4.325	4.05	
Sheets, C.R., Pittsburgh	5.325	5.325	5.325	4.95	
Sheets, C.R., Chicago	5.325	5.325	5.325	4.95	
Sheets, C.R., Detriot	5.325-5.425	5.325-5.425	5.325-5.425	5.10	
Sheets, Galv., Pittsburgh	5.85	5.85	5.85	5.45	
Strip, H.R., Pittsburgh	4.325	4.325	4.325	4.05	3.50
Strip, H.R., Chicago	4.325	4.325	4.325	4.05	
Strip, C.R., Pittsburgh	6.25	6.25	6.25	5.75	4.15
Strip, C.R., Chicago	6.35	6.35	6.35	6.00	
Strip, C.R., Detroit	6.35	6.35	6.35	5.60-5.90	4.35
Wire, Basic, Pittsburgh	6.25	6.25	6.25	5.75	4.50
Nails, Wire, Pittsburgh	7.60	7.60	7.60	6.85	5.30
Tin plate (1.50 lb),box, Pitts.	$9.45	$9.45	$9.05	$9.05	$
SEMIFINISHED STEEL					
Billets, Forging, Pitts. (NT)	$84.50	$84.50	$84.50	$78.00	$
Wire rods, 7/32-5/8" Pitts.	5.025	5.025	5.025	4.675	
PIG IRON, Gross Ton					
Bessemer, Pitts.	$59.50	$59.50	$59.50	$57.00	$
Basic, Valley	58.50	58.50	58.50	56.00	
Basic, deld. Phila.	62.16	62.16	59.16	59.66	5
No. 2 Fdry, Pitts.	59.00	59.00	59.00	56.50	
No. 2 Fdry, Chicago	59.00	59.00	59.00	56.50	
No. 2 Fdry, Valley	59.00	59.00	59.00	56.50	
No. 2 Fdry, deld. Phila.	62.66	62.66	59.66	50.16	5
No. 2 Fdry, Birm.	55.00	55.00	55.00	52.88	4
No. 2 Fdry (Birm.) deld. Cin.	62.70	62.70	62.70	60.58	5
Malleable, Valley	59.00	59.00	59.00	56.50	
Malleable, Chicago	59.00	59.00	59.00	56.50	
Ferromanganese, Duquesne	190.00†	190.00†	190.00†	190.00†	17

†74-76% Mn, net ton. *75-82% Mn, gross ton, Etna, Pa.

SCRAP, Gross Ton (Including broker's commission)

No. 1 Heavy Melt, Pitts.	$44.50	$44.50	$43.50	$34.50	$
No. 1 Heavy Melt, E. Pa.	46.50	46.50	46.50	33.50	
No. 1 Heavy Melt, Chicago	44.50	44.00	45.00	33.00	
No. 1 Heavy Melt, Valley	48.00	48.00	46.50	35.50	
No. 1 Heavy Melt, Cleve.	45.50	45.50	44.00	33.50	
No. 1 Heavy Melt, Buffalo	43.50	38.50	38.50	30.50	
Rails, Rerolling, Chicago	65.50	65.50	64.50	54.50	
No. 1 Cast, Chicago	47.50	47.50	46.50	39.50	
COKE, Net Ton					
Beehive, Furn, Connlsvl.	$13.625	$13.625	$13.625	$13.75	$
Beehive, Fdry, Connlsvl.	16.50	16.50	16.50	16.75	
Oven, Fdry, Chicago	25.75	25.75	25.75	24.50	

Daily Nonferrous Price Record

	Price Nov. 2	Last Change	Previous Price	Oct. Avg.	Sept. Avg.	Nov. 1954 Avg.
Copper	43.00–45.00	Oct. 7, 1955	43.00–50.00	44.594	45.380	30.000
Lead	15.30	Sept. 26, 1955	14.80	15.300	14.920	14.800
Zinc	13.00	Oct. 21, 1955	13.00–13.50	13.020	12.940	11.500
Tin	96.75	Nov. 2, 1955	97.00	96.230	96.565	91.196
Nickel	64.50	Nov. 24, 1954	60.00	64.500	64.500	60.000
Aluminum	24.40	Aug. 8, 1955	23.20–24.40	24.400	24.400	22.200
Magnesium	32.50	Aug. 16, 1955	28.50	32.500	32.500	27.000

Quotations in cents per pound base COPPER, deld. Conn. Valley; LEAD, mon grade, deld. St. Louis; prime western, E. St. Louis; Straits, deld, New York; NICKEL, trolytic cathodes, 99.9%, base s refinery, unpacked; ALUMINUM, pr ingots, 99 + %, deld.; MAGNE 99.8%, Freeport, Tex.

What You Can Use the Markets Section for:

- **A source of price information.**
  Current prices are reported each week. Price changes are shown in italics. Price trends are shown in tables of indexes and comparisons.
- **A directory of producing points.**
  Want to know who makes something, or where it is made? The steel price tables alphabetically list the cities of production and indicate the producing company. If you are a buyer, you may want to make a map showing comparative distances of sources of supply and to help you compute freight costs. If you are a seller of supplies you can make a map to spot your sales possibilities.
- **A source of price data for making your own comparisons.**
  Maybe you want to keep a continuous record of pri spread between various forms of steel. You can get yo base price information from STEEL's price tables.
- **A source of information on market trends.**
  Newsy items tell you about the supply-demand situatio of materials, including iron and steel, nonferrous meta and scrap. Other articles analyze special situations of i terest and importance to you.
- **Reports on iron and steel production, and materials and pro uct shipments.**

A NEW PLANT

TOLEDO

OR A NEW

20th Century

persuasive abrasive

Recently we put our new Toledo, Ohio plant into production. It is specifically designed for you.

From laboratory microscopes to grading screens, every facility of this plant has been selected to furnish you the best metallic abrasive for the lowest possible price.

This modern factory — The Toledo Steel Shot Division — will be devoted to the production of a brand new steel shot, Toledo REALSTEEL — the newest member in our complete line of 20th Century quality shot and grit.

Write for our newest literature.

The CLEVELAND METAL ABRASIVE Co.

802 East 67th St., Cleveland 8, Ohio
Howell Works: Howell, Michigan
Toledo Steel Shot Division: Toledo, Ohio

One of the world's largest producers of quality shot, grit and powder—
Hard Iron — Malleable (*Normaiized) — Cut Wire — Cast Steel (Realsteel)
*Copyrighted trade name

Nonferrous Metals

Despite metal shortages and labor difficulties, nonferrous companies have chalked up a record nine months in sales and profits. Fourth quarter outlook is even brighter

Nonferrous Metal Prices, Pages 188 & 189

SALES AND PROFITS of the nonferrous industries for the first nine months of 1955 are running 25.4 per cent and 52.9 per cent, respectively, ahead of the same period last year. Prospects for the fourth quarter are brighter than ever.

Of the companies whose third-quarter reports are available, only one showed a decline in its profits in the 1955 period. Bridgeport Brass Co. reported a decline from $3,753,411 last year to $3,462,150 this year because of the heavy expenses involved in starting up the company's aluminum facilities in Adrian, Mich., earlier in the year. However, that facility is beginning to pay its own way, and third-quarter profits showed an increase over third quarter, 1954. Two other companies showed good profits for the first nine months after suffering losses in the first three quarters last year.

Scarcities Hurt—Despite the shortage of various metals, especially acute during the third quarter, most fabricators showed moderate to large gains in both sales and profits. Basic metal producers showed even larger percentage gains, largely because of the higher prices prevailing since midyear. Generally, prices are expected to remain high through the fourth quarter at least. In addition, supply of some of the scarcer metals, such as copper and nickel, is expected to improve because of greater production, or government stockpile diversions, or both.

Titanium Sponge Price Down

The price of titanium metal sponge has been reduced for the fourth time in less than two years. Grade A-1 sponge is now $3.75 a pound, compared with $5 a pound in March, 1954. This is a decline of 20 cents a pound from the previous price, effective Nov. 1. Grade A-2 was reduced from $3.50 to $3.25 a pound; grade A-2 fines from $3 to $2.75 a pound.

Dr. J. B. Sutton, specialty products sales manager for the pigment department of E. I. du Pont de Nemours & Co. Inc., said: "Improvements in manufacturing processes and the broadening of commercial markets should cause this trend to continue." He also said that the ductility and workability of grade A-1 sponge has been improved.

Magnesium Outlook Brightens

Based on an exhaustive test run in its new supersonic ramjet engine, Marquardt Aircraft Co. believes magnesium alloy HK31 (3 per cent thorium and 0.75 per cent zirconium) is in for greatly expanded use in the missile and engine field. That's what Alan V. Levy, superviser of materials and process section of Marquardt, told the 11th annual convention of the Magnesium Association.

STEEL's Metal Price Averages for Oct., 1955
(Cents per lb)

Electrolytic Copper, deld. Connecticut	44.594
Lead, St. Louis	15.300
Prime Western Zinc, E. St. Louis, Ill.	13.020
Straits Tin, New York	96.230
Primary Aluminum Ingots, deld.	24.400
Magnesium, Freeport, Tex.	32.500
Nickel, f.o.b. refinery	64.500

Using HK31, Marquardt fabricated the diffuser and forward aerodynamic section of an advanced ramjet engine which has to operate at temperatures in excess of 600° F. The engine requirements called for the use of sheet and casting applications, fusion welding, protective coating, joining and all the common types of fabrication used in aircraft construction, with the exception of resistance welding and complex formed surfaces. Mr. Levy reported: "We feel that the material has behaved well, considering its state of development."

The convention also got some inside information on the use of magnesium in the German Volkswagen auto. Both the American magnesium and auto industries have been watching the development for several years. The magnesium people see it as a new tonnage market for their product. The automakers see it as a means of cutting weight and costs.

Ludwig C. Boehner, chief engineer of Volkswagenwerk, told the meeting that the use of magnesium has "contributed to the successful production of our light and economical car." By using 36 lb of magnesium casting in the engine, clutch and transmission housing, about 110 lb have been saved in the over-all weight of the car.

More Aluminum Postponements

International complications are further clouding up the domestic aluminum picture. Arthur Flemming, director of the Office of Defense Mobilization, originally ordered delivery of 50 million lb of aluminum to the government. About 28 million lb were to be for the stockpile, while 22 million lb were to help relieve the metal shortage in Great Britain. Aluminum Co. of America and Kaiser Aluminum & Chemical Corp. were to forgive shipments due from Aluminium Ltd., so that Aluminium, in turn, could ship the metal to England.

The only hitch is that Alcoa and Kaiser haven't been getting enough metal from Canada to make up 2 million lb in the fourth quarter. Power failures and drouth have reduced that country's production. So it looks like Mr. Flemming will postpone the payment of this metal until the spring, when aluminum production is normally higher.

The aluminum industry also has asked ODM to forgive shipments of the light metal to the stockpile in the first quarter of 1956. Because it looks like the present shortage will go right on into next year, the request will probably be granted.

Nickel Doles Continue

The Office of Defense Mobilization has announced another "gift" from the stockpile for nickel users. But this one is really going to cost consumers. For both November and December, 1.1 million lb of ferronickel and nickel ingot will be released in addition to the 3 million lb a month previously announced. This $1 a pound variety of the metal is all that's left for the government to give out. A total of nearly 24 million lb of the scarce metal have been diverted from stockpile delivery since Mar. 1, or about 10 per cent of the total supply.

American Zinc and its products

from A *to* Z





DUAL OPERATION AT HILLSBORO, ILLINOIS

(1) The Oxide Division supplies American process lead-free and leaded zinc oxide, as well as French process zinc oxide. (2) In the Metal Division, Prime Western, Select, Brass Special, Intermediate and High Grade slab zinc are produced. For complete picture of American Zinc operations, see map above.

PRODUCERS OF

ALL GRADES OF SLAB ZINC
ZINC ANODES (Plating & Galvanic)
METALLIC CADMIUM
SULPHURIC ACID
LEAD-FREE and LEADED ZINC OXIDES
ZINC CARBONATE
GERMANIUM DIOXIDE
AGRICULTURAL LIMESTONE
CRUSHED STONE

Distributors for

American Zinc Sales Company

AMERICAN ZINC, LEAD & SMELTING COMPANY

Columbus, Ohio • Chicago • St. Louis • New York • Detroit • Pittsburgh

Nonferrous Metals

Cents per pound, carlots, except as otherwise noted.

PRIMARY METALS AND ALLOYS

Aluminum: 99 + %, ingots 24.40, pigs 22.50. 10,000 lb or more, f.o.b. shipping point. Freight allowed on 500 lb or more.

Aluminum Alloy: No. 13, 12% Si, 26.2; No. 43, 5% Si, 26.00; No. 142, 4% Cu, 1.5% Mg, 2% Ni, 28.20; No. 195, 4.5% Cu, 0.8% Si, 27.60; No. 214, 3.8% Mg, 27.80; No. 356, 7% Si, 0.3% Mg, 26.20.

Antimony: R.M.M. brand, 99.5%, 33.00, Lone Star brand, 33.50, f.o.b. Laredo, Tex., in bulk. Foreign brands, 99.5%, 27.50-28.50, New York, duty paid, 10.000 lb or more.

Beryllium: 97%, lump or beads, $71.50 per lb, f.o.b. Cleveland or Reading, Pa.

Beryllium Aluminum: 5% Be, $72.75 per lb of contained Be, f.o.b. Reading, Pa., Elmore, O.

Beryllium Copper: 3.75-4.25% Be, $43 per lb of contained Be, with balance as Cu at market price on shipment date, f.o.b. Reading, Pa., or Elmore, O.

Bismuth: $2.25 per lb, ton lots.

Cadmium: Sticks and bars, $1.70 per lb, deld.

Cobalt: 97-99%, $2.60 per lb for 550-lb keg; $2.62 per lb for 100-lb case; $2.67 per lb under 100 lb.

Columbium: Powder, $119.20 per lb, nom.

Copper: Electrolytic, 43.00 deld. Conn. Valley; 43.00 deld. Midwest; custom smelters, 45.00 deld.; Lake, 43.00 deld.; Fire refined, 42.75 deld.

Germanium: 99.9%, $295 per lb, nom.

Gold: U. S. Treasury, $35 per oz.

Indium: 99.9%, $2.25 per troy oz.

Iridium: $100-$120 nom. per troy oz.

Lead: Common, 15.30, chemical, 15.40, corroding, 15.40, St. Louis, New York basis, add 0.20.

Lithium: 99%+, cups or ingot, $11.50; rod, $13.50; shot or wire, $14.50, f.o.b. Minneapolis, 100 lb lots.

Magnesium: 99.8%, self-palletizing pig, 32.50; notched ingot, 33.25, 10.000 lb or more, f.o.b. Freeport, Tex. For Port Newark, N. J., add 1.40 for pig and 1.45 for ingot; for Madison, Ill., add 1.20 for pig and 1.25 for ingot; for Los Angeles, add 2.00 for both pig and ingot. Sticks 1.3 in. diameter, 53.00, 100 to 4999 lb, f.o.b. Madison, Ill.

Magnesium Alloys: AZ91C and alloys C, G, H and R, 36.00; alloy M, 38.00, 10.000 lb or more, f.o.b. Freeport, Tex. For Port Newark, N. J., add 1.40; for Madison, Ill., add 0.50; for Los Angeles, add 2.50.

Mercury: Open market, spot, New York, $278-$283 per 76-lb flask.

Molybdenum: Powder 99% hydrogen reduced, $3-$3.25 per lb; pressed ingot, $4.06 per lb; sintered ingot, $5.53 per lb.

Nickel: Electrolytic cathodes, sheets (4 x 4 in. and larger), unpacked, 64.50; 10-lb pigs, unpacked, 67.65; "XX" nickel shot, 69.00; "F" nickel shot or ingots for addition to cast iron, 64.50; prices f.o.b. Port Colborne, Ont., including import duty. New York basis, add 0.92.

Osmium: $80-$100, nom., per troy oz.

Palladium: $22-$24 per troy oz.

Platinum: $91-$102 per troy oz from refineries.

Radium: $16-$21.50 per mg radium content, depending on quantity.

Rhodium: $118-$125 per troy oz.

Ruthenium: $45-$55 per troy oz.

Selenium: 99.5%, $9-$10 per lb.

Silver: Open market, 91.625 per troy oz.

Sodium: 16.50, c.l.; 17.00, l.c.l.

Tantalum: Sheet, rod, $68.70 per lb; powder, $56.63 per lb.

Tellurium: $1.75 per lb.

Thallium: $12.50 per lb.

Tin: Straits, N. Y., spot 97.00; prompt, 96.875.

Titanium: Sponge, 99.3+%, grade A-1 ductile (0.3% Fe max), $3.75, grade A-2 (0.5% Fe max), $3.25 per pound.

Tungsten: Powder, 98.8%, carbon, reduced, 1000-lb lots, $4.50 per lb, nom., f.o.b. shipping point; less than 1000 lb add 15.00; 99+% hydrogen reduced, $4.65. Treated ingots, $6.70.

Zinc: Prime Western, 13.00; brass special, 13.25; intermediate, 13.50, East St. Louis, freight allowed over 0.50 per pound. High grade, 14.35; special high grade 14.50-14.75, deld. Diecasting alloy ingot No. 3, 17.50; No. 2, 18.50; No. 5, 18.00, deld.

Zirconium: Ingots, commercial grade, $14.40 per lb; low-hafnium reactor grade, $23.07. Sponge, $10 per lb. Powder electronics grade, $15 per lb; flash grade, $11.50.

(Note: Chromium, manganese and silicon metals are listed in ferroalloy section.)

SECONDARY METALS AND ALLOYS

Aluminum Ingot: Piston alloys, 31.50-33.50; No. 12 foundry alloy (No. 2 grade) 30.50-30.75; 5% silicon alloy, 0.60 Cu max, 32.00-32.75; 13 alloy, 0.60 Cu max, 32.00-32.75; 195 alloy, 32.00-32.75; 108 alloy, 30.50. Steel deoxidizing grades, notch bars, granulated or shot: Grade 1, 31.25-32.25; grade 2, 30.25-31.25; grade 3, 29.50-30.50; grade 4, 29.00-30.00.

Brass Ingot: Red brass No. 115, 41.00; tin bronze No. 225, 54.00; No. 245, 47.25; high-leaded tin bronze No. 305, 44.75; No. 1 yellow No. 405, 32.75; manganese bronze No. 421, 36.25.

Magnesium Alloy Ingot: AZ63A, 34.00; AZ91B, 34.00; AZ91C, 34.00; AZ92A, 34.00.

NONFERROUS MILL PRODUCTS

BERYLLIUM COPPER

(Base prices per lb, plus mill extras, 2000 to 5000 lb, f.o.b. Temple, Pa.; nominal 1.9% Be alloy) Strip, $1.84; rod, bar, wire, $1.81.

COPPER WIRE

Bare, soft, f.o.b. eastern mills, 100,000-lb lots, 48.35; 30,000-lb lots 48.88; l.c.l., 48.98. Weatherproof, 100,000-lb lots, 46.03; 30,000-lb lots, 46.28; l.c.l., 46.78. Magnetic wire deld., 15,000 lb or more, 55.52; l.c.l., 56.27.

LEAD

(Prices to jobbers, f.o.b. Buffalo, Cleveland, Pittsburgh) Sheets, full rolls, 140 sq ft or more, $21 per cwt; pipe, full coils, $21 per cwt; traps and bends, list prices plus 30%.

TITANIUM

(Prices per lb, 10,000 lb and over, f.o.b. mill) Sheets, $14.00-$14.50; sheared mill plate, $11.00; strip, $14.00-$14.50; wire, $10.00-$10.50; forging billets, $8.75; hot-rolled and forged bars, $8.75.

ZINC

(Prices per lb, c.l., f.o.b. mill) Sheets, 23.00; ribbon zinc in coils, 20.50; plates 19.50-22.25.

ZIRCONIUM

Plate, $22; H.R. strip, $19; C.R. strip, $29; forged or H.R. bars, $17; wire, 0.015 in., 1.00c per linear foot.

NICKEL, MONEL, INCONEL

	"A" Nickel	Monel	Inconel
Sheets, C.R.	102	83	99
Strip, C.R.	102	92	125
Plate, H.R.	97	87	95
Rod, Shapes H.R.	87	74	93
Seamless Tubes	122	110	153
Shot, Blocks	...	71	...

ALUMINUM

Screw Machine Stock: 30,000 lb base.

Diam. (in.) or across flats	Round 2011-T3	Round 2017-T4	Hexagonal 2011-T3	Hexagonal 2017-T4
Drawn				
0.125	67.9	66.4	...	...
0.156-0.172	57.5	55.9	...	...
0.188	57.5	55.9	...	71.7
0.219-0.234	54.5	52.9	...	...
0.250-0.281	54.5	52.9	...	68.4
0.313	54.5	52.9	...	65.2
Cold-finished				
0.375-0.547	53.4	51.4	63.7	61.3
0.563-0.688	53.4	51.4	60.6	57.5
0.750-1.000	52.1	50.1	55.4	54.2
1.063	52.1	50.1	...	52.3
1.125-1.500	50.1	48.2	53.6	52.3
Rolled				
1.563	48.8	46.9	...	...
1.625-2.000	48.2	46.2	...	50.5
2.125-2.500	47.0	45.0	...	...
2.563-3.375	45.6	43.6	...	...

ALUMINUM

Sheets and Circles: 1100 and 3003 mill finish (30,000 lb base; freight allowed)

Thickness Range Inches	Flat Sheet	Flat Sheet Circles*	Coiled Sheet	Coiled Sheet Circles†
0.249-0.136	37.5	42.3	...	.
0.135-0.096	38.0	43.2	...	.
0.095-0.077	38.7	44.2	36.1	41
0.076-0.061	39.3	45.1	36.3	41
0.060-0.048	39.9	45.6	36.7	42
0.047-0.038	40.4	46.5	37.2	42
0.037-0.030	40.8	47.0	37.6	43
0.029-0.024	41.4	47.5	37.9	43
0.023-0.019	42.2	49.0	38.8	44
0.018-0.017	43.0	...	39.4	45
0.016-0.015	43.9	...	40.2	46
0.014	44.9	...	41.2	47
0.013-0.012	46.1	...	41.9	48
0.011	47.1	...	43.1	50
0.010-0.0095	48.4	...	44.3	52
0.009-0.0085	49.7	...	45.8	54
0.008-0.0075	51.3	...	47.0	56
0.007	52.8	...	48.5	58
0.006	54.4	...	49.9	63

*48 in. max diam. †26 in. max diam.

ALUMINUM

Plates and Circles: Thickness 0.250-3 in., 24-60 in. width or diam. 72-240 in. lengths.

Alloy	Plate Base	Circle Base
1100-F, 3003-F	36.5	40.8
5050-F	37.6	41.9
3004-F	38.6	43.8
5052-F	39.9	45.2
6061-T6	41.1	46.0
2024-T4*	43.6	49.9
7075-T6*	51.4	58.5

*24-48 in. widths or diam, 72-180 in. lengths

ALUMINUM

Forging Stock: Round, Class 1, 39.10-50.10 in specific lengths 36-144 in., diameters 0.375-8 in. Rectangles and squares, Class 1, 43.00-56.20 in random lengths, 0.375-4 in. thick, widths 0.750-10 in.

Pipe: A.S.A. Schedule 40, alloy 6063-T6, 20-ft lengths, plain ends, 90,000-lb base, per 100 ft

Nom. Pipe Size (in.)		Nom. Pipe Size (in.)	
¾	$16.85	2	$ 51.9
1	26.50	4	143.0
1¼	35.85	6	256.7
1½	42.90	8	386.3

MAGNESIUM

Sheet: AZ31, commercial grade, 0.032 in. 99c; 0.064 in., 78.00c; 0.125 in., 63.50c, 30,000 lb and over, f.o.b. mill.

Plate: AZ31, 61.00c, 30,000 lb or more, 0.25 in. and over, widths 24-60 in., lengths 72-18 in.; tread plate, 64.00c, 30,000 lb or more. ¼ in. thick, widths 24-60 in., lengths 60-192 in. tooling plate, 66.00c, 30,000 lbs or more, .25-3.000 in., widths 60-72 in., lengths 72-180 i

Extrusions: AZ31 commercial grade, rectangles, ¼ x 2 in., 64.70c; 1 x 4 in., 69.50c. Ro 1 in., 61.50c; 2 in., 59.00c. Tubing, 1 in. O x 0.065 in., 82.50c; Angles, 1 x 1 x ⅛-in 68.40c; 2 x 2 x ¼-in., 62.50c. Channels, in., 63.40c. I-beams, 5 in., 62.70c.

NONFERROUS SCRAP

DEALER'S BUYING PRICES

(Cents per pound, New York, in ton lots)

Aluminum: 1100 clippings, 19.50; old sheet 16.50-18.00; borings and turnings, 11.00-11.5 crankcases, 16.50-18.00; industrial castings 16.50-18.00.

Copper and Brass: No. 1 heavy copper a wire, 35.00-36.00; No. 2 heavy copper a wire, 34.00-34.50; light copper, 31.50-32.5 No. 1 composition red brass, 28.00-29.00; N 1 composition turnings, 26.00-28.00; yell

BRASS MILL PRICES

	MILL PRODUCTS a				SCRAP ALLOWANCES	
	Sheet, Strip, Plate	Rod	Wire	Seamless Tube	Clean Heavy	Rod Ends	Clean Turnin
Copper	62.76b	60.36c	....	62.82	39.000	39.000	38.25
Yellow Brass	52.27	42.41d	52.81	55.18	28.875	28.625	26.75
Red Brass, 85%	58.09	58.03	58.63	60.90	34.250	34.000	33.50
Low Brass, 80%	56.55	56.49	57.09	59.36	32.750	32.250	31.75
Naval Brass	55.63	49.94	62.69	58.79	26.750	26.500	26.00
Com. Bronze, 90%	60.18	60.12	60.72	62.74	35.750	35.500	35.00
Nickel Silver, 10%	66.00	68.33g	68.33	....	32.500	32.250	16.25
Phos. Bronze, A, 5%	80.99	81.49	81.49	82.67	39.250	39.000	38.00
Silicon Bronze	66.54	65.73	66.58	68.68e	37.625	37.375	36.87
Manganese Bronze	59.37	53.38	63.82	....	27.000	26.750	25.75
Muntz Metal	53.74	49.55	....	....	27.000	26.750	26.25

a. Cents per lb, f.o.b. mill; freight allowed on 500 lb or more. b. Hot-rolled. c. Cold-drawn d. Free cutting. e. 3% silicon. f. Prices in cents per lb for less than 20,000 lb, f.o.b. shipping point. On lots over 20,000 lb at one time, of any or all kinds of scrap, add 1 cent per lb. g. Lead

ass turnings, 15.50-16.00; new brass clippings, 24.00-25.50; light brass, 15.50-17.50; avy yellow brass, 17.50-20.00; new brass d ends, 22.00-24.00; auto radiators, unveated, 23.00-23.50; cocks and faucets, 21.00-.50; brass pipe, 23.00-24.00.

ead: Heavy, 12.00-12.50; battery plates, 6.50-.75; linotype and stereotype, 13.25-14.25; electotype, 12.00-12.75; mixed babbitt, 14.50.

agnesium: Clippings, 18.50-19.50; clean castgs, 18.00-19.00; iron castings, not over 10% movable Fe, less full deduction for Fe, 16.00-.00.

onel: Clippings, 54.50-60.00; old sheets, .00-50.00; turnings, 44.00; rods, 54.50-60.00.

ickel: Sheets and clips, 90.00-125.00; rolled odes, 90.00-125.00; turnings, 75.00-100.00; d ends, 90.00-125.00.

inc: Old zinc, 5.50-6.00; new die-cast scrap, .00-5.75; old die-cast scrap; 3.25-3.50.

REFINER'S BUYING PRICES

(Cents per pound, carlots, delivered refinery)

luminum: 1100 clippings, 22.50; 3003 clippings, 22.25-22.50; 6151 clippings, 22.00-22.50; 052 clippings, 22.00-22.50; 2014 clippings, .50; 2017 clippings, 21.50; 2024 clippings, .50; mixed clippings, 21.50-22.00; old sheet, .00; old cast, 19.00-20.00; clean old cable free of steel), 22.00-22.50; borings and turngs, 19.00-20.50.

eryllium Copper: Heavy scrap, 0.020-in. and eavier, not less than 1.5% Be, 65.00; light crap, 60.00; turnings and borings, 43.00-55.00.

opper and Brass: No. 1 copper and wire, .00; No. 2 copper and wire, 37.50; light copper, 35.00-35.25; refinery brass (60% copper) er dry copper content, 35.50.

INGOTMAKERS' BUYING PRICES

(Cents per pound, carlots, delivered)

opper and Brass: No. 1 copper and wire, .00; No. 2 copper and wire, 37.50; light opper, 35.00-35.25; No. 1 composition borings, .50; No. 1 composition solids, 32.00-32.50; eavy yellow brass solids 22.00; yellow brass urnings, 21.00; radiators, 24.50-25.00.

PLATING MATERIAL

F.o.b. shipping point, freight allowed on uantities)

ANODES

admium: Special or patented shapes, $1.70 er lb.

opper: Flat-rolled, 59.42, oval, 58.92, 000-10,000 lb; electrodeposited, 56.78, 2000-000 lb lots; cast 62.54, 5000-10,000 lb quantiies.

ickel: Depolarized, less than 100 lb, $1.015; 00-499 lb, 99.50; 500-4999 lb, 95.50; 5000-9,999 lb, 93.50; 30,000 lb, 91.50. Carbonized, educt 3 cents a lb. All prices eastern delivery ffective Jan. 1, 1955.

in: Bar or slab, less than 200 lb, $1.155; 000-499 lb, $1.14; 500-999 lb, $1.135; 1000 or more, $1.13.

inc: Balls, 21.00; flat tops, 21.00; flats, 2.75; ovals, 22.00, ton lots.

CHEMICALS

admium Oxide: $2.15 per lb. in 100-lb drums.

hromic Acid: Less than 10,000 lb, 28.50; over 0,000 lb, 27.50.

opper Cyanide: 100 lb, 85.25; 200 lb, 84.50; 00 lb, 84.25; 400-900 lb, 85.50; 1000 lb, 81.50.

opper Sulphate: 500-1900 lb, 17.90; 2000-5900 , 15.90; 6000 lb or more, 15.65.

ickel Chloride: 100 lb, 46.50; 200 lb, 44.50; 00 lb, 35.25; 400-4900 lb, 33.25; 5000-35,900 9.50; 10,000 lb and over, 38.50. All prices astern delivery, effective Jan. 1, 1955.

ickel Sulphate: 100 lb, 38.25; 200 lb, 36.25; 300 lb, 35.25; 400-4900 lb, 33.25; 5000-35,900 , 31.25; 36,000 lb, 30.25. All prices eastern elivery, effective Jan. 1, 1955.

lver Cyanide: (Cents per ounce) 4-oz bottle, 6.875; 16-oz bottle, 85.625; 80-oz bottle, 3.125; 100-oz bottle, 83.125; f.o.b. St. Louis, ew York and Los Angeles. Effective Sept. 0, 1955.

odium Cyanide: Egg, under 1000 lb, 19.80; 000-19,900 lb, 18.80; 20,000 lb and over, 7.80; granular, add 1-cent premium to above.

odium Stannate: Less than 100 lb, 73.00; 100-00 lb, 58.6; 700-1900 lb, 56.1; 2000-9900 lb, 4.4; 10,000 lb or more, 53.2.

tannous Chloride (Anhydrous): Less than 50 , $1.594; 50 lb, $1.254; 100-300 lb, $1.104; 00-900 lb, $1.08; 1000-1900 lb, $1.055; 2000-900 lb, $1.019; 5000-19,900 lb, 95.8; 20,000 lb r more, 89.7.

tannous Sulphate: Less than 500 lb, $1.293; 0 lb, 99.30; 100-1900 lb, 97.30; 2000 lb or nore, 95.3.

inc Cyanide: Under 1000 lb, 54.30; 1000 lb nd over, 52.30.

THERE'S *this* ABOUT

"Fischer Turned"

BRASS and ALUMINUM NUTS

QUALITY MATERIALS

MASS PRODUCTION



UNIFORM ACCURACY



RIGIDLY INSPECTED

REALISTICALLY PRICED

OVER 50 YEARS EXPERIENCE



Cut your assembly costs with Fischer precision-turned brass and aluminum nuts.

Uniformly accurate, each Fischer nut is countersunk on both sides for faster starting . . . tapped square with its face to Class 2 tolerances for smoother, easier running and superior bearing surface . . . turned from stock under basic size so it's never tight on wrenches . . . tapped through to eliminate "blanks" or rejects . . . cleaned and degreased before delivery.

You pay no premium for this extra quality . . . Fischer *turned* nuts cost no more than those produced by other, less accurate methods.

Write today for complete catalog.

1905-1955 50th ANNIVERSARY FISCHER SPECIAL MFG. CO. CINCINNATI OHIO

Fischer

SPECIAL MFG. CO.

476 MORGAN ST. • CINCINNATI 6, OHIO

C-281-FS

Steel Prices

Mill prices as reported to STEEL, cents per pound except as otherwise noted. *Changes shown in italics.* Code numbers following mill points indicate producing company. Key on page 191. Key to footnotes, Page 193.

SEMIFINISHED

INGOTS, Carbon, Forging (NT)
Munhall,Pa. U5 .....$65.50

INGOTS, Alloy (NT)
Detroit R7 .....$69.00
Houston S5 .....74.00
Midland,Pa. C18 .....69.00
Munhall,Pa. U5 .....69.00

BILLETS, BLOOMS & SLABS Carbon, Rerolling (NT)
Aliquippa,Pa. J5 ....$68.50
Bessemer,Pa. U5 .....68.50
Bridgeport,Conn. N19..73.50
Buffalo R2 .....68.50
Clairton,Pa. U5 .....68.50
Ensley,Ala. T2 .....68.50
Fairfield,Ala. T2 .....68.50
Fontana,Calif. K1 ....76.00
Gary,Ind. U5 .....68.50
Johnstown,Pa. B2 ....68.50
Lackawanna,N.Y. B2 ..68.50
LoneStar,Tex. L6 ....74.50
Munhall, Pa. U5 .....68.50
Pittsburgh J5 .....68.50
S.Chicago,Ill. R2, U5..68.50
S.Duquesne,Pa. U5 ...68.50
Youngstown R2 .....68.50

Carbon, Forging (NT)
Aliquippa,Pa. J5 ....$84.50
Bessemer,Pa. U5 .....84.50
Bridgeport,Conn. N19..89.50
Buffalo R2 .....84.50
Canton,O. R2 .....86.50
Clairton,Pa. U5 .....84.50
Conshohocken,Pa. A3..89.50
Ensley,Ala. T2 .....84.50
Fairfield,Ala. T2 .....84.50
Fontana, Calif. K1 ....92.00
Gary,Ind. U5 .....84.50
Geneva,Utah C11 .....84.50
Houton S5 .....89.50
Johnstown,Pa. B2 ....84.50
Lackawanna,N.Y. B2..84.50
LosAngeles B3 .....94.00
Midland,Pa. C18 .....84.50
Munhall,Pa. U5 .....84.50
Pittsburgh J5 .....84.50
Seattle B3 .....98.00
S.Chicago R2,U5,W14..84.50
S.Duquesne,Pa. U5 ....84.50
S.SanFrancisco B3 ....94.00

Alloy, Forging (NT)
Bethlehem,Pa. B2 ...$96.00
Buffalo R2 .....96.00
Canton,O. R2, T7 ...96.00
Conshohocken,Pa. A3..103.00
Detroit R7 .....96.00
Fontana,Calif. K1 ....115.00
Gary,Ind. U5 .....96.00
Houston S5 .....101.00
Ind.Harbor,Ind. Y1 ...96.00
Johnstown,Pa. B2 ....96.00
Lackawanna,N.Y. B2 ..96.00
LosAngeles B3 .....116.00
Massillon,O. R2 .....96.00
Midland,Pa. C18 .....96.00
Munhall,Pa. U5 .....96.00
S.Chicago R2,U5,W14..96.00
S.Duquesne,Pa. U5 ....96.00
Struthers,O. Y1 .....96.00
Warren,O. C17 .....96.00

ROUNDS, SEAMLESS TUBE (NT)
Buffalo R2 .....$103.50
Canton,O. R2 .....103.50
Cleveland R2 .....103.50
Gary,Ind. U5 .....103.50
S.Chicago R2, W14 ...103.50
S.Duquesne,Pa. U5 ...103.50

SKELP
Aliquippa,Pa. J5 ....4.325
LoneStar,Tex. L6 ....4.625
Munhall,Pa. U5 .....4.225
SparrowsPoint,Md. B2..4.225
Warren,O. R2 .....4.225
Youngstown R2, U5 ...4.225

WIRE RODS
AlabamaCity,Ala. R2 ..5.025
Aliquippa,Pa. J5 .....5.025
Alton,Ill. L1 .....5.20
Buffalo B11, W12 ....5.025
Cleveland A7 .....5.025
Donora,Pa. A7 .....5.025
Fairfield,Ala. T2 ....5.025
Houston S5 .....5.275
IndianaHarbor,Ind. Y1..5.025
Johnstown,Pa. B2 ....5.025
Joliet,Ill. A7 .....5.025
KansasCity,Mo. S5 ....5.275
Kokomo,Ind. C16 ....5.125
LosAngeles B3 .....5.825
Minnequa,Colo. C10 ...5.275
Monessen,Pa. P7 .....5.025
N.Tonawanda,N.Y. B11.5.025
Pittsburg,Calif. C11 ...5.675
Portsmouth P12 .....5.025
Roebling,N.J. R5 .....5.125
S.Chicago,Ill. R2 .....5.025
SparrowsPoint,Md. B2..5.125
Sterling,Ill.(1) N15 ....5.025
Sterling,Ill. N15 .....5.125
Struthers,O. Y1 .....5.025
Worcester,Mass. A7 ...5.325

STRUCTURALS

Carbon Steel Std. Shapes
Ala.City,Ala. R2 .....4.60
Aliquippa,Pa. J5 .....4.60
Bessemer,Ala. T2 .....4.60
Bethlehem,Pa. B2 .....4.65
Birmingham C15 .....4.60
Clairton,Pa. U5 .....4.60
Fairfield,Ala. T2 .....4.60
Fontana,Calif. K1 .....5.25
Gary,Ind. U5 .....4.60
Geneva,Utah C11 .....4.60
Houston S5 .....4.70
Ind.Harbor,Ind. I-2 ....4.60
Johnstown,Pa. B2 ....4.65
KansasCity,Mo. S5 ....4.70
Lackawanna,N.Y. B2 ...4.65
LosAngeles B3 .....5.30
Minnequa,Colo. C10 ....4.90
Munhall,Pa. U5 .....4.60
Niles,Calif. P1 .....4.90
Portland,Oreg. O4 ....5.35
Phoenixville,Pa. P4 ....5.15
Seattle B3 .....5.35
S.Chicago U5, W14 ....4.60
S.SanFrancisco B3 ....5.25
Torrance,Calif. C11 ....5.30
Weirton,W.Va. W6 ....4.60

Wide Flange
Bethlehem,Pa. B2 .....4.65
Clairton,Pa. U5 .....4.60
Fontana,Calif. K1 ....5.40
Lackawanna,N.Y. B2 ...4.65
Munhall,Pa. U5 .....4.60
Phoenixville,Pa. P4 ....5.15
S.Chicago,Ill. U5 .....4.60

Alloy Std. Shapes
Clairton,Pa. U5 .....5.65
Fontana,Calif. K1 .....7.30
Gary,Ind. U5 .....5.65
Houton S5 .....5.75
Munhall,Pa. U5 .....5.65
S.Chicago,Ill. U5 .....5.65

H.S, L.A. Std. Shapes
Aliquippa,Pa. J5 .....6.75
Bessemer,Ala. T2 .....6.75
Bethlehem,Pa. B2 .....6.80
Clairton,Pa. U5 .....6.75
Fairfield,Ala. T2 .....6.75
Fontana,Calif. K1 ....7.40
Gary,Ind. U5 .....6.75
Geneva,Utah C11 .....6.75
Houston S5 .....6.85
Ind.Harbor,Ind. I-2, Y1.6.75
Johnstown,Pa. B2 .....6.80
KansasCity,Mo. S5 ....6.85
Lackawanna,N.Y. B2 ..6.80
LosAngeles B3 .....7.45
Munhall,Pa. U5 .....6.75
Seattle B3 .....7.50
S.Chicago,Ill. U5, W14..6.75
S.SanFrancisco B3 ....7.40
Struthers,O. Y1 .....6.75

H.S., L.A. Wide Flange
Bethlehem,Pa. B2 .....6.80
Lackawanna,N.Y. B2 ..6.80
Munhall,Pa. U5 .....6.75
S.Chicago,Ill. U5 .....6.75

PILING

BEARING PILES
Bethlehem,Pa. B2 .....4.65
Lackawanna,N.Y. B2 ..4.65
Munhall,Pa. U5 .....4.60
S.Chicago,Ill. U5 .....4.60

STEEL SHEET PILING
Ind.Harbor,Ind. I-2 ....5.45
Lackawanna,N.Y. B2 ...5.45
Munhall,Pa. U5 .....5.45
S.Chicago,Ill. U5 .....5.45

PLATES

PLATES, Carbon Steel
Ala.City,Ala. R2 .....4.50
Aliquippa,Pa. J5 .....4.50
Ashland,Ky.(15) A10 ...4.50
Bessemer,Ala. T2 .....4.50
Bridgeport,Conn. N19 ..4.75
Buffalo R2 .....4.50
Clairton,Pa. U5 .....4.50
Claymont,Del. C22 ....4.80
Cleveland J5, R2 .....4.60
Coatesville,Pa. L7 ....4.80
Conshohocken,Pa. A3 ..4.50
Detroit M1 .....4.60
Ecorse,Mich. G5 .....4.60
Fairfield,Ala. T2 .....4.50
Fontana,Calif.(30) K1 ..5.15
Gary,Ind. U5 .....4.50
Geneva,Utah C11 .....4.50
GraniteCity,Ill. G4 ....4.70
Harrisburg,Pa. P4 .....5.10
Houston S5 .....4.60
Ind.Harbor,Ind. I-2, Y1.4.50
Johnstown,Pa. B2 .....4.50
Lackawanna,N.Y. B2 ..4.50
LoneStar,Tex. L6 .....4.85
Mansfield,O. E6 .....4.50
Minnequa,Colo. C10 ....5.35
Munhall,Pa. U5 .....4.50
Newport,Ky. N9 .....4.50
Pittsburgh J5 .....4.50
Riverdale,Ill. A1 .....4.50
Seattle B3 .....5.40
Sharon,Pa. S3 .....4.50
S.Chicago R2, U5, W14.4.50
SparrowsPoint,Md. B2 ..4.50
Steubenville,O. W10 ....4.50
Warren,O. R2 .....4.50
Weirton,W.Va. W6 ....4.50
Youngstown R2, U5, Y1.4.50

PLATES, Carbon Abras. Resist.
Claymont,Del. C22 .....5.65
Fontana,Calif. K1 ....6.30
Geneva,Utah C11 .....5.65
Johnstown,Pa. B2 .....5.65
SparrowsPoint,Md. B2 .5.65

PLATES, Wrought Iron
Economy,Pa. B14 ....10.40

PLATES,High-Strength Low-Alloy
Aliquippa,Pa. J5 .....6.725
Bessemer,Ala. T2 .....6.725
Clairton,Pa. U5 .....6.725
Cleveland J5, R2 .....6.725
Claymont,Del. C22 ....6.725
Coatesville,Pa. L7 ....6.725
Conshohocken,Pa. A3 ..6.725
Ecorse,Mich. G5 .....6.825
Fairfield,Ala. T2 .....6.725
Fontana,Calif.(30) K1 .7.375
Gary,Ind. U5 .....6.725
Geneva,Utah C11 .....6.725
Houston S5 .....6.825
Ind.Harbor,Ind. I-2, Y1.6.725
Johnstown,Pa. B2 .....6.725
LosAngeles B3 .....7.625
Munhall,Pa. U5 .....6.725
Pittsburgh J5 .....6.725
Seattle B3 .....7.625
Sharon,Pa. S3 .....6.725
S.Chicago,Ill. U5, W14.6.725
SparrowsPoint,Md. B2..6.725
Youngstown U5, Y1 ...6.725

PLATES, Alloy
Bridgeport,Conn. N19 ...6.55
Claymont,Del. C22 ....6.30
Coatesville,Pa. L7 ....6.30
Fontana,Calif. K1 .....6.95
Gary,Ind. U5 .....6.30
Houston S5 .....6.40
Ind.Harbor,Ind. Y1 ....6.30
Johnstown,Pa. B2 .....6.30
Munhall,Pa. U5 .....6.30
Newport,Ky. N9 .....6.30
Seattle B3 .....7.20
Sharon,Pa. S3 .....6.30
S.Chicago,Ill. U5, W14..6.30
SparrowsPoint,Md. B2 ..6.30
Youngstown Y1 .....6.30

FLOOR PLATES
Cleveland J5 .....5.575
Conshohocken,Pa. A3 ..5.575
Harrisburg,Pa. P4 ....5.575
Ind.Harbor,Ind. I-2 ....5.575
Munhall,Pa. U5 .....5.575
S.Chicago,Ill. U5 .....5.575

PLATES, Ingot Iron
Ashland c.l. (15) A10...4.75
Ashland l.c.l. (15) A10..5.25
Cleveland c.l. R2 .....5.10
Warren,O. c.l. R2 .....5.10

BARS

BARS, Hot-Rolled Carbon
Ala.City,Ala. R2 .....4.65
Aliquippa,Pa. J5 .....4.65
Alton,Ill. L1 .....4.85
Atlanta A11 .....4.85
Bessemer,Ala. T2 .....4.65
Birmingham C15 .....4.65
Bridgeport,Conn. N19 ..4.80
Buffalo R2 .....4.65
Canton,O. R2 .....4.75
Clairton,Pa. U5 .....4.65
Cleveland R2 .....4.65
Ecorse,Mich. G5 .....4.75
Emeryville,Calif. J7 ....5.40
Fairfield,Ala. T2 .....4.65
FairlessHills,Pa. U5 ....4.80
Fontana,Calif. K1 ....5.35
Gary,Ind. U5 .....4.65
Houston S5 .....4.90
Ind.Harbor,Ind. I-2, Y1.4.65
Johnstown,Pa. B2 .....4.65
Joliet,Ill. P22 .....4.65
KansasCity,Mo. S5 ....4.90
Lackawanna,N.Y. B2 ...4.65
Los Angeles B3 .....5.35
Massillon,O. R2 .....4.75
Midland,Pa. C18 .....4.65
Milton,Pa. M18 .....4.65
Minnequa,Colo. C10 ....5.10
Niles,Calif. P1 .....5.00
N.Tonawanda,N.Y. B11..4.65
Pittsburg,Calif. C11 ...5.35
Pittsburgh J5 .....4.65
Portland,Oreg. O4 .....5.40
Seattle B3, N14 .....5.40
S.Chicago R2, U5, W14..4.65
S.Duquesne,Pa. U5 ....4.65
S.SanFran.,Calif. B3 ...5.40
Sterling,Ill.(1) N15 ....4.65
Sterling,Ill. N15 .....4.75
Struthers,O. Y1 .....4.65
Torrance,Calif. C11 ....5.35
Warren,O. R2 .....4.65
Weirton,W.Va. W6 ....4.65
Youngstown R2, U5 ....4.65

BARS, H.R. Leaded Alloy
Warren,O. C17 .....6.325

BARS, Hot-Rolled Alloy
Bethlehem,Pa. B2 ....5.575
Bridgeport,Conn. N19 .5.725
Buffalo R2 .....5.575
Canton,O. R2, T7 ....5.575
Clairton,Pa. U5 .....5.575
Detroit R7 .....5.575
Ecorse,Mich. G5 .....5.675
Fontana,Calif. K1 ....6.625
FairlessHills,Pa. U5 ....5.725
Gary,Ind. U5 .....5.575
Houston S5 .....5.825
Ind.Harbor,Ind. I-2,Y1.5.575
Johnstown,Pa. B2 ....5.575
KansasCity,Mo. S5 ....5.825
Lackawanna,N.Y. B2 ..5.575
LosAngeles B3 .....6.625
Massillon,O. R2 .....5.575
Midland,Pa. C18 .....5.575
S.Chicago, R2, U5, W14.5.575
S.Duquesne,Pa. U5 ....5.575
Struthers,O. Y1 .....5.575
Warren,O. C17 .....5.575
Youngstown U5 .....5.575

BARS & SMALL SHAPES, H.R. High-Strength Low-Alloy
Aliquippa,Pa. J5 .....6.80
Bessemer,Ala. T2 .....6.80
Bethlehem,Pa. B2 .....6.80
Clairton,Pa. U5 .....6.80
Cleveland R2 .....6.80
Ecorse,Mich. G5 .....6.90
Fairfield,Ala. T2 .....6.80
Fontana,Calif. K1 .....7.50
Gary,Ind. U5 .....6.80
Houston S5 .....7.05
Ind.Harb.,Ind. I-2, Y1 ..6.80
Johnstown,Pa. B2 .....6.80
KansasCity,Mo. S5 ....7.05
Lackawanna,N.Y. B2 ...6.80
LosAngeles B3 .....7.50
Pittsburgh J5 .....6.80
Seattle B3 .....7.55
S.Chicago W14 .....6.80
S.Duquesne,Pa. U5 ....6.80
S.SanFrancisco B3 ....7.55
Struthers,O. Y1 .....6.80
Warren,O. R2 .....6.80
Youngstown U5 .....6.80

BAR SIZE ANGLES; H.R. Carbon
Bethlehem,Pa. B2 .....4.80

BAR SIZE ANGLES; S. Shapes
Aliquippa,Pa. J5 .....4.65
Atlanta A11 .....4.85
Fontana,Calif. K1 .....5.35
Niles,Calif. P1 .....5.00
Pittsburgh J5 .....4.3
Portland,Oreg. O4 .....5.0
SanFrancisco S7 .....5.0

BAR SHAPES, Hot-Rolled Alloy
Clairton,Pa. U5 .....5.6
Gary,Ind. U5 .....5.6
Houston S5 .....5.9
KansasCity,Mo. S5 ....5.9
Youngstown U5 .....5.6

BARS, C.F. Leaded Alloy
Ambridge,Pa. W18 ....8.32
Camden,N.J. P13 .....8.5
Chicago W18 .....8.32
Cleveland C20 .....8.32
Monaca,Pa. S17 .....8.32
Newark,N.J. W18 .....8.5
SpringCity,Pa. K3 ....8.5
Warren,O. C17 .....8.32

BARS, Cold-Finished Carbon
Ambridge,Pa. W18 ....5.90
BeaverFalls,Pa. M12, R2 5.90
Buffalo B5 .....5.90
Camden,N.J. P13 .....6.3
Carnegie,Pa. C12 .....5.90
Chicago W18 .....5.90
Cleveland A7, C20 ....5.90
Detroit R7 .....5.90
Detroit B5, P17 .....6.10
Donora,Pa. A7 .....5.90
Elyria,O. W18 .....5.90
FranklinPark,Ill. N5 ...5.90
Gary,Ind. R2 .....5.90
GreenBay,Wis. F7 ....5.90
Hammond,Ind. L2, M13.5.90
Hartford,Conn. R2 ....6.40
Harvey,Ill. B5 .....5.90
LosAngeles R2, S30 ....7.35
Mansfield,Mass. B5 ....6.45
Massillon,O. R2, R8 ...5.90
Midland,Pa. C18 .....5.90
Monaca,Pa. S17 .....5.90
Newark,N.J. W18 .....6.35
NewCastle,Pa.(17) B4 ..5.90
Pittsburgh J5 .....5.90
Plymouth,Mich. P5 ....6.15
Putnam,Conn. W18 .....6.45
Readville,Mass. C14 ....6.45
S.Chicago,Ill. W14 ....5.90
SpringCity,Pa. K3 ....6.35
Struthers,O. Y1 .....5.90
Waukegan,Ill. A7 .....5.90
Worcester.Mass. W19 ...6.35
Youngstown F3, Y1 ....5.90

BARS, Cold-Finished Carbon (Turned and Ground)
Cumberland,Md. C19 ....5.15

BARS, Cold-Finished Alloy
Ambridge,Pa. W18 ....7.425
BearverFalls,Pa.M12,R2 7.425
Bethlehem,Pa. B2 .....7.425
Buffalo B5 .....7.425
Camden,N.J. P13 .....7.60
Canton,O. T7 .....7.425
Carnegie,Pa. C12 .....7.425
Chicago W18 .....7.425
Cleveland A7, C20 ....7.425
Detroit R7 .....7.425
Detroit B5, P17 .....7.625
Donora,Pa. A7 .....7.425
Elyria,O. W8 .....7.425
Gary,Ind. R2 .....7.425
GreenBay,Wis. F7 ....7.425
Hammond,Ind. L2, M13.7.425
Hartford,Conn. R2 ....7.725
Harvey,Ill. B5 .....7.425
Lackawanna,N.Y. B2 ..7.425
LosAngeles S30 .....9.10
Mansfield,Mass. B5 ....7.725
Massillon,O. R2, R8 ...7.425
Midland,Pa. C18 .....7.425
Monaca,Pa. S17 .....7.425
Newark,N.J. W18 .....7.60
Plymouth,Mich. P5 ..7.625
S.Chicago W14 .....7.425
SpringCity,Pa. K3 ....7.60
Struthers,O. Y1 .....7.425
Warren,O. C17 .....7.425
Waukegan,Ill. A7 .....7.425
Worcester,Mass. A7 ...7.725
Youngstown F3, Y1 ...7.425

BARS, Reinforcing (To Fabricators)
Ala.City,Ala. R2 .....4.[illegible]
Atlanta A11 .....4.8[illegible]
Birmingham C15 .....4.6[illegible]
Buffalo R2 .....4.6[illegible]
Cleveland R2 .....4.6[illegible]
Ecorse,Mich. G5 .....4.7[illegible]
Emeryville,Calif. J7 ...5.4[illegible]
Fairfield,Ala. T2 .....4.6[illegible]
FairlessHills,Pa. U5 ....4.8[illegible]
Fontana,Calif. K1 .....5.3[illegible]
Ft.Worth,Tex.(42) T4 ..5.1[illegible]
Gary,Ind. U5 .....4.6[illegible]
Houston S5 .....4.9[illegible]

Ind.Harbor,Ind. I-2, Y1.4.65
Johnstown,Pa. B2 .....4.65
Joliet,Ill. P22 .....4.65
KansasCity,Mo. S5 ....4.90
Lackawanna,N.Y. B2 ..4.65
LosAngeles B3 .....5.35
Milton,Pa. M18 .....4.65
Minnequa,Colo. C10 ....5.10
Niles,Calif. P1 .....5.00
Pittsburg,Calif. C11 ....5.35
Pittsburgh J5 .....4.65
Portland,Oreg. O4 .....5.40
SandSprings,Okla. S5 ..5.15
Seattle B3, N14 .....5.40
S.Chicago R2 .....4.65
S.Duquesne,Pa. U5 ....4.65
S.SanFrancisco B3 ....5.40
SparrowsPoint,Md. B2 ..4.65
Sterling,Ill.(1) N15 ....4.65
Sterling,Ill. N15 .....4.75
Struthers,O. Y1 .....4.65
Torrance,Calif. C11 ....5.35
Youngstown R2, U5, Y1.4.65

BARS, Reinforcing (Fabricated; to Consumers)

Johnstown,Pa. ½-1" B2.6.15
KansasCity,Kans. S5 ...6.45
Lackawanna,N.Y. B2 ..6.17
Marion,O. P11 .....5.90
Pittsburgh U8 .....6.17
Seattle B3, N14 .....6.60
SparrowsPt. ½-1" B2..6.15
Williamsport,Pa. S19 ..6.00

RAIL STEEL BARS

Avis,Pa.(3) J8 .....4.25
ChicagoHts.(3) C2, I-2..4.55
ChicagoHts.(4) C2, I-2..4.65
Ft.Worth, Tex.(26) T4 ..4.95
Franklin,Pa.(3) F5 ....4.55
Franklin,Pa.(4) F5 ....4.65
Marion,O. (3) P11 .....4.50
Moline,Ill.(3) R2 .....4.65
Tonawanda(3) B12 ....4.50
Tonawanda(4) B12 ....4.65
Williamsport,Pa(3) S19.4.65

BARS, Wrought Iron

Economy,Pa.(S.R.)B14 11.50
Economy,Pa.(D.R.)B14 14.30
Economy(Staybolt)B14 14.65
McK.Rks. (S.R.) L5 ..11.50
McK.Rks.(D.R.) L5 ...16.00
McK.Rks.(Staybolt) L5.17.00

SHEETS

SHEETS, Hot-Rolled Steel (18 Gage and Heavier)

Ala.City,Ala. R2 .....4.325
Allenport,Pa. P7 .....4.325
Ashland,Ky.(8) A10 ..4.325
Cleveland J5, R2 .....4.325
Conshohocken,Pa. A3 .4.375
Detroit(8) M1 .....4.425
Dravosburg,Pa. U5 ..4.325
Ecorse,Mich. G5 .....4.425
Fairfield,Ala. T2 ....4.325
FairlessHills,Pa. U5 ...4.375
Fontana,Calif. K1 ....5.075
Gary, Ind. U5 .....4.325
Geneva,Utah C11 ....4.425
GraniteCity,Ill. G4 ....4.525
Ind.Harbor,Ind. I-2, Y1.4.325
Kokomo,Ind. C16 ....4.425
Lackawanna,N.Y. B2 ..4.325
Mansfield,O. E6, (37)..4.325
Munhall,Pa. U5 .....4.325
Newport,Ky.(8) N9 ...4.325
Niles,O. N12 .....4.325
Pittsburg,Calif. C11...5.025
Pittsburgh J5 .....4.325
Portsmouth,O. P12 ....4.325
Riverdale,Ill. A1 ....4.325
Sharon,Pa. S3 .....4.325
S.Chicago,Ill. W14 ....4.325
SparrowsPoint,Md. B2.4.325
Steubenville,O. W10 ...4.325
Warren,O. R2 .....4.325
Weirton,W.Va. W6 ..4.325
Youngstown U5, Y1 ..4.325

SHEETS, H.R. (19 Ga. & Lighter)

Ala.City,Ala. R2 .....5.625
Kokomo,Ind. C16 ....5.475
Niles,O. N12 .....5.325

SHEETS, H.R. Alloy

Ind.Harbor,Ind. Y1 ....7.20
Youngstown Y1 .....7.20

SHEETS, H.R.(14 Ga. & Heavier) High-Strength Low-Alloy

Cleveland J5, R2 ....6.375
Conshohocken,Pa. A3 ..6.425
Dravosburg,Pa. U5 ....6.375
Ecorse,Mich. G5 .....6.475
Fairfield,Ala. T2 ....6.375
FairlessHills,Pa. U5 ...6.425
Fontana,Calif. K1 ....7.125
Gary,Ind. U5 .....6.375
Ind.Harbor,Ind. I-2, Y1 6.375
Lackawanna(35) B2 ..6.375
Munhall,Pa. U5 .....6.375
Pittsburgh J5 .....6.375
Sharon,Pa. S3 .....6.375
S.Chicago,Ill. U5 .....6.375
SparrowsPoint(36) B2..6.375
Warren,O. R2 .....6.375
Weirton,W.Va. W6 ....6.375
Youngstown U5, Y1....6.375

SHEETS, Hot-Rolled Ingot Iron (18 Gage and Heavier)

Ashland,Ky. (8) A10 ..4.575
Cleveland R2 .....4.925
Ind.Harbor,Ind. I-2 ...4.575
Warren,O. R2 .....4.925

SHEETS, Cold-Rolled Steel (Commercial Quality)

Allenport,Pa. P7 .....5.325
Cleveland J5, R2 ....5.325
Conshohocken,Pa. A3 ..5.375
Dravosburg,Pa. U5 ....5.325
Detroit M1 .....5.325
Ecorse,Mich. G5 .....5.425
Fairfield,Ala. T2 .....5.325
FairlessHills,Pa. U5 ..5.375
Follansbee,W.Va. F4 ..5.325
Fontana,Calif. K1 ....6.425
Gary,Ind. U5 .....5.325
GraniteCity,Ill. G4 ....5.525
Ind.Harbor,Ind I-2, Y1 5.325
Lackawanna,N.Y. B2..5.325
Mansfield,O. E6 .....5.325
Middletown,O. A10 ....5.325
Newport,Ky. N9 .....5.325
Pittsburg,Calif. C11 ..6.275
Pittsburgh J5 .....5.325
Portsmouth,O. P12 ....5.325
SparrowsPoint,Md. B2..5.325
Steubenville,O. W10 ...5.325
Warren,O. R2 .....5.325
Weirton,W.Va. W6 ....5.325
Youngstown Y1 .....5.325

SHEETS, Cold-Rolled High-Strength Low-Alloy

Cleveland J5, R2 .....7.875
Dravosburg,Pa. U5 ....7.875
Ecorse,Mich. G5 .....7.975
FairlessHills,Pa. U5 ...7.925
Fontana,Calif. K1 ....8.975
Gary,Ind. U5 .....7.875
IndianaHarbor,Ind. Y1.7.875
Lackawanna(37) B2 ..7.875
Pittsburgh J5 .....7.875
SparrowsPoint(38) B2.7.875
Warren,O. R2 .....7.875
Weirton,W.Va. W6 ....7.875
Youngstown Y1 .....7.875

SHEETS, Cold-Rolled Ingot Iron

Cleveland R2 .....5.925
Middletown,O. A10 ....5.825
Warren,O. R2 .....5.925

SHEETS, Culvert (16 Gage)	Cu Alloy	Cu Fe
Ashland,Ky. A10	6.90	...
Canton,O. R2	6.10	6.55
Dravosburg U5	6.10	...
Fairfield T2	6.10	...
Gary,Ind. U5	6.10	6.35
Ind.Harbor I-2	6.10	6.35
Kokomo,Ind. C16	6.20	...
MartinsFry. W10	6.10	...
Newport,Ky. N9	6.10	6.35
Pitts.,Calif. C11	6.85	...
SparrowsPt. B2	6.10	...

SHEETS, Culvert—Pure Iron

Ashland,Ky. A10 .....7.15
Gary,Ind. U5 .....6.35
MartinsFry,O. W10 ....6.35

SHEETS, Galvanized Steel Hot-Dipped

Ala.City,Ala. R2 .....5.85‡
Ashland,Ky. A10 .....5.85†
Canton,O. R2 .....5.85‡
Delphos,O. N16 .....6.60‡
Dover,O. R1 .....5.85‡
Dravosburg,Pa. U5 ...5.85†
Fairfield,Ala. T2 .....5.85†
Gary,Ind. U5 .....5.85*
GraniteCity,Ill. G4 ....6.05
Ind.Harbor,Ind. I-2 ...5.85†
Kokomo,Ind. C16 .....5.95‡
MartinsFerry,O. W10 ..5.85*
Middletown,O. A10 ....5.85†
Newport,Ky. N9 .....5.85‡
Niles,O. N12 .....6.85‡
Pittsburg,Calif. C1 ....6.60*
SparrowsPt.,Md. B2 ...5.85†
Steubenville,O. W10 ...5.85‡
Warren,O. R2 .....5.85†
Weirton,W.Va. W6 ....5.85*

*Continuous and noncontinuous. †Continuous. ‡Noncontinuous.

SHEETS, Well Casing

Fontana,Calif. K1 ....6.575

SHEETS, Galvanized High-Strength Low-Alloy

Dravosburg,Pa. U5 ....8.60
SparrowsPoint(39) B2 ..8.60

SHEETS, Galvannealed Steel

Canton,O. R2 .....6.25
Dravosburg,Pa. U5 ....6.25
Kokomo,Ind. C16 .....6.60
Newport,Ky. N9 .....6.25
Niles,O. N12 .....7.25

SHEETS, Galvanized Ingot Iron (Hot-dipped Continuous)

Ashland,Ky. A10 .....6.10
Canton,O. R2 .....6.60
Middletown,O. A10 ....6.10

SHEETS, Electrogalvanized

Cleveland(28) R2 .....6.70
Niles,O.(28) R2 .....6.70
Weirton,W.Va. W6 ....6.55

SHEETS, Aluminum Coated

Butler,Pa. A10 (type 1).8.50
Butler,Pa. A10 (type 2).8.60

SHEETS, Enameling Iron

Ashland,Ky. A10 .....5.90
Cleveland R2 .....5.90
Dravosburg,Pa. U5 ....5.90
Gary,Ind. U5 .....5.90
GraniteCity,Ill. G4 .....6.10
Ind.Harbor,Ind. I-2 ....5.90
Middletown,O. A10 ....5.90
Niles,O. N12 .....5.90
Youngstown Y1 .....5.90

BLUED STOCK, 29 Gage

Follansbee,W.Va. F4 ...7.75
Ind.Harbor,Ind. I-2 ....7.75
Yorkville,O. W10 .....7.75

SHEETS, Long Terne Steel (Commercial Quality)

BeechBottom,W.Va. W10 6.25
Gary,Ind. U5 .....6.25
Mansfield,O. E6 .....6.25
Middletown,O. A10 ....6.25
Niles,O. N12 .....6.25
Weirton,W.Va. W6 .....6.25

SHEETS, Long Terne, Ingot Iron

Middletown,O. A10 .....6.65

Key to Producers

A1 Acme Steel Co.
A3 Alan Wood Steel Co.
A4 Allegheny Ludlum Steel
A5 Alloy Metal Wire Div., H. K. Porter Co. Inc.
A6 American Shim Steel Co.
A7 American Steel & Wire Div., U. S. Steel Corp.
A8 Anchor Drawn Steel Co.
A9 Angell Nail & Chaplet
A10 Armco Steel Corp.
A11 Atlantic Steel Co.

B1 Babcock & Wilcox Co.
B2 Bethlehem Steel Co.
B3 Beth. Pac. Coast Steel
B4 Blair Strip Steel Co.
B5 Bliss & Laughlin Inc.
B8 Braeburn Alloy Steel
B9 Brainard Steel Div., Sharon Steel Corp.
B10 E. & G. Brooke, Wickwire Spencer Steel Div. Colo. Fuel & Iron
B11 Buffalo Bolt Co., Div., Buffalo-Eclipse Corp.
B12 Buffalo Steel Division H. K. Porter Co. Inc.
B14 A. M. Byers Co.
B15 J. Bishop & Co.

C1 Calstrip Steel Corp.
C2 Calumet Steel Div. Borg-Warner Corp.
C4 Carpenter Steel Co.
C7 Cleve. Cold Rolling Mills
C8 Cold Metal Products Co.
C9 Colonial Steel Co.
C10 Colorado Fuel & Iron
C11 Columbia-Geneva Steel
C12 Columbia Steel & Shaft.
C13 Columbia Tool Steel Co.
C14 Compressed Steel Shaft.
C15 Connors Steel Div. H. K. Porter Co. Inc.
C16 Continental Steel Corp.
C17 Copperweld Steel Co.
C18 Crucible Steel Co.
C19 Cumberland Steel Co.
C20 Cuyahoga Steel & Wire
C22 Claymont Steel Products Dept. Wickwire Spencer Steel Division
C23 Charter Wire Inc.
C24 G. O. Carlson Inc.

D2 Detroit Steel Corp.
D3 Detroit Tube & Steel Div., Sharon Steel Corp.
D4 Disston & Sons, Henry
D6 Driver-Harris Co.
D7 Dickson Weatherproof Nail Co.
D8 Damascus Tube Co.
D9 Wilbur B. Driver Co.

E1 Eastern Gas&Fuel Assoc.
E2 Eastern Stainless Steel
E4 Electro Metallurgical Co.
E5 Elliott Bros. Steel Co.
E6 Empire Steel Corp.

F2 Firth Sterling Inc.
F3 Fitzsimmons Steel Co.
F4 Follansbee Steel Corp.
F5 Franklin Steel Div. Borg-Warner Corp.
F6 Fretz-Moon Tube Co.
F7 Ft. Howard Steel & Wire
F8 Ft. Wayne Metals Inc.

G2 Globe Iron Co.
G4 Granite City Steel Co.
G5 Great Lakes Steel Corp.
G6 Greer Steel Co.

H1 Hanna Furnace Corp.
H7 Helical Tube Co.

I-1 Igoe Bros. Inc.
I-2 Inland Steel Co.
I-3 Interlake Iron Corp.
I-4 Ingersoll Steel Div., Borg-Warner Corp.
I-6 Ivins, E., Steel Tube
I-7 Indiana Steel & Wire Co.

J1 Jackson Iron & Steel Co.
J3 Jessop Steel Co.
J4 Johnson Steel & Wire Co.
J5 Jones & Laughlin Steel
J6 Joslyn Mfg. & Supply
J7 Judson Steel Corp.
J8 Jersey Shore Steel Co.

K1 Kaiser Steel Corp.
K2 Keokuk Electro-Metals
K3 Keystone Drawn Steel
K4 Keystone Steel & Wire
K7 Kenmore Metals Corp.

L1 Laclede Steel Co.
L2 LaSalle Steel Co.
L3 Latrobe Steel Co.
L5 Lockhart Iron & Steel
L6 Lone Star Steel Co.
L7 Lukens Steel Co.

M1 McLouth Steel Corp.
M4 Mahoning Valley Steel
M6 Mercer Pipe Div., Sawhill Tubular Products
M8 Mid-States Steel & Wire
M12 Moltrup Steel Products
M13 Monarch Steel Div., Jones & Laughlin Steel Corp.
M14 McInnes Steel Co.
M16 Md. Fine & Special. Wire
M17 Metal Forming Corp.
M18 Milton Steel Prod. Div., Merritt-Chapman&Scott

N1 National-Standard Co.
N2 National Supply Co.
N3 National Tube Div., U. S. Steel Corp.
N5 Nelsen Steel & Wire Co.
N6 NewEng.HighCarb.Wire
N8 Newman-Crosby Steel
N9 Newport Steel Corp.
N12 Niles Rolling Mill Div. Sharon Steel Corp.
N14 Northwest.SteelRoll.Mills
N15 Northwestern S.&W. Co.
N16 New Delphos Mfg. Co.
N19 Northeastern Steel Corp.

O3 Oliver Iron & Steel Corp.
O4 Oregon Steel Mills

P1 Pacific States Steel Corp.
P2 Pacific Tube Co.
P4 Phoenix Iron & Steel Co. Sub. of Barium Steel Corp.
P5 Pilgrim Drawn Steel
P6 Pittsburgh Coke & Chem.
P7 Pittsburgh Steel Co.
P11 Pollak Steel Co.
P12 Portsmouth Division Detroit Steel Corp.
P13 Precision Drawn Steel
P14 Pitts. Screw & Bolt Co.
P15 Pittsburgh Metallurgical
P16 Page Steel & Wire Div., Amer. Chain & Cable
P17 Plymouth Steel Co.
P19 Pitts. Rolling Mills
P20 Prod. Steel Strip Corp.
P22 Phoenix Mfg. Co.

R1 Reeves Steel &Mfg. Co.
R2 Republic Steel Corp.
R3 Rhode Island Steel Corp.
R5 Roebling's Sons, John A.
R6 Rome Strip Steel Co.
R7 Rotary Electric Steel Co.
R8 RelianceDiv.,EatonMfg.
R9 Rome Mfg. Co.
R10 Rodney Metals Inc.

S1 Seneca Wire & Mfg. Co.
S3 Sharon Steel Corp.
S4 Sharon Tube Co.
S5 Sheffield Steel Div., Armco Steel Corp.
S6 Shenango Furnace Co.
S7 Simmons Co.
S8 Simonds Saw & Steel Co.
S12 Spencer Wire Corp.
S13 Standard Forgings Corp.
S14 Standard Tube Co.
S15 Stanley Works
S17 Superior Drawn Steel Co.
S18 Superior Steel Corp.
S19 Sweet's Steel Co.
S20 Southern States Steel
S23 Superior Tube Co.
S25 Stainless Welded Prod.
S26 Specialty Wire Co. Inc.
S30 Sierra Drawn Steel Corp.
S40 Seneca Steel Service

T2 Tenn. Coal & Iron Div. U. S. Steel Corp.
T3 Tenn. Prod. & Chem.
T4 Texas Steel Co.
T5 Thomas Strip Division, Pittsburgh Steel Co.
T6 Thompson Wire Co.
T7 Timken Roller Bearing
T9 Tonawanda Iron Div. Am. Rad. & Stan. San.
T13 Tube Methods Inc.

U4 Universal-Cyclops Steel
U5 United States Steel Corp.
U6 U. S. Pipe & Foundry
U7 Ulbrich Stainless Steels
U8 U. S. Steel Supply Div. U. S. Steel Corp.

V2 Vanadium-Alloys Steel
V3 Vulcan Crucible Division, H. K. Porter Co. Inc.

W1 Wallace Barnes Co.
W2 Wallingford Steel Co.
W3 Washburn Wire Co.
W4 Washington Steel Corp.
W6 Weirton Steel Co.
W7 W. Va. Steel & Mfg. Co.
W8 Western Automatic Machine Screw Co.
W9 Wheatland Tube Co.
W10 Wheeling Steel Corp.
W12 Wickwire Spencer Steel Div., Colo. Fuel & Iron
W13 Wilson Steel & Wire Co.
W14 Wisconsin Steel Div., International Harvester
W15 Woodward Iron Co.
W18 Wyckoff Steel Co.
W19 Worcester Pressed Steel

Y1 Youngstown Sheet&Tube

STRIP

STRIP, Hot-Rolled Carbon

Ala.City,Ala.(27) R2 ..4.325
Allenport,Pa. P7 .....4.325
Alton,Ill. L1 .....4.50
Ashland,Ky.(8) A10 ..4.325
Atlanta A11 .....4.525
Bessemer,Ala. T2 ....4.325
Birmingham C15 .....4.325
Bridgeport,Conn. N19..4.625
Buffalo(27) R2 .....4.325
Conshohocken,Pa. A3 ..4.375
Detroit M1 .....4.425
Ecorse,Mich. G5 .....4.425
Fairfield,Ala. T2 ....4.325
Fontana,Calif. K1 ....5.075
Gary,Ind. U5 .....4.325
Ind.Harbor,Ind. I-2, Y1.4.325
Johnstown,Pa.(25) B2..4.325
Lackaw'na,N.Y.(24) B2 4.325
LosAngeles(25) B3 ....5.075
Milton,Pa. M18 .....4.325
Minnequa,Colo. C10 ..5.425
NewBritain(10) S15 ..4.325
N.Tonawanda,N.Y. B11 4.325
Pittsburg,Calif. C11 ..5.075
Portsmouth,O. P12 ....4.325
Riverdale,Ill. A1 .....4.325
SanFrancisco S7 .....5.05
Seattle(25) B3 .....5.325
Seattle N14 .....5.40
Sharon,Pa. S3 .....4.325
S.Chicago, Ill. W14 ...4.325
S.SanFrancisco(25) B3.5.075
SparrowsPoint,Md. B2..4.325
Sterling(1) N15 .....4.325
Sterling,Ill. N15 .....4.425
Torrance,Calif. C11 ..5.075
Warren,O. R2 .....4.325
Weirton W.Va. W6 ....4.325
Youngstown U5 .....4.325

STRIP, Hot-Rolled Alloy

Bridgeport,Conn. N19 ..7.50
Carnegie,Pa. S18 .....7.20
Fontana,Calif. K1 .....8.85
Gary,Ind. U5 .....7.20
Ind.Harbor,Ind. Y1 ....7.20
LosAngeles B3 .....8.40
Newport,Ky. N9 .....7.20
Sharon, Pa. S3 .....7.20
S.Chicago W14 .....7.20
Youngstown U5, Y1 ....7.20

STRIP, Hot-Rolled High-Strength Low-Alloy

Bessemer,Ala. T2 ....6.425
Conshohocken,Pa. A3 ..6.425
Ecorse,Mich. G5 .....6.525
Fairfield,Ala. T2 ....6.425
Fontana,Calif. K1 ....7.525
Gary,Ind. U5 .....6.425
Houston S5 .....6.675
Ind.Harbor,Ind. I-2, Y1 6.425
KansasCity,Mo. S5 ....6 675
Lackawanna,N.Y. B2 ..6.425
LosAngeles(25) B3 ....7.175
Seattle(25) B3 .....7.425
Sharon,Pa. S3 .....6.425
S.SanFrancisco(25) B3.7.175
SparrowsPoint,Md. B2..6.425
Warren,O. R2 .....6.425
Weirton,W.Va. W6 ....6.425
Youngstown U5, Y1 ..6.425

STRIP, Hot-Rolled Ingot Iron

Ashland,Ky.(8) A10 ..4.575
Warren,O. R2 .....4.925

STRIP, Cold-Rolled Carbon

Anderson,Ind. G6 .....6.25
Baltimore T6 .....6 25
Boston T6 .....6.80
Buffalo S40 .....6.25
Cleveland J5 .....6.25
Cleveland A7 .....6.25
Conshohocken,Pa. A3 ...6 30
Dearborn,Mich. D3 ....6.35
Detroit D2, M1, P20 ...6.35
Dover,O. G6 .....6.25
Ecorse,Mich. G5 .....6.35
Follansbee,W.Va. F4 ..6.25
Fontana,Calif. K1 ....8.00
Franklin Park,Ill. T6 ..6 35
Ind.Harbor,Ind. I-2 ...6 35
Ind.Harbor,Ind. Y1 ....6.25
Indianapolis C8 .....6.40
Lackawanna,N.Y. B2 ..6.25
LosAngeles C1 .....8.50
NewBedford,Mass. R10..6.70
NewBritain(10) S15 ...6.25
NewCastle,Pa. B4, E5..6.25
NewHaven,Conn. A7....7.00
NewHaven,Conn. D2....6.70
NewKensington,Pa. A6..6.25
Pawtucket,R.I. R3 ....6.90
Pawtucket,R.I. N8 ....6.80
Pittsburgh J5 .....6 25
Portsmouth,O. P12 ....6.25
Riverdale,Ill. A1 .....6.35
Rome,N.Y. (32) R6 ....6.25
Sharon,Pa. S3 .....6.25
SparrowsPt.,Md. B2 ....6.25
Trenton,N.J.(31) R5 ...7.80
Wallingford,Conn. W2 ..6.70
Warren,O. R2, T5 ....6.25
Weirton,W.Va W6 ....6.25
Worcester,Mass. A7 ....7.10
Youngstown Y1 .....6.25
Youngstown C8 .....6.25

STRIP, Cold-Rolled Alloy

Boston T6 .....13.80
Carnegie,Pa. S18 ....13.45
Cleveland A7 .....13.45
Dover,O. G6 .....13.45
FranklinPark,Ill. T6 ..13.45
Harrison,N.J. C18 ....13.45
Indianapolis C8 .....13.60
Pawtucket,R.I. N8 ...13.80
Sharon,Pa. S3 .....13.45
Worcester,Mass. A7 ..13.75
Youngstown C8 .....13.45

STRIP, Cold-Rolled High-Strength Low-Alloy

Cleveland A7 .....9.10
Dearborn,Mich. D3 ....9.20
Dover,O. G6 .....9.30
Ecorse,Mich. G5 .....9.20

STRIP, Cold-Finished Spring Steel (Annealed)	0.26-0.40C	0.41-0.60C	0.61-0.80C	0.81-1.05C	1.06-1.35C
Baltimore T6	7.30	9.25	10.80	12.95	15.65
Boston T6	7.55	9.25	10.80	12.95	15.65
Bristol,Conn. W1	...	...	10.80	12.95	15.65
Carnegie, Pa. S18	...	8.95	10.50	12.65	....
Cleveland A7	7.00	8.95	10 50	12.65	15.35
Cleveland C7	...	8.95	10.50	12.65	15.35
Dearborn,Mich. D3	7.10	9.05	10.60	....	....
Detroit D2	7.10	9.05	10.60	12.75	....
Dover,O. G6	7.00	8.95	10.50	12.65	15.35
Follansbee,W.Va. F4	7.00	8.95	10.50**	....	....
FranklinPark,Ill. T6	7.10	8.95	10 50	12.65	15.35
Harrison,N.J. C18	...	...	10.80	12.95	15.65
Indianapolis C8	7.15	9.10	10.50	12.65	15.35
NewBritain,Conn.(10) S15.	7.00	8.95	10.50	12.65	15.35
NewCastle,Pa. B4, E5	7.00	8.95	10.50	12.65	....
NewHaven,Conn. D2	7.45	9.25	10.80	12.95	....
NewKensington,Pa. A6	7.00	8.95	10.50	....	....
New York W3	...	9.25	10.80	12.95	15.65
Pawtucket,R.I. N8	7.55	9.25	10.80	12.95	15.35
Riverdale,Ill. A1	7.10	8.95	10 50	12.65	15.35
Rome,N.Y.(32) R6	7.00	8.95	10 50	12 65	15.35
Sharon,Pa. S3	7.00	8.95	10.50	12.65	15.35
Trenton,N.J. R5	...	9.25	10.80	12.95	15.65
Wallingford,Conn. W2	7.45	9.25	10.80	12.95	15.65
Warren,O. T5	7.00	8.95	10.50	12.65	15.35
Weirton,W.Va. W6	7.00	8.95	10.50	12.65	15.35
Worcester,Mass. T6	7.55	9.25	10.80	12.95	15.65
Worcester,Mass. A7	7.85	9.25	10.80	12.95	15.65
Youngstown C8	7.00	8.95	10.50	12.65	15.35
Spring Steel (Tempered)					
Bristol,Conn. W1	...	...	14.40	17.60	....
Buffalo, W12	...	...	14.40	....	....
FranklinPark,Ill. T6	...	...	14.90	18.10	21.50
Harrison,N.J. C18	...	...	14.40	17.60	21.00
NewYork W3	...	...	14.40	17.60	21.00
Trenton,N.J. R5	...	...	14.40	17.60	21.00
Worcester,Mass. A7, T6	...	...	14.40	17.60	21.00
Worcester,Mass. W12	...	...	14.40	....	....
Youngstown C8	...	...	14.75	17.95	21.35

**0.065 C, max.

Ind.Harbor,Ind. Y1 ....9.30
Lackawanna,N.Y. B2 ..9.10
Sharon,Pa. S3 .....9.10
SparrowsPoint,Md. B2 ..9.10
Warren,O. R2 .....9.10
Weirton,W.Va. W6 ....9.10
Youngstown Y1 .....9.30

STRIP, Electrogalvanized

Cleveland A7 .....6.25*
Dover,O. G6 .....6.25*
Riverdale,Ill. A1 .....6.55*
Youngstown C8 .....6.25*
Warren,O. T5 .....6.25*
Warren,O. B9 .....6.45*
Weirton,W.Va. W6 ....5.75*
Worcester,Mass. A7 ...7.10*

*Plus galvanizing extras.

STRIP, Galvanized (Continuous)

Sharon,Pa. S3 .....6.55

TIGHT COOPERAGE HOOP

Atlanta A11 .....5.05
Riverdale,Ill. A1 .....4.90
Sharon,Pa. S3 .....4.75
Youngstown U5 .....4.75

SILICON STEEL

H.R. SHEETS(22 Ga.,cut lengths)	Field	Armature	Electric	Motor	Dynamo
BeechBottom,W.Va. W10	...	...	9.95	10.95	11.85
Brackenridge,Pa. A4	...	...	9.95	10.95	11.85
Mansfield,O. E6	8.40	9.35	9.95	10.95	11.85
Newport,Ky. N9	8.40	9.35	9.95	10.95	11.85
Niles,O. N12	8.40	9.35	9.95	10 95	....
Vandergrift,Pa. U5	...	9.35	9.95	10.95	11.85
Warren,O. R2	8.40	9.35	9.95	10.95	11.85
Zanesville,O. A10	...	9.35	9.95	10.95	11.85

C.R. COILS & CUT LENGTHS, (22 Ga.)

Fully Processed (Semiprocessed ½c lower)	Field	Armature	Electric	Motor	Dynamo
Brackenridge,Pa. A4	...	...	10.70	11.70	12.60
GraniteCity,Ill. G4	8.80*	9.80*	10.40*	11.40*	....
IndianaHarbor,Ind. I-2	8.60†	9.60*	10.20*	11.20*	....
Vandergrift,Pa. U5	...	10.10†	10.70†	11.70†	12.60†
Vandergrift,Pa. U5	8.60*	9.60*	10.20*	11.20*	12.10*
Warren,O. R2	8.60†	10.10	10.70	11.70	12.60
Zanesville,O. A10	...	10.10	10.70	11.70	12.60

H.R. SHEETS (22 Ga., cut lengths)	Transformer Grade T-72	T-65	T-58	T-52
BeechBottom,W.Va. W10	12.80	13.35	13.85	14.85
Brackenridge,Pa. A4	12.80	....	....	....
Newport,Ky. N9	12.80	....	....	....
Vandergrift,Pa. U5	12.80	13.35	13.85	14.85
Zanesville,O. A10	12.80§	13.35§	13.85§	14.85§

C.R. COILS & CUT LENGTHS (22 Ga.)	Grain Oriented T-100	T-90	T-80	T-73	T-72
Brackenridge,Pa. A4	....	15.85	17.45	17.95	13.55§
Butler,Pa. A10	....	....	17.45	17.95	....
Vandergrift,Pa. U5	14.85	15.85	17.45	17.95	13.55
Warren,O. R2	....	....	....	....	13.55‡

*Semiprocessed. †Fully processed only. ‡Coils, annealed, semiprocessed ½c lower. §Coils, ¾-cent higher.

TIN MILL PRODUCTS

TIN PLATE Electrolytic (Base Box)	0.25 lb	0.50 lb	0.75 lb
Aliquippa,Pa. J5	$7.90	$8.15	$8.55
Dravosburg, Pa. U5	7.90	8.15	8.55
Fairfield,Ala. T2	8.00	8.25	8.65
FairlessHills,Pa. U5	8.00	8.25	8.65
Gary,Ind. U5	7.90	8.15	8.55
GraniteCity,Ill. G4	8.00	8.25	8.65
IndianaHarbor,Ind. I-2, Y1	7.90	8.15	8.55
Niles,O. R2	7.90	8.15	8.55
Pittsburg,Calif. C11	8.65	8.90	9.30
SparrowsPoint,Md. B2	8.00	8.25	8.65
Weirton,W.Va. W6	7.90	8.15	8.55
Yorkville,O. W10	7.90	8.15	8.55

ELECTROTIN (22-27 Gage; Dollars per 100 lb)			
Aliquippa,Pa. J5	6.575	....	....
Niles,O. R2	7.075	7.275	7.475

TINPLATE, American Coke (Base Box)	1.25 lb	1.50 lb
Aliquippa,Pa. J5	$9.20	$9.45
Dravosburg,Pa. U5	9.20	9.45
Fairfield,Ala. T2.	9.30	9.55
Fairless,Pa. U5..	9.30	9.55
Gary,Ind. U5....	9.20	9.45
Ind.Har. I-2, Y1.	9.20	9.45
Pitts.,Calif. C11..	9.95	10.20
Sp.Pt.,Md. B2 ..	9.30	9.55
Weirton,W.Va. W6	9.20	9.45
Yorkville,O. W10.	9.20	9.45

BLACK PLATE, (Base Box)

Aliquippa,Pa. J5 .....$7.00
Dravosburg,Pa. U5 ....7.00
Fairfield,Ala. T2 .....7.10
FairlessHills,Pa. U5 ...7.10
Gary,Ind. U5 .....7.00
GraniteCity,Ill. G4 ....7.10
Ind.Harbor,Ind. I-2, Y1 7.00
Niles,O. R2 .....7.00
Pittsburg,Calif. C11 ...7.75
SparrowsPoint,Md. B2 ..7.10
Warren,O. R2 .....7.00
Weirton,W.Va. W6 ....7.00
Yorkville,O. W10 .....7.00

HOLLOWARE ENAMELING Black Plate (29 Gage)

Dravosburg,Pa. U5 ...6.65
Gary,Ind. U5 .....6.65
GraniteCity,Ill. G4 ....6.75
Ind.Harbor,Ind. Y1 ....6.65
Yorkville,O. W10 .....6.65

MANUFACTURING TERNES (Special Coated; Base Box)

Dravosburg,Pa. U5 ..$8.70
Gary,Ind. U5 .....8.70

MANUFACTURING TERNES (Light Coated 6 lb; Base Box)

Yorkville,O. W10 .....$9.15

ROOFING SHORT TERNES (8 lb Coated; Base Box)

Gary,Ind. U5 .....$10.25

WIRE

WIRE, Manufacturers Bright, Low Carbon

AlabamaCity,Ala. R2 ..6.25
Aliquippa,Pa. J5 .....6.25
Alton,Ill. L1 .....6.425
Atlanta A11 .....6.45
Bartonville,Ill. K4 ....6.35
Buffalo W12 .....6.25
Chicago W13 .....6.25
Cleveland A7 .....6 25
Crawfordsville,Ind. M8..6.35
Donora,Pa. A7 .....6.25
Duluth,Minn. A7 .....6.25
Fairfield,Ala. T2 .....6.25
Fostoria,O.(24) S1 ....6.45
Houston S5 .....6.50
Jacksonville,Fla. M8 ...6.77
Johnstown,Pa. B2 .....6.25
Joliet,Ill. A7 .....6.25
KansasCity,Mo. S5 ....6.50
Kokomo,Ind. C16 .....6.35
LosAngeles B3 .....7.20
Minnequa,Colo. C10 ....6.50
Monessen,Pa. P7 .....6.25
Newark 6-8 ga. I-1 ....6.90
N. Tonawanda B11 ....6 25
Palmer,Mass. W12 ....6.55
Pittsburg,Calif. C11 ...7.20
Portsmouth,O. P12 ....6.25
Rankin,Pa. A7 .....6.25
S Chicago,Ill. R2 .....6.25
S.SanFrancisco C10 ....7.20
SparrowsPoint,Md. B2 ..6.35
Sterling,Ill.(1) N15 ....6.25
Sterling,Ill. N15 .....6.35
Struthers,O. Y1 .....6.25
Waukegan,Ill. A7 .....6.25
Worcester,Mass. A7 ....6.55

WIRE, MB Spring, High Carbon

Aliquinna,Pa. J5 .....7.90
Alton,Ill. L1 .....8.075
Bartonville,Ill. K4 .....8.00
Buffalo W12 .....7.90
Cleveland A7 .....7.90
Donora,Pa. A7 .....7.90
Duluth,Minn. A7 .....7.90
Fostoria,O. S1 .....7.95
Johnstown,Pa. B2 .....7.90
LosAngeles B3 .....8.85
Milbury,Mass.(12) N6 ..8.20
Minnequa,Colo. C10 ....8.15
Monessen,Pa. P16 .....7.90
Muncie,Ind. I-7 .....8.10
Palmer,Mass. W12 ....8.20
Pittsburg,Calif. C11 ...8.85
Portsmouth,O. P12 .....7.90
Roebling,N.J. R5 .....8.20
S.Chicago,Ill. R2 .....7.90
S.SanFrancisco C10 ....8.85
SparrowsPt.,Md. B2 ....8.00
Struthers,O. Y1 .....7.90
Trenton,N.J. A7 .....8.20
Waukegan,Ill. A7 .....7.90
Worcester A7,J4,T6,W12.8.20

WIRE, Upholstery Spring

Aliquippa,Pa. J5 .....7.60
Alton,Ill. L1 .....7.775
Buffalo W12 .....7.60
Cleveland A7 .....7.60
Donora,Pa. A7 .....7.60
Duluth,Minn. A7 .....7.60
Johnstown,Pa. B2 .....7.60
KansasCity,Mo. S5 ....7 85
LosAngeles B3 .....8.55
Minnequa,Colo. C10 ...7.775
Monessen Pa. P16 .....7.60
NewHaven Conn. A7 ...7.90
Palmer,Mass. W12 ....7.90
Pittsburg Calif. C11 ....8.55
Portsmouth,O. P12 ....7.60
Roebling,N.J. R5 .....7.90
S Chicago,Ill. R2 .....7.60
S SanFrancisco C10 ....8.55
SparrowsPoint,Md. B2 .7.70
Struthers,O. Y1 .....7.60
Trenton,N.J. A7 .....7.90
Waukegan,Ill A7 .....7.60
Worcester,Mass. A7 ....7.90

WIRE, Fine & Weaving(8" Coils)

Alton,Ill. L1 .....12.725
Bartonville,Ill. K4 ....12.65
Buffalo W12 .....12.55
Chicago W13 .....12.55
Cleveland A7 .....12.55
Crawfordsville,Ind. M8.12.65
Fostoria,O. S1 .....12.55
Jacksonville,Fla. M8 .13 08
Johnstown,Pa. B2 ....12.55
Kokomo,Ind. C16 .....12.55
Minnequa,Colo. C10 ....12.30
Monessen,Pa. P16 ....12.55
Muncie,Ind. I-7 .....12.75
Palmer,Mass. W12 ....12.85
Roebling,N.J. R5 .....12.85
S.SanFrancisco C10 ....12.90
Waukegan,Ill. A7 .....12.55
Worcester,Mass.A7,T6 .12.85

WIRE, Gal'd ACSR for Cores

Bartonville,Ill. K4 ....10.70
Buffalo W12 .....10.70
Johnstown,Pa. B2 .....10.70
Minnequa,Colo. C10 ...10.825
Monessen,Pa. P16 ....10.70
Muncie,Ind. I-7 .....10.90
Pittsburg,Calif. C11 ...11.50
Portsmouth,O. P12 ....10.70
Roebling,N.J. R5 .....11.00
SparrowsPt., Md. B2 ....10.80

ROPE WIRE (A)

Bartonville Ill. K4 .....10.55
Buffalo W12 .....10.55
Fostoria,O.(23) S1 ....10.55
Johnstown,Pa. B2 ....10 55
Monessen,Pa. P16 ....10.55
Muncie,Ind. I-7 .....10.75
Palmer,Mass. W12 ....10.85
Portsmouth O. P12 ....9.75
Roebling,N.J. R5 .....10.85
SparrowsPt. B2 .....10.65
Struther,O. Y1 .....10.55
Worcester,Mass. J4 ....10.85

(A) Plow and Mild Plow; add 0.25c for Improved Plow.

WIRE
(Continued)

WIRE, Tire Bead

Bartonville, Ill. K4	14.15
Monessen, Pa. P16	14.20
Roebling, N.J. R5	14.35

WIRE, Cold-Rolled Flat

Anderson Ind. G6	9.00
Baltimore T6	9.30
Buffalo W12	9.00
Cleveland A7	9.00
Crawfordsville, Ind. M8	9.00
Dover, O. G6	9.00
Fostoria, O. S1	9.00
Franklin Park, Ill. T6	9.10
Kokomo, Ind. C16	9.00
Massillon, O. R8	9.00
Milwaukee C23	9.20
Monessen, Pa. P16	9.00
Pawtucket, R.I. N8	9.30
Riverdale, Ill. A1	9.10
Rome, N.Y. R6	9.00
Trenton, N.J. R5	9.30
Worcester A7, T6, W12	9.30

NAIL, Stock

To Dealers & Mfrs. (7) Col.	
Alabama City, Ala. R2	152
Aliquippa, Pa. J5	152
Atlanta A11	154
Bartonville, Ill. K4	154
Chicago, Ill. W13	152
Cleveland A9	157
Crawfordsville, Ind. M8	154
Donora, Pa. A7	152
Duluth, Minn. A7	152
Fairfield, Ala. T2	152
Galveston, Tex. D7	157
Houston, Tex. S5	157
Johnstown, Pa. B2	152
Joliet, Ill. A7	152
Kansas City, Mo. S5	157
Kokomo, Ind. C16	154
Minnequa, Colo. C10	157
Monessen, Pa. P7	152
Pittsburg, Calif. C11	171
Rankin, Pa. A7	152
S. Chicago, Ill. R2	152
Sparrows Pt., Md. B2	154
Sterling, Ill. (1) N15	152
Worcester, Mass. A7	158

NAILS, CUT (100 lb keg)

To Dealers (33)	
Conshohocken, Pa. A3	$9.05
Wheeling, W.Va. W10	9.05

STAPLES, Polished Stock

To Dealers & Mfrs. (7) Col.	
Aliquippa, Pa. J5	152
Atlanta A11	154
Bartonville, Ill. K4	154
Crawfordsville, Ind. M8	154
Donora, Pa. A7	152
Duluth, Minn. A7	152
Fairfield, Ala. T2	152
Johnstown, Pa. B2	152
Joliet, Ill. A7	152
Kokomo, Ind. C16	154
Minnequa, Colo. C10	157
Monessen, Pa. P7	152
Pittsburg, Calif. C11	171
Rankin, Pa. A2	152
Sparrows Pt., Md. B2	154
Sterling, Ill. (1) N15	152
Worcester, Mass. A7	158

TIE WIRE, Automatic Baler (14½ Ga.) (Per 97 lb Net Box)

Coil No. 3150	
Alabama City, Ala. R2	$9.35
Bartonville, Ill. K4	9.45
Buffalo W12	9.35
Crawfordsville, Ind. M8	9.46
Donora, Pa. A7	9.35
Duluth, Minn. A7	9.35
Johnstown, Pa. B2	9.35
Joliet, Ill. A7	9.35
Kokomo, Ind. C16	9.45
Los Angeles B3	10.14
Minnequa, Colo. C10	9.60
Pittsburg, Calif. C11	10.43
S. Chicago, Ill. R2	9.35
Sparrows Pt., Md. B2	9.45
Sterling, Ill. N15	9.35

Coil No. 6500 Stand.	
Alabama City, Ala. R2	$9.65
Bartonville, Ill. K4	9.75
Buffalo W12	9.60
Crawfordsville, Ind. M8	9.75
Donora, Pa. A7	9.65
Duluth, Minn. A7	9.65
Johnstown, Pa. B3	9.65
Joliet, Ill. A7	9.65
Kokomo, Ind. C16	9.75
Los Angeles B3	10.45
Minnequa, Colo. C10	9 90
Pittsburg, Calif. C11	10.13
S. Chicago, Ill. R2	9.65
Sparrows Pt., Md. B2	9.75
Sterling, Ill. N15	9.65

Coil No. 6500 Interim	
Alabama City, Ala. R2	$9.70
Bartonville, Ill. K4	9.80
Buffalo W12	9.70
Crawfordsville, Ind. M8	9.80
Donora, Pa. A7	9.70
Duluth, Minn. A7	9.70
Johnstown, Pa. B2	9.70
Joliet, Ill. A7	9.70
Kokomo, Ind. C16	9.80
Los Angeles B3	10.50
Minnequa, Colo. C10	9.95
Pittsburg, Calif. C11	10.50
S. Chicago, Ill. R2	9.70
Sparrows Pt., Md. B2	9.80
Sterling, Ill. N15	9.70

WIRE, Barbed

	Col.
Alabama City, Ala. R2	175**
Aliquippa J5	172§
Atlanta A11	181
Bartonville, Ill. K4	181
Crawfordsville, Ind. M8	181
Donora, Pa. A7	175†
Duluth, Minn. A7	175†
Fairfield, Ala. T2	175†
Houston, Tex. S5	180†
Johnstown, Pa. B2	179*
Joliet, Ill. A7	175†
Kansas City, Mo. S5	180†
Kokomo, Ind. C16	177†
Minnequa, Colo. C10	180**
Monessen, Pa. P7	179*
Pittsburg, Calif. C11	195†
Rankin, Pa. A7	175†
S. Chicago, Ill. R2	175**
S. San Francisco C10	195**
Sparrows Point, Md. B2	131*
Sterling, Ill. (1) N15	179*

WOVEN Fence, 9-15 Ga.

	Col.
Ala. City, Ala. R2	162**
Ala. City, 17 ga. R2	241**
Ala. City, 18 ga. R2	251**
Aliq'ppa, Pa. 9-14½ ga J5	165§
Atlanta A11	168
Bartonville, Ill K4	168
Crawfordsville, Ind. M8	168
Donora, Pa. A7	162†
Duluth, Minn. A7	162†
Fairfield, Ala T2	162†
Houston, Tex. S5	167†
Johnstown, Pa. (43) B2	166
Joliet, Ill. A7	162†
Kansas City, Mo. S5	167†
Kokomo, Ind. C16	164†
Minnequa, Colo. C10	167**
Monessen, Pa. 9 ga. P17	166*
Pittsburg, Calif. C11	185†
Rankin, Pa. A7	162†
S. Chicago, Ill. R2	162**
Sterling, Ill. (1) N15	166*

WIRE (16 Gage) Stone

	An'ld Galv. Stone
Ala. City, Ala. R2	14.50 16.05**
Bartonville, Ill. K4	14.60 16.50
Buffalo W12	14.50 ....
Cleveland A7	14.50 ....
Crawf'dsville, Ind. M8	14.60 16.50
Fostoria, O. S1	14.60 16.15†
Johnstown, Pa. B2	14.15 16.40*
Kokomo, Ind. C16	14.60 16.15†
Minnequa, Colo. C10	14.75 16.45**
Palmer, Mass. W12	14.50 16.05*
Pitts., Calif. C11	14.85 16.40†
S. Chicago, Ill. R2	14.50 16.05**
Sparrows Pt., Md. B2	14.60 16.50*
Sterling, Ill. (1) N15	14.50 16.45††
Waukegan, Ill. A7	14.50 16.05†
Worcester, Mass. A7	14.80 ....

WIRE, Merchant Quality (6 to 8 gage)

	An'ld Galv.
Ala. City, Ala. R2	7.40 7.80**
Aliquippa J5	7.40 7.925§
Atlanta A11	7.50 8.075
Bartonville (48) K4	7.50 8.075
Buffalo W12	7.40 8.80†
Cleveland A7	7.40 ....
Crawfordsville, Ind. M8	7.50 8.075
Donora, Pa. A7	7.40 7.80†
Duluth, Minn. A7	7.40 7.80†
Fairfield T2	7.40 7.80†
Houston, Tex. S5	7 65 8.05†
Jacks'ville, Fla. M8	7.90 8.475
Johnstown B2 (48)	7.40 7.975*
Joliet, Ill. A7	7.40 7.80†
Kansas City, Mo. S5	7.65 8.05†
Kokomo C16	7.50 7.90†
Los Angeles B3	8.35 8.925*
Minnequa C10	7.65 8 05**
Monessen P7 (48)	7.40 7.975*
Palmer, Mass. W12	7.70 8.10†
Pitts., Calif. C11	8 35 8.75†
Portsmouth, O. P12	7.40 ....
Rankin A7	7.40 7.80†
S. Chicago R2	7.40 7.80**
S. San Fran. C10	8.35 8.75**
Sparrows Pt B2 (48)	7 50 8.075*
Str'ling (1) (48) N15	7.40 8.00††
Struthers, O (48) Y1	7.40 7.90‡
Worcester, Mass. A7	7.70 ....

*Based on 12.50c zinc; †5c zinc; §10c zinc; ‡Less than 10c zinc; **Subject to zinc equalization extras. ††13c zinc.

BALE TIES, Single Loop

	Col.
Alabama City, Ala. R2	173
Atlanta A11	175
Bartonville, Ill. K4	175
Crawfordsville, Ind. M8	175
Donora, Pa. A7	173
Duluth, Minn. A7	173
Fairfield, Ala. T2	173
Joliet, Ill. A7	173
Houston S5	178
Kansas City, Mo. S5	178
Kokomo, Ind. C16	175
Minnequa, Colo. C10	178
S. Chicago R2	173
S. San Fran., Calif. C10	197
Sparrows Point, Md. B2	175
Sterling, Ill. (1) N15	173

FENCE POSTS

	Col.
Chicago Hts., Ill. C2, I-2	157
Duluth, Minn. A7	157
Franklin, Pa. F5	157
Huntington, W.Va. W7	157
Johnstown, Pa. B2	168
Marion, O. P11	157
Minnequa, Colo. C10	162
Moline Ill. R2	162
S. Chicago, Ill. R2	157
Tonawanda, N.Y. B12	157
Williamsport, Pa. S10	168

FASTENERS

(Base discounts, full case quantity, per cent off list to consumer, f.o.b. mill)

Carriage, Machine Bolts

Full-Size Body (cut thread)

†½" x 6" and smaller	61
Larger than ½" diam. and all diams. longer than 6"	55

Under-Size Body (rolled thread; not nutted):

½" x 6" and smaller.	61

Carriage, Machine & Lag Bolts, Hot Galvanized:

½" and smaller	42
Larger than ½" diam. and all diams. longer than 6"	32

†½" x 4" and smaller and shorter are not nutted.

Lag Bolts

All diams. x 6" and shorter	61
All diams. longer than 6"	55

Plow, Tap & Blank Bolts

½" x 6" and smaller.	61
Larger than ½" diam. and all diams, longer than 6"	55

Ribbed Neck, Carriage, Step, Elevator, Fitting-Up and Tire Bolts:

All sizes	61

STOVE BOLTS, SLOTTED (nuts not attached; bulk)

⅛" to ¼" diam. incl., 3" or shorter:	
25,000 to 199,999 pieces	61
200,000 or more pieces	64
⅛" to ½" diam. incl., 3" or shorter:	
15,000 to 99,999 pieces	61
100,000 or more pieces	64
Longer than 3", any diam.:	
5000 to 99,999 pieces.	61
100,000 or more pieces	64

RIVETS

F.o.b. Cleveland, and/or freight equalized with Pittsburgh. f.o.b. Chicago, and/or freight equalized with Birmingham except where equalization is too great.

Structural ½-in., larger 9.95
⅞-in. under. List less 32%

BOILER TUBES

Net base c.l. prices, dollars per 100 ft, mill; minimum wall thickness, cut lengths 10 to 24 ft. inclusive.

O.D. In.	B.W. Gage	Seamless H.R.	Seamless C.D.	Elec. Weld H.R.
1	13	....	21.06	20.41
1¼	13	....	24.94	20.44
1½	13	23.31	27.57	22.60
1¾	13	27.54	32.57	26.71
2	13	30.87	36.51	29.93
2¼	12	34.77	41.12	33.72
2½	12	37.73	44.63	36.59
2½	12	41.57	49.16	40.31
2¾	12	45.00	53.22	43.65
3	12	47.99	56.76	46.54

RAILWAY MATERIALS

	Standard No. 1	Standard No. 2	Tee Rails All No. 2	Tee Rails 60 lb Under
RAILS				
Bessemer, Pa. U5	4.725	4.625	4.675	5.65
Ensley, Ala. T2	4.725	4.625	....	5.65
Fairfield, Ala. T2	....	....	....	5.65
Gary, Ind. U5	4.725	....	....	....
Huntington, W.Va. W7	....	....	....	5.65
Indiana Harbor, Ind. I-2	4.725	4.625	4.675	....
Johnstown, Pa. B2	....	....	....	(16) 5.65
Lackawanna, N.Y. B2	4.725	4.625	....	5.65
Minnequa, Colo. C10	4.725	4.625	....	6.15
Steelton, Pa. B2	4.725	4.625	....	....
Williamsport, Pa. S19	....	....	....	5.65

TIE PLATES

Fairfield, Ala. T2	5.625
Gary, Ind. U5	5.625
Ind. Harbor, Ind. I-2	5.625
Lackawanna, N.Y. B2	5.625
Minnequa, Colo. C10	5.625
Seattle B3	5.775
Steelton, Pa. B2	5.625
Torrance, Calif. C11	5.775

TRACK BOLTS (20) Treated

Cleveland R2	12.40
Kansas City, Mo. S5	12.40
Lebanon, Pa. B2	12.40
Minnequa, Colo. C10	12.40
Pittsburgh O3, P14	12.40
Seattle B3	12.90

AXLES

Ind. Harbor, Ind. S13	7.25
Johnstown, Pa. B2	7.25

JOINT BARS

Bessemer, Pa. U5	5.825
Fairfield, Ala. T2	5.825
Ind. Harbor, Ind. I-2	5.825
Joliet, Ill. U5	5.825
Lackawanna, N.Y. B2	5.825
Minnequa, Colo. C10	5.825
Steelton, Pa. B2	5.825

SCREW SPIKES

Cleveland R2	11.90
Pittsburgh O3	11.90

STANDARD TRACK SPIKES

Fairfield, Ala. T2	7.90
Ind. Harbor, Ind. I-2, Y1	7.90
Kansas City, Mo. S5	7.90
Lebanon, Pa. B2	7.90
Minnequa, Colo. C10	7.90
Pittsburgh J5	7.90
Seattle B3	8.40
S. Chicago, Ill. R2	7.90
Struthers, O. Y1	7.90
Youngstown R2	7.90

METAL POWDER

(Per pound f.o.b shipping point in ton lots for minus 100 mesh, except as otherwise noted)

	Cents
Sponge iron:	
98+% Fe, annealed	*9.25*
Unannealed:	
Minus 100 mesh	11.75
Minus 35 mesh	*8.25*
Minus 20 mesh	9.00
Swedish, c.i.f. Camden, N. J., c.l. in bags.	9.50
Domestic (Swedish), f.o.b. Riverton, N.J., in bags	9.50
Canadian, f.o.b. Shipping point	9.50
Electrolytic iron:	
Melting stock, 99.9% Fe, irregular fragments of ⅛ in. x 1.3 in.	22.00
Annealed, 99.5% Fe.	36.50
Unannealed (99+% Fe)	*34.00*
Unannealed (99+% Fe) (minus 325 mesh)	*57.00*
Powder Flakes (minus 16, plus 100 mesh).	31.00
Carbonyl Iron: 97.9-99.8% size 5 to 10 microns.	83.00-148.00
Aluminum:	
Atomized, 500 lb. drum frght. allowed	
Carlots	34.50
Ton lots	36.50
Antimony, 500 lb lots	32.00*
Brass, 5000-lb lots	38.00-50.00†
Bronze, 5000-lb lots	*61.25-64.50†*
Copper:	
Electrolytic	*56.75*
Reduced	*56.75*
Lead	*22.80*
Manganese:	
Minus 35 mesh	*64.00*
Minus 100 mesh	*70.00*
Minus 200 mesh	*75.00*
Nickel, unannealed	*$1.00*
Nickel-Silver, 5000-lb lots	*58.75-61.50†*
Phosphor-Bronze, ¼-ton lots	58.50
Silicon	*47.50*
Solder	7.00*
Stainless Steel, 302	*99.00*
Stainless Steel, 316	*$1.32*
Tin	14.50*
Zinc, 5000-lb lots	18.75-32.50‡

Tungsten	Dollars
Melting grade, 99% 60 to 200 mesh:	
1000 lb and over	4.50
Less than 1000 lb.	4.65
Chromium, electrolytic 99.2% Cr min.	3.50

*Plus cost of metal. †Depending on composition. ‡Depending on mesh. §70% Cu, 20% Zn, 10% Ni, **64% Cu, 18% Zn, 18% Ni.

Footnotes

(1) Chicago Base.
(2) Angles, flats, bands.
(3) Merchant.
(4) Reinforcing.
(6) Chicago or Birm. base.
(7) To jobbers, 3 cols. lower.
(8) 16 Ga. and heavier.
(10) Pittsburgh base.
(11) Cleveland & Pitts. base.
(12) Worcester, Mass., base.
(13) Add 0.25c for 17 Ga. & heavier.
(14) Gage 0.143 to 0.249 in.; for gage 0.142 and lighter, 5.80c.
(15) ⅝" and thinner.
(16) 40 lb and under.
(17) Flats only; 0.25 in. & heavier.
(18) To dealers.
(19) Chicago & Pitts. base.
(20) 0.25 off for untreated.
(21) New Haven, Conn., base.
(22) Deld. San Francisco Bay area.
(23) Mild plow, 10.55c.
(24) Deduct 0.10c, finer than 15 Ga.
(25) Bar mill bands.
(26) Delivered in mill zone, 5.10c.
(27) Bar mill sizes.
(28) Bonderized.
(29) Youngstown base.
(30) Sheared; for universal mill and 0.45c for carbon, add 0.40c for alloy and 0.45c H.S.-L.A.
(31) Widths over ⅝-in.; 6.90c for widths ⅝-in. and under by 0.125 in. and thinner.
(32) Buffalo base.
(33) To jobbers, deduct 20c.
(34) 9.60c for cut lengths.
(35) 72" and narrower.
(36) 54" and narrower.
(37) 13 Ga. & heavier; 60" & narrower.
(38) 14 Ga. & lighter; 48" & narrower.
(39) 48" and narrower.
(40) Lighter than 0.035"; 0.035" and heavier, 0.25c higher.
(41) 9.10c for cut lengths.
(42) Mill lengths, f.o.b. mill; deld. in mill zone or within switching limits, 5.25c.
(43) 9-14½ Ga.
(48) 6-7 Ga.

SEAMLESS STANDARD PIPE, Threaded and Coupled

Carload discounts from list, %

Size—Inches	2		2½		3		3½		4		5		6	
List Per Ft	37c		58.5c		76.5c		92c		$1.09		$1.48		$1.92	
Pounds Per Ft	3.68		5.82		7.62		9.20		10.89		14.81		19.18	
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*
Aliquippa, Pa. J5	6.5	+10	10.5	+7.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25
Ambridge, Pa. N2	6.5	..	10.5	...	13	...	14.5	...	14.5	...	14	...	16.5	..
Lorain, O. N3	6.5	+10	10.5	+7.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25
Youngstown Y1	6.5	+10	10.5	+7.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25

ELECTRIC WELD STANDARD PIPE, Threaded and Coupled

Carload discounts from list, %

Youngstown R2	6.5	+10	10.5	+7.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25

BUTTWELD STANDARD PIPE, Threaded and Coupled

Carload discounts from list, %

Size—Inches	⅛		¼		⅜		½		¾		1		1¼	
List Per Ft	5.5c		6c		6c		8.5c		11.5c		17c		23c	
Pounds Per Ft	0.24		0.42		0.57		0.85		1.13		1.68		2.28	
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*
Aliquippa, Pa. J5	...	...	....	....	....	....	17.5	0.25	20.5	4.25	23	7.75	25.5	9
Alton, Ill. L1	...	...	....	....	....	....	15.5	+1.75	18.5	2.25	21	5.75	23.5	7
Benwood, W. Va. W10	16.5	+12	7.25	+18.25	+1.75	+26.25	17.5	0.25	20.5	4.75	23	7.75	25.5	7
Butler, Pa. F6	17.5	+11	9	+16.5	0.5	+24	...	...	...	...	...	...	...	...
Etna, Pa. N2	...	...	....	....	....	....	17.5	0.25	20.5	4.25	23	7.75	25.5	9
Fairless Hills, Pa. N3	...	...	....	....	....	....	15.5	+1.75	18.5	2.75	21	5.75	23.5	7
Fontana, Calif. K1	...	...	....	....	....	....	6	+11.25	9	+7.25	11.5	+3.75	14	+2.5
Ind. Harbor, Ind. Y1	...	...	....	....	....	....	16.5	+0.75	19.5	3.25	22	6.75	24.5	8
Lorain, O. N3	...	...	....	....	....	....	17.5	0.25	20.5	4.25	23	7.75	25.5	9
Sharon, Pa. S4	17.5	+11	9	+16.5	0.5	+24	...	...	...	...	...	...	...	...
Sharon, Pa. M6	...	...	....	....	....	....	17.5	0.25	20.5	4.25	23	7.75	25.5	9
Sparrows Pt., Md. B2	15.5	+13	7	+18.5	+1.5	+26	15.5	+1.75	18.5	2.25	21	5.75	23.5	7
Youngstown R2, Y1	...	...	....	....	....	....	17.5	0.25	20.5	4.25	23	7.75	25.5	9
Wheatland, Pa. W9	17.5	+11	9	+16.5	0.5	+24	17.5	0.25	20.5	4.25	23	7.75	25.5	9

Size—Inches	1½		2		2½		3		3½		4	
List Per Ft	27.5c		37c		58.5c		76.5c		92c		$1.09	
Pounds Per Ft	2.73		3.68		5.82		7.62		9.20		10.89	
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*
Aliquippa, Pa. J5	26	10	26.5	10.5	28	10.75	28	10.75	....	....	....	....
Alton, Ill. L1	24	8	24.5	8.5	26	8.75	26	8.75	....	....	....	....
Benwood, W. Va. W10	26	10	26.5	10.5	28	10.75	28	10.75	18.5	0.75	18.5	0.75
Etna, Pa. N2	26	10	26.5	10.5	28	10.75	28	10.75	18.5	0.75	18.5	0.75
Fairless Hills, Pa. N3	24	8	24.5	8.5	26	8.75	26	8.75	16.5	+1.25	16.5	+1.25
Fontana, Calif. K1	14.5	+1.5	15	+1	16.5	+0.75	16.5	+0.75	7	+10.75	7	+10.75
Ind. Harbor, Ind. Y1	25	9	25.5	9.5	27	9.75	27	9.75	17.5	+0.25	17.5	+0.25
Lorain, O. N3	26	10	26.5	10.5	28	10.75	28	10.75	....	....	....	....
Sharon, Pa. M6	26	10	26.5	10.5	28	10.75	28	10.75	....	....	....	....
Sparrows Pt., Md. B2	24	8	24.5	8.5	26	8.75	26	8.75	16.5	+1.25	16.5	+1.25
Youngstown R2, Y1	26	10	26.5	10.5	28	10.75	28	10.75	18.5	0.75	18.5	0.75
Wheatland, Pa. W9	26	10	26.5	10.5	28	10.75	28	10.75	18.5	0.75	18.5	0.75

*Galvanized pipe discounts based on current price of zinc (13.00c, East St. Louis).

Stainless Steel

Representative prices, cents per pound; subject to current lists of extras

AISI Type	Rerolling Ingots	Rerolling Slabs, Billets	Forging Billets	Seamless Tube Billets	H.R. Strip	Shapes; H.R. & C.F. Bars; Wire	Plates	Sheets	C.R. Strip; Flat Wire
201	17.00	21.50	....	....	31.00	....	....	42.25	39.00
202	18.25	24.00	31.00	36.25	33.50	36.75	38.75	42.50	42.50
301	17.75	22.25	....	36.75	32.00	38.00	....	44.25	41.00
302	19.00	24.75	32.00	37.25	34.50	38.25	40.25	44.50	44.50
302B	20.25	26.50	33.00	37.25	37.75	38.25	40.25	47.00	47.00
303	....	26.75	34.75	40.00	....	41.00	....	....	....
304	20.25	26.00	33.75	39.00	37.25	40.25	43.00	47.25	47.25
304L	....	....	38.75	44.00	42.25	45.25	48.00	52.25	52.25
305	21.75	28.25	....	39.50	40.25	40.25	43.50	50.25	50.25
308	22.00	29.00	38.50	44.25	41.25	45.50	49.75	52.00	52.00
309	29.50	38.25	46.75	53.50	53.50	54.75	58.25	67.00	67.00
309S	31.50	41.00	51.00	59.00	58.50	60.25	63.75	74.00	74.00
310	37.25	48.00	62.25	72.25	68.50	73.50	75.25	78.75	78.75
314	....	....	....	....	....	....	75.25	....	....
316	31.50	40.25	51.25	59.50	58.25	60.75	64.00	68.25	68.25
316L	....	....	56.25	64.75	63.25	65.75	69.25	73.25	73.25
317	37.25	48.25	62.75	72.75	73.50	74.50	77.00	83.75	83.75
321	25.00	32.00	38.25	44.00	44.25	45.25	49.25	54.25	54.25
18-8CbTa	29.25	38.00	45.75	52.25	53.25	53.50	58.00	66.50	66.50
403	....	....	28.75	32.75	....	34.00	36.25	....	44.00
405	17.50	23.00	26.75	31.00	32.25	32.00	33.75	42.25	42.25
410	15.00	19.50	25.50	29.50	28.00	30.50	31.75	36.25	36.25
416	....	....	26.00	30.00	....	31.00	....	....	....
420	23.50	30.25	31.00	36.00	37.75	37.25	40.75	56.00	56.00
430	15.25	19.75	26.00	30.00	28.75	31.00	32.25	36.75	36.75
430F	....	....	26.50	30.50	....	31.50	....	....	....
431	16.00	20.50	26.50	30.50	29.75	31.50	33.00	38.00	38.00
446	....	....	35.50	40.50	53.25	42.00	43.25	63.25	63.25

Stainless Steel Producers Are: Allegheny Ludlum Steel Corp.; Alloy Metal Wire Co. Inc.; Alloy Tube Div., Carpenter Steel Co.; American Steel & Wire Div., U. S. Steel Corp.; Armco Steel Corp.; Babcock & Wilcox Co.; Bethlehem Steel Co.; J. Bishop & Co.; G. O. Carlson Inc.; Carpenter Steel Co.; Charter Wire Products Co.; Cold Metal Products Co.; Crucible Steel Co. of America; Damascus Tube Co.; Wilbur B. Driver Co.; Driver-Harris Co.; Eastern Stainless Steel Corp.; Ellwood Ivins Steel Tube Works Inc.; Firth Sterling Inc.; Ft. Wayne Metals Inc.; Globe Steel Tubes Co.; Helical Tube Co.; Indiana Steel & Wire Co.; Ingersoll Steel Div., Borg-Warner Corp.; Jessop Steel Co.; Johnson Steel & Wire Co. Inc.; Joslyn Mfg. & Supply Co.; Kenmore Metals Corp.; Maryland Fine & Specialty Wire Co.; McLouth Steel Corp.; Metal Forming Corp.; McInnes Steel Co.; National-Standard Co.; National Tube Div., U. S. Steel Corp.; Newman-Crosby Steel Co.; Pacific Tube Co.; Page Steel & Tube Div., American Chain & Cable Co. Inc.; Pittsburgh Rolling Mills Inc.; Republic Steel Corp.; Rodney Metals Inc.; Rome Mfg. Co.; Rotary Electric Steel Co.; Sharon Steel Corp.; Sawhill Tubular Products Inc.; Simonds Saw & Steel Co., Specialty Wire Co. Inc.; Spencer Wire Corp.; Stainless Welded Products Inc.; Standard Tube Co.; Superior Steel Corp.; Superior Tube Co.; Timken Roller Bearing Co.; Trent Tube Co.; Tube Methods Inc.; Ulbrich Stainless Steels; United States Steel Corp.; Universal-Cyclops Steel Co.; Wallingford Steel Co.; Washington Steel Corp.

Clad Steel

	Plates—Carbon Base 10%	Plates—Carbon Base 20%	Sheets Carbon Base 20%
Stainless:			
302	....	....	30.50
304	30.30	36.05	32.50
304-L	32.30	37.95	....
310	41.30	47.00	....
316	35.50	41.40	47.00
316-L	40.00	46.10	....
316-CB	41.15	48.45	....
321	32.00	37.75	37.25
347	34.40	41.40	48.25
405	25.80	33.35	....
410	25.30	32.85	....
430	25.30	32.85	....
Inconel	49.45	65.45	....
Nickel	41.05	55.65	....
Nickel, Low Carbon	43.25	60.05	....
Monel	42.35	56.35	....
Copper*	....	....	46.00

	Strip, Carbon Base—Cold Rolled— 10%	Strip, Carbon Base—Cold Rolled— Both Sides
Copper*	30.00	38.00

*Deoxidized. Production points: Stainless-clad sheets, New Castle, Ind. I-4; stainless-clad plates, Claymont, Del. C22, Coatesville, Pa. L7, New Castle, Ind. I-4 and Washington, Pa. J3; nickel, inconel, monel-clad plates, Coatesville L7; copper-clad strip, Carnegie, Pa. S18.

Tool Steel

Grade	$ per lb	Grade	$ per lb
Regular carbon	0.275	5%Cr Hot Work	0.430-0.460
Extra Carbon	0.330	W-Cr Hot Work	0.450
Special Carbon	0.390	V-Cr Hot Work	0.470
Oil Hardening	0.430	Hi-Carbon-Cr	0.770

Grade by Analysis (%) W	Cr	V	Co	Mo	$ per lb
20.25	4.25	1.6	12.25	...	4.090
18.25	4.25	1	4.75	...	2.305-2.475
18	4	2	9	...	2.675-2.6775
18	4	2	....	...	1.765
18	4	1	....	...	1.600
13.75	3.75	2	5	...	2.245
13.5	4	3	....	...	1.865
9	3.5	..	....	...	1.180
6	4	2	....	5	1.105
6	4	3	....	6	1.350
1.5	4	1	....	8.5	0.960

Tool steel producers include: A4, A8, B2, B8, C4, C9, C13, C18, D4, F2, J3, M14, S8, U4, V2 and V3.

Pig Iron

F.o.b. furnace prices in dollars per gross ton, as reported to STEEL. Minimum delivered prices are approximate and do not include 3% federal tax.

Birmingham District	Basic	No. 2 Foundry	Malle-able	Besse-mer
AlabamaCity,Ala. R2	54.50	55.00‡	....	....
Birmingham R2	54.50	55.00‡	....	....
Birmingham U6	....	55.00‡	59.00	....
Woodward,Ala. W15	54.50	55.00‡	59.00	....
Cincinnati, deld.	....	62.70	....	....
Buffalo District				
Buffalo H1, R2	58.50	59.00	59.50	60.00
Tonawanda,N.Y. W12	58.50	59.00	59.50	60.00
N.Tonawanda,N.Y. T9	....	59.00	59.50	60.00
Boston, deld.	69.15	69.65	70.15	....
Rochester,N.Y. deld.	61.52	62.02	62.52	....
Syracuse,N.Y. deld.	62.62	63.12	63.62	....
Chicago District				
Chicago I-3	58.50	59.00	59.00	59.50
Gary,Ind. U5	58.50	....	59.00	....
S.Chicago R2	58.50	....	59.00	....
S.Chicago,Ill. Y1	58.50	59.00	59.00	59.50
S.Chicago,Ill. U5, W14	58.50	....	59.00	59.50
Milwaukee, deld.	60.67	61.17	61.17	61.67
Muskegon,Mich. deld.	....	65.30	65.30	....
Cleveland District				
Cleveland A7, R2	58.50	59.00	59.00	59.50
Akron,O., deld.	61.25	61.75	61.75	62.25
Lorain,O. N3	58.50	....	....	59.50
Mid-Atlantic District				
Bethlehem,Pa. B2	60.50	61.00	61.50	62.00
NewYork, deld.	....	64.78	65.28	....
Newark, deld.	63.52	64.02	64.52	65.02
Birdsboro,Pa. B10	60.50	61.00	61.50	62.00
Chester,Pa. P4	60.50	61.00	61.50	....
Philadelphia, deld.	62.16	62.66	63.16	....
Steelton,Pa. B2	60.50	61.00	61.50	62.00
Swedeland,Pa. A3	60.50	61.00	61.50	62.00
Philadelphia, deld.	62.16	62.66	63.16	63.66
Troy,N.Y. R2	60.50	61.00	61.50	62.00
Pittsburgh District				
NevilleIsland,Pa. P6	58.50	59.00	59.00	....
Pittsburgh (N&S sides), Aliquippa,deld.	....	60.37	60.37	60.87
McKeesRocks, deld.	....	60.04	60.04	60.54
Lawrenceville,Homestead, Wilmerding,Monaca, deld.	....	60.66	60.66	61.16
Verona,Trafford, deld.	60.69	61.19	61.19	61.69
Brackenridge, deld.	60.95	61.45	61.45	61.95
Bessemer,Pa. U5	58.50	....	59.00	59.50
Clairton,Rankin,S.Duquesne,Pa. U5	58.50	....	....	....
McKeesport,Pa. N3	58.50	....	....	59.50
Midland,Pa. C18	58.50	....	....	....

Youngstown District	Basic	No. 2 Foundry	Malle-able	Besse-mer
Hubbard,O. Y1	....	....	59.00	....
Sharpsville,Pa. S6	58.50	....	59.00	59.50
Youngstown Y1	....	....	59.00	59.50
Youngstown U5	58.50	....	....	59.50
Mansfield,O., deld.	63.40	....	63.90	64.40
Duluth I-3	58.50	59.00	59.00	59.50
Erie,Pa. I-3	58.50	59.00	59.00	59.50
Everett,Mass. E1	62.00	62.50	63.00	....
Fontana,Calif. K1	64.50	65.00	....	....
Geneva,Utah C11	58.50	59.00	....	....
GraniteCity,Ill. G4	60.40	60.90	61.40	....
Ironton,Utah C11	58.50	59.00	....	....
LoneStar,Texas L6	....	55.00*	....	....
Minnequa,Colo. C10	60.50	61.00	61.50	....
Rockwood,Tenn. T3	....	55.00‡	59.00	....
Toledo,O. I-3	58.50	59.00	59.00	59.50
Cincinnati, deld.	64.26	64.76	....	....

*Phos. 0.51-0.75%; $56, Phos. 0.31-0.50%.
‡Intermediate (Phos. 0.31-0.69%), $56.

PIG IRON DIFFERENTIALS

Silicon: Add 50 cents per ton for each 0.25% Si or percentage thereof over base grade, 1.75-2.25%, except on low phos iron on which base is 1.75-2.00%.
Manganese: Add 50 cents per ton for each 0.50% manganese over 1% or portion thereof.
Nickel: Under 0.05% no extra; 0.50-0.74%, inclusive, add $2 per ton and each additional 0.25%, add $1 per ton.

BLAST FURNACE SILVERY PIG IRON, Gross Ton

(Base 6.00-6.50% silicon; add $1 for each 0.5% Si; 75 cents for each 0.50% Mn over 1%)

Jackson,O. G2, J1	$67.50
Buffalo H1	68.75

ELECTRIC FURNACE SILVERY IRON, Gross Ton

(Base 14.01-14.50% silicon; add $1 for each 0.5% Si to 18%; $1 for each 0.50% Mn over 1%; $2 per gross ton premium for 0.045% max P)

NiagaraFalls,N.Y. P15	$83.50
Keokuk,Iowa, (Open-hearth & Fdry, freight allowed K2)	90.00
Keokuk, O.H. & Fdry, 12½ lb piglets, 16% Si, frgt allowed K2	93.00

LOW PHOSPHORUS PIG IRON, Gross Ton

Lyles,Tenn. T3 (Phos. 0.035% max)	$72.50
Steelton,Pa. B2 (Phos. 0.035% max)	66.50
Philadelphia, deld.	70.05
Troy,N.Y. R2 (Phos. 0.035% max)	66.50
Cleveland A7 (Intermediate) (Phos. 0.036-0.075% max)	63.50
Duluth I-3 (Intermediate) (Phos. 0.036-0.075% max)	63.50
Erie,Pa. I-3 (Intermediate) (Phos. 0.036-0.075% max)	63.50

Warehouse Steel Products

Representative prices, per pound, subject to extras, f.o.b. warehouse. City delivery charges are 25 cents per 100 lb except: Buffalo, Cleveland, Erie, 30 cents; Moline, Norfolk, Richmond, Washington, 20 cents; Birmingham, Chattanooga, Jackson, 15 cents; Baltimore, Boston, Los Angeles, New York, Philadelphia, Portland, San Francisco, 10 cents; Atlanta, Houston, Seattle, Spokane, no charge.

	SHEETS				STRIP		BARS			Standard Structural Shapes	PLATES	
	Hot-Rolled	Cold-Rolled	Gal. 10 Ga.†	Stainless Type 302	H.R.*	C.R.*	H.R. Rds.	C.F. Rds.‡	H.R. Alloy 4140††[5]		Carbon	Floor
Atlanta	7.14	8.20	8.87	....	7.40	...	7.42	9.39	....	7.63	7.49	9.48
Baltimore	7.03	8.32	8.37	....	7.65	...	7.61	8.62[3]	13.44	7.93	7.21	8.87
Birmingham	6.80	7.90	8.85	....	7.06	...	7.08	9.35	....	7.28	6.99	9.10
Boston	7.70	8.81	10.27	45.67	7.96	...	7.83	9.53	14.45	8.13	7.89	9.36
Buffalo	6.80	8.05	9.77	....	7.15	...	7.10	7.90	13.10	7.40	7.15	8.70
Chattanooga	6.95	8.10	8.60	....	7.20	...	7.20	9.18	....	7.45	7.25	9.05
Chicago	6.80	8.09	8.50	49.05	7.06	...	7.08	7.75	12.85	7.28	6.99	8.46
Cincinnati	6.92	8.08	8.90	46.10	7.30	...	7.32	8.05	13.09	7.75	7.28	8.71
Cleveland	6.80	8.09	8.85	49.16	7.16	...	7.14	7.85	12.91	7.61	7.16	8.63
Detroit	6.99	8.28	8.78	43.50	7.34	...	7.36	8.04	13.05	7.75	7.27	8.65
Erie, Pa.	6.80	7.90	8.85	....	7.15	...	7.08	7.85	....	7.40	7.15	8.63
Houston	7.85	8.75	10.49	....	8.15	...	8.25	9.85	14.00	8.20	7.80	9.20
Jackson, Miss.	7.10	8.20	9.20	....	7.40	...	7.40	9.44	....	7.60	7.45	9.30
Los Angeles	8.05	10.00	11.00	....	8.35	...	8.05	11.25	14.25	8.30	8.05	10.25
Milwaukee	6.89	8.18	8.59	....	7.15	...	7.17	7.94	12.94	7.45	7.08	8.55
Moline, Ill.	7.15	8.44	8.85	....	7.41	...	7.43	8.10	....	7.63	7.34	...
New York	7.46	8.68	9.44	44.95	8.07	...	7.96	9.48	13.28	7.99	7.76	9.19
Norfolk, Va.	7.25	...	...	....	7.65	...	7.65	9.50	....	7.95	7.45	8.95
Philadelphia	7.14	8.42	9.35	45.98	7.67	9.02	7.64	8.46	13.16	7.74	7.37	8.69**
Pittsburgh	6.80	8.09	9.20	49.00	7.16	...	7.08	7.85	12.85	7.28	6.99	8.46
Portland, Oreg.	7.80	8.80	10.65	....	8.00	...	7.95	12.20	15.00	7.85	7.75	9.66
Richmond, Va.	7.00	...	9.47	....	7.65	...	7.70	8.85	....	7.95	7.20	9.10
St. Louis	7.09	8.38	9.19	43.89	7.35	...	7.37	8.14	13.14	7.68	7.28	8.75
St. Paul	7.46	8.59	9.16	....	7.72	...	7.74	8.51	13.51	7.94	7.65	9.12
San Francisco	8.10	9.65	10.15	51.65	8.35	...	8.05	11.20	14.25[3]	8.25	8.05	10.25
Seattle	8.55	10.40	10.80	54.00	8.65	...	8.35	11.70	14.60	8.30	8.20	10.10
Spokane	8.55	11.00[7]	10.80	....	9.05	...	8.35	11.80	15.35	8.30	8.20	10.60
Washington	7.50	8.79	7.97	....	8.12	...	8.08	9.09	....	8.40	7.68	9.34

Prices do not include gage extras; †prices include gage and coating extras (based on 12.50-cent zinc), except in Birmingham (coating extra excluded); ‡includes 35-cent special bar quality extras; **⅛-in. and heavier; ††as annealed; §§under ½-in.

Base quantities, 2000 to 4999 lb except as noted; Cold-rolled strip and cold-finished bars, 2000 lb and over except in Seattle, 2000 to 9999 lb, and in Los Angeles, 6000 lb and over; stainless sheets, 8000 lb except in Chicago. New York and Boston, 10,000 lb, and in San Francisco, 2000 to 4999 lb; hot-rolled products on West Coast, 2000 to 9999 lb; [2]—500 to 9999 lb; [3]—400 to 999 lb; [4]—4000 lb and over; [5]—1000 to 1999 lb; [6]—1000 lb and over; [7]—1500 to 3999 lb; [8]—2000 to 3999 lb; [9]—f.o.b. local delivery in lots of 10,000 lb and over.

FAMOUS FIRSTS IN THE IRON & STEEL INDUSTRY

AMERICA'S FIRST IRON PLATE ROLLING MILL

Thirteen years after the War of 1812, Lukens Steel Company in Coatesville, Pennsylvania, was producing America's first rolled iron plates for boilers. Using tools and equipment that would seem exceedingly crude today, they rolled charcoal blooms into plates.

In 1825 the production of plates was limited to less than 34 inches width in this water-driven mill. Today, Lukens Steel Company has the country's largest plate mill, producing rolled plates up to 195 inches in width.

Another famous first in the iron and steel industry is BAKER'S MAGDOLITE, the original dead-burned dolomite. Ever since its beginning, BAKER'S MAGDOLITE has maintained a superior product. One that is always 5 ways better: Composition, Preparation, Strength, Economy and Quality. Order BAKER'S MAGDOLITE next time, and see for yourself how it delivers more uniform ingots, in greater numbers, and with less defective material.

5/55

ANOTHER FAMOUS FIRST

JEBCO PRODUCTS SINCE 1889

BAKER'S MAGDOLITE

The original dead-burned dolomite

THE J. E. BAKER COMPANY

YORK, PENNSYLVANIA • PLANTS: BILLMEYER, YORK, PENNSYLVANIA • MILLERSVILLE, OHIO

Silicon Steel: Nearing the Record

(Shipments in thousands of tons)

*Estimated
Source: American Iron & Steel Institute

Electrical Steel Surges

CONSUMPTION of electricity is expected to quadruple by 1975. That's good news to producers of silicon steel, because the two industries grow together. Wherever electricity is generated or used to run fractional horsepower motors, you'll find electrical steel, as it is sometimes called.

On the basis of figures for the first eight months of 1955, producers will ship about 780,000 tons of electrical steel this year, just short of the record (820,096 tons) in 1953 (see chart). Consumption probably will top 1953's, however, because that was the year of the great inventory buildup. This brisk business will probably continue into 1956, if bookings are any indication. Several producers that make this steel on an allotment basis already have opened the books for the first quarter of next year. All allotments have been snapped up.

Trends—There are four big developments in this industry. The one most talked about is the rapid rise of grain oriented silicon (STEEL, Oct. 11, 1954, p. 181). Introduced in 1937, today, this product accounts for about one-fourth of all silicon steel production. Only four of the eleven companies in this business produce grain oriented, and they are doing most of the expansion in this direction.

U. S. Steel Corp. is installing facilities at Vandergrift, Pa., for expected availability in 1956. Armco Steel Corp. is increasing its facilities at Butler, Pa. Crucible Steel Co. of America, most recent steel producer to get into the field, began shipments in September. Allegheny Ludlum Steel Corp. began operation of its new, 56-in., continuous, cold-rolling mill at Brackenridge, Pa., in September, 1954. While it rolls both stainless and electrical steel, electrical dominates the rolling schedule. The company is installing additional equipment and hopes to increase production of this steel before year end.

Feeling the Pressure—Another major producer of silicon sheet reports that its customers have been putting pressure on it to get into the production of grain oriented, but so far the company has not moved in that direction.

All the expansion has not been in grain oriented, however. Republic Steel Corp., which produces regular silicon steel, says it started with just one annealing furnace for electrical sheet in 1935. Now it has fourteen, with three more to be completed soon and another six in the planning stage. Most producers feel there is bound to be further expansion in the industry, because even now the electrical industry has outstripped the capacity of silicon steel producers to supply it.

Trend No. 2—Mill customers are showing more preference than ever for coiled stock, pushing handmill sheets farther in the background. Producers that have older equipment are converting to continuous mill operations or offering welded coils. Even though coils are more expensive, they are more economical to handle and fabricate.

Trend No. 3 — Normally, electrical steel undergoes several anneals in the mill and is sold with a guarantee of minimum core loss. There is a trend to stop the annealing process in the mill short of full anneal and selling the steel without the core loss guarantee for about $10 a ton under the normal price.

The fabricator stamps the fine grain metal and finishes the anneal himself. It is up to the fabricator to maintain close metallurgical control of the anneal, but if done properly, the finished product will have satisfactory magnetic qualities. The savings come from the cheaper mill price and longer die life.

Trend No. 4—Some mills report they are plating the core material with a varnish or similar protective coating. This serves two purposes: The coating acts as a lubricant for the dies, and it provides a better insulation than the oxide coating the steel normally develops during annealing. The cost of the coated steel is $12 to $18 a ton more than the uncoated, but increased die life and improved magnetic qualities of the core make up for it, producers claim.

The instability of the copper industry over the past year has caused great concern among customers, electrical steel producers say. In the long run, the steelmen think this situation will result in less copper and more— or higher grade— silicon steel in motors, generators and transformers.

New Markets—Although big power equipment is the biggest single user of silicon steel, there are many smaller uses which probably outweigh it when they are added up. Appliances have provided the big surge in the postwar years. Electronics is a real comer. Even though a single radio or television set does not use a large amount of electrical steel, the industry as a whole is becoming a big factor.

These new and smaller uses of silicon steel have changed the marketing patterns of the producers in the last 15 years. One producer states that in 1940, just two companies bought about 80 per cent of all silicon steel produced. They can account for only about 40 per cent

of the total market today.

Silicon steel producers are confident that their marketing pattern is not static. It will expand and shift with new uses and increased electrical consumption far into the future.

Sheets, Strip . . .

Sheet & Strip Prices, Pages 191 & 192

Most of the sheet mills are entering new business for first quarter shipment. But they are not accepting all tonnage offered. With due allowances for arrearages, some makers won't have more than half their first quarter output available for new orders. This will be especially true of hot and cold-rolled sheets, and in lesser degree in galvanized and certain specialties, such as electrical sheets and enameling stock.

For what consolation it may afford buyers, the situation with most sheetmakers should be no worse in the first quarter than it is at present; it should be better than it was in the third quarter this year, during which time the mills were badly oversold, having booked heavy miscellaneous consumer business in anticipation of a summer slump in automotive requirements—which never developed.

Cowles

DRYORTH*

Anhydrous Sodium Orthosilicate

High-powered Cleaning at Low Cost

• Cowles DRYORTH is free-flowing, granular, dust-free. It contains not less than 60% Na_2O and is quickly and completely soluble.

DRYORTH is a fast, economical cleaner for

★ strip and sheet steel
★ steel pipe — before galvanizing
★ heavy ferrous parts and castings

Try DRYORTH for these and other basic cleaning operations. DRYORTH — anhydrous sodium orthosilicate — assures long cleaning mileage at low cost.

*Reg. U. S. Pat. Off.

Cowles also manufactures a complete line of cleaners engineered to handle all kinds of cleaning problems on both ferrous and non-ferrous metals. The Cowles Technical Man in your area will be glad to discuss any metal cleaning problems you have. Write us today!

COWLES CHEMICAL COMPANY
7016 Euclid Avenue
Cleveland 3, Ohio

Inland Steel Co. started up its new No. 2 galvanizing line last week, to become the third largest producer of continuous galvanized steel in the country. Under construction for a year, the new line has a rated capacity of 6000 tons of continuous coated sheets a month and will raise the company's capacity for the product to about 20,000 tons monthly. All three lines were constructed under license from Armco Steel Corp.

Pressure for sheets is building up in the St. Louis area where several ingot conversion deals are reported.

Steel Bars . . .

Bar Prices, Page 190

Most sellers of hot-rolled carbon bars are entering new business on their books for the first quarter. As a general thing, bookings are on a month-to-month basis.

Sellers' district offices have been flooded with requests since first quarter books were opened. Little supply relief is expected in the early part of next year.

Sales of cold-finished bars are strong to a wide variety of consuming industries, with machine tool and auto builders' purchases ahead of those by miscellaneous users. Sellers of alloy bars will enter the first quarter on a more or less current delivery basis.

Reinforcing Bars . . .

Reinforcing Bar Prices, Page 190

Reinforcing bar producers in the Pacific Northwest are operating at approximate capacity. They hold fair order backlogs, though recent bookings have consisted mostly of small contracts, involving less than 100 tons each.

Tubular Goods . . .

Tubular Goods Prices, Page 194

The first quarter will see the continuance of current heavy demand for mechanical and pressure tubing. Pittsburgh district mills are booking first quarter orders on specialty tube products, with January rolling schedules practically filled. Oil country tubular goods are already sold out through the first quarter.

Some utilities and other users of seamless tubing are finding the product so difficult to obtain they are switching to buttweld when possible. Buttweld production is rising, deliveries are lengthening.

More extended deliveries on seamless and electricwelded pipe are stimulating forward buying in New England, notably by the utilities which

are placing part of their estimated 1956 requirements. First quarter schedules are well filled on 5 in. and larger sizes. Buttweld and electric-welded tubing shipments are still available in four to five weeks.

Wire . . .

Wire Prices, Pages 192 & 193

Three operating divisions of U. S. Steel Corp. (American Steel & Wire, Tennessee Coal & Iron and Columbia-Geneva) announced a revision in size extras for hot-rolled carbon steel wire rods 35/64-in. and smaller. These changes, effective Oct. 29, represent increases ranging from $1 to $4 a ton.

Manufacturers wire sales continue to exceed expectations. Tonnage is difficult to obtain for fourth quarter shipment. Orders are being taken for the first quarter.

Demand for merchant products is off seasonally, notably farm fence. Competition from foreign nails and fencing is reported increasing.

Warehouse . . .

Warehouse Prices, Page 195

Warehouse stocks average about half those held on Jan. 1. The tonnage would be lower if distributors were not exercising limitations on quantities shipped. Products in tightest supply are structurals, plates and sheets—in that order. Seasonal easing is developing in galvanized sheets.

Prospects for an improvement in steel supply during the first quarter are growing dim as steelmakers open order books for that period. A growing number of regular mill customers are trying to build their stocks by purchasing from warehouses. They are generally unsuccessful. Few warehouses have sufficiently well-balanced stocks to cover their needs.

Plates . .

Plate Prices, Page 190

Despite efforts to bring commitments into better balance, plate producers are still well oversold. Few, if any, believe they will be able to start off the new year on an even keel.

Mills that have opened books for first quarter orders have made allowances in one degree or another for arrearages that they are sure will have to be taken into account.

Demand is heavy for tankwork of all descriptions; also for construction and heavy equipment. Car requirements are being restricted because of lack of steel, plates in particular. Due to delays by the railroads, carbuilders were forced to come into the steel market this summer when demand elsewhere was already taxing producers' facilities to the limit. Builders of this equipment will get only a small portion of what they require this year, but they should fare better in the first and second quarters next year.

About 52,500 tons of steel, chiefly plates, will be required for the superaircraft carrier recently awarded to the New York Shipbuilding Corp., Camden, N. J. Requirements will include 1020 tons of aluminum and 1000 tons of weld metal. March delivery is being asked on initial steel requirements.

Freight car requirements continue to expand, with the Reading in the market for 1400 cars and the Pennsylvania inquiring for 4000 tons of steel for 200 piggyback cars to be built in its own shops at Altoona, Pa.

The Claymont, Del., plate producer has resumed operations on its larger mill following a long suspension for repairs.

Structural Shapes . . .

Structural Shape Prices, Page 190

Order backlogs of the leading structural fabricating shops continue to increase, now standing at eight to nine months in some instances. The

THOMAS FLEXIBLE COUPLINGS...
for more years of better service!



Installation of three 351-DBZ-B Thomas Couplings in Columbia Breweries, Tacoma, Wash. between motors and Vilter refrigeration compressors.

Patented Flexible Disc Rings of special steel transmit the power and provide for parallel and angular misalignment as well as free end float.

DISTINCTIVE ADVANTAGES

FACTS	EXPLANATION
NO MAINTENANCE	Requires No Attention. Visual Inspection While Operating.
NO LUBRICATION	No Wearing Parts. Freedom from Shut-downs.
NO BACKLASH	No Loose Parts. All Parts Solidly Bolted.
CAN NOT "CREATE" THRUST	Free End Float under Load and Misalignment. No Rubbing Action to cause Axial Movement.
PERMANENT TORSIONAL CHARACTERISTICS	Drives Like a Solid Coupling. Elastic Constant Does Not Change. Original Balance is Maintained.



Thomas Couplings are made for a wide range of speeds, horsepower and shaft sizes and can be assembled or disassembled without disturbing the connected machines, except in rare instances.



THOMAS

Write for our new Engineering Catalog No. 51A

THOMAS FLEXIBLE COUPLING COMPANY
Largest Exclusive Coupling Manufacturer in the World
WARREN, PENNSYLVANIA, U.S.A.

500 Gears . . .

DOWN THE DRAIN

PRESIDENT, THE CINCINNATI GEAR CO.

We don't like to admit it, but we make our share of mistakes. Fortunately, these do not occur too often but when they do, we see to it that they do not reach you, our customer. Before any gear leaves our factory, it goes through a tough final inspection. Each of our highly trained inspectors checks the work as if he were the inspector in the customer's plant. These men answer only to me, thereby eliminating any possibility of influence that might be exerted by those interested only in production.

Recently when we were manufacturing a large order of bronze worm gears, a very serious error was inadvertently made during the manufacturing process. In spite of constant vigilance, this was not discovered until the gears reached final inspection. The boys sure found it at that time. Actually the error amounted to the fact that the teeth had been cut about .010 too deep. While it might have been possible to make the mating worms oversize, this thought was the farthest from our minds. Because the worm gears were NOT correct, they were scrapped and replaced. The loss resulted in one of the largest single scrapped orders that we ever had. It hurt.

We believe that our ardent will to supply gears of only the highest quality pays off. Our customers have the assurance that when they receive gears from CINCINNATI GEAR, these have been through a rigid and thorough inspection and are ready for assembly. Our men understand that there is "no compromise with quality," and that is the policy under which they operate. We also believe this is the least costly for our customers because once they receive our gears, they know there will be no "hidden" costs during assembly.

THE CINCINNATI GEAR CO.

CINCINNATI 27, OHIO

"Gears — Good Gears Only"

CINTI

shortage of steel is restricting operations and is having some bearing on the backlog situation. But the major factor still is heavy construction demand. Seasonal influences are tending to retard business slightly, but there is still more work coming out than fabricators can promptly cope with.

Shape producers are beginning to accept tonnage for first quarter shipment. Carry-overs in some cases may be a little less than at the beginning of the current quarter, but, if so, it will be because of rejections of considerable new tonnage in recent weeks.

New England shops are hard pressed for plain material. A leading producer is shipping August tonnage. An eastern Pennsylvania supplier is overbooked, and no help is in sight from Pittsburgh mills.

Bids have been closed by the Consolidated Edison Co. of New York on 18,000 tons for two power house units. Each unit will require 9000 tons, with one definitely scheduled for erection in Astoria and the other for likely erection in Staten Island.

STRUCTURAL SHAPES . . .

STRUCTURAL STEEL PLACED

3200 tons, plant addition, General Electric Co., Louisville, to Ingalls Iron Works, Birmingham.

2000 tons, Aviation Trades high school, Queens, New York, for the Board of Education, through Caristo Contracting Co., Brooklyn, N. Y., general contractor, to Lehigh Structural Steel Co., Allentown, Pa.

1900 tons, 21-story apartment, 59th St. and Sutton Place, New York, to Bethlehem Steel Co., Bethlehem, Pa.

1000 tons, assembly shop, Bath Iron Works, Bath, Me., to American Bridge Division, U. S. Steel Corp., Pittsburgh.

950 tons, Washington state Skagit county bridge (erected), to United Concrete Pipe Co., Auburn, Wash.; Neukirch Bros., Seattle, general contractor.

750 tons, coal preparation plant, Clinchfield Coal Corp., Dante, Va., through the Link-Belt Co. to Bristol Steel & Iron Works Inc., Bristol, Va.

600 tons, RCA factory building, Cambridge, O., to American Bridge Division, U. S. Steel Corp., Pittsburgh.

475 tons, senior high school, Rosalyn, Long Island, N. Y., to Schacht Steel Construction Inc., New York.

450 tons, building, High Voltage Engineering Co., Burlington, Mass., to A. O. Wilson Structural Co., Cambridge, Mass.

400 tons, Robert E. Speer library, Princeton University, Princeton, N. J., to American Bridge Division, U. S. Steel Corp., Pittsburgh.

385 tons, Bailey junior high school, West Haven, Conn., to Connecticut Steel Co., New Haven; Fusco-Amatruda Co., New Haven, general contractor; 80 tons of reinforcing bars, Fox Steel Co., Orange, Conn.

375 tons, building, Tracerlab Inc., Waltham, Mass., to A. O. Wilson Structural Co., Cambridge, Mass.; Gilbane Building Corp., Providence, R. I., general contractor.

340 tons, state bridge, Rockland county, N. Y., to Pine Brook Iron Works, Scranton, Pa.

250 tons, plant, Pennsylvania Power & Light Co., Harrisburg, Pa., to Reading Metalcraft Co., Reading, Pa.

250 tons, building, Lowell Industrial Development Commission, Lowell, Mass., to A. O. Wilson Structural Co., Cambridge, Mass.

300 tons, crossline railroad bridges, Charlotte, N. C., to American Bridge Division, U. S. Steel Corp., Pittsburgh; Blythe Bros. Co. Inc., Charlotte, general contractor; 90 tons



That 5 minute talk

SAVED

$6,532 on fuel

It's tough on the BTU Burglar, but the word is getting around just the same . . . that industrial furnaces *don't* have to be burgled for billions of BTU's—worth thousands of dollars—per year.

Typical example: A bolt manufacturer relined three furnaces with *lightweight* B&W Insulating Firebrick. Analysis of fuel cost per ton of steel reveals that the B&W linings save $6,532 per year, compared with the ordinary heavy firebrick linings in the plant's other furnaces.

Heavy furnace linings waste your fuel dollars two ways: They soak up and hold large quantities of heat which are lost when the furnace is cooled; and they conduct and lose too much heat through the walls. Lightweight insulating firebrick, containing millions of tiny air cells, heat up and cool quickly, absorbing and storing very little heat. Also, they resist heat flow, keeping it inside the furnace to do productive work.

If you want to save on fuel, your logical choice is the lightest weight refractory you can buy—*lightweight* B&W Insulating Firebrick.

Investigate now so that you can try B&W Insulating Firebrick next time you reline your furnace or kiln. Write today for complete facts or contact the B&W Refractories Engineer in your locality.

BABCOCK & WILCOX

THE BABCOCK & WILCOX CO.
REFRACTORIES DIVISION
GENERAL OFFICES 161 EAST 42nd ST. NEW YORK 17 N.Y.
WORKS: AUGUSTA, GA.

R-506

of reinforcing bars, Easterby & Mumaw, Atlanta.

300 tons plus, Oregon state Yamhill county bridge, to unstated interest; Hamilton & Thomas, Eugene, Oreg., general contractor.

225 tons, warehouse and garage, New England Telephone & Telegraph Co., Brockton, Mass., to Groisser & Shlager Iron Works, Somerville, Mass.; Turner Construction Co., Boston, general contractor.

200 tons, pulp plant project, to Isaacson Iron Works, Seattle.

STRUCTURAL STEEL PENDING

18,000 tons, two power house units, Consolidated Edison Co. of New York, New York; bids closed Nov. 4.

545 tons, five beam bridges, state highway, Spaulding turnpike, Dover, N. H. 200 tons, bulk warehouse, Ladd Air Field, Alaska; bids to U. S. Engineer, postponed to Nov. 11.

220 tons, state bridge, Union county, Pa.; bids Nov. 18.

REINFORCING BARS . . .

REINFORCING BARS PLACED

500 tons, state bridge, Ocean county, N. J., to Bethlehem Steel Co., Bethlehem, Pa.

115 tons, health center, Newton, Mass., to Northern Steel Inc., Medford, Mass.; S. & A. Allen Construction Co., Boston, general contractor; 50 tons of structurals to Groisser & Shlager Iron Works, Somerville, Mass.

110 tons, Washington state Skagit river bridge and 25 tons for a Washington state Whatcom county project, to Northwest Steel Rolling Mills Inc., Seattle.

REINFORCING BARS PENDING

380 tons, three state bridges, North Providence-Lincoln, R. I.

240 tons, five beam bridges, Spaulding turnpike, Dover, N. H.; also 120 tons of steel bearing piles.

236 tons, state bridge work, Cambria county, Pa., bids Nov. 18; project will also require 2567 tons of structural steel.

PLATES . . .

PLATES PLACED

300 tons, 3,950,000-gal standpipe, Wilmette, Ill., to Chicago Bridge & Iron Co., Chicago.

181 tons, H-piling, Idaho state Priest river bridge, to Bethlehem Pacific Coast Steel Corp., Seattle; Kiewit-Daugherty, joint contractors.

PLATES PENDING

2600 tons, fuel storage tanks, including 25 vertical, bolted, knocked down, 10,000-bbl capacity, Bureau of Yards and Docks, Navy, Port Hueneme, Calif.; also 36 tanks, 4520 to 5434-gal capacity.

850 tons, eight 25,000-bbl fuel storage tanks, Elmendorf Air Base, Alaska; bids Nov. 15, U. S. Engineer, Anchorage, Alaska.

150 tons, 1-million-gal standpipe, District No. 75, Bellevue, Wash.; Pittsburgh-Des Moines Steel Co., Seattle, low at $59,480.

150 tons, 1-million-gal storage tank; Pittsburgh-Des Moines Steel Co., Seattle, low at $40,014 to Quincy, Wash.

130 tons, fuel storage tanks, Fairchild Air Base, Washington; bids Nov. 17 to the U. S. Engineer, Seattle.

PIPE . . .

CAST IRON PIPE PLACED

131 tons, various sizes, to Pacific States Cast Iron Pipe Co., Seattle, by Tacoma, Wash.

CAST IRON PIPE PENDING

100 tons, 1564 ft of 20-in., class 150; bids to Seattle, Nov. 4.

RAILS, CARS . . .

RAILROAD CARS PLACED

Alaska railroad, 50 seventy-ton flatcars, to the Warren Car Co., Warren, Pa.

Nickel Plate, 100 flatcars, to its Ironton, O. shops.

Pennsylvania, 200 piggyback cars, to its Altoona, Pa. shops.

St. Louis-Southwestern, 700 fifty-ton boxcars, to Pullman-Standard Car Mfg. Co., Chicago.

RAILROAD CARS PENDING

Reading, 500 seventy-ton gondolas, 500 seventy-ton hoppers and 400 boxcars.

RENT OR BUY
SILENT HOIST
LIFTRUK
on the
"DAY-BY-DAY
EARN-ITS-WAY
PLAN"

3-5-7½-10-15 ton
CAPACITIES

If you can reasonably use a Heavy Duty LIFTRUK for at least two hours a day average, to improve the movement of goods in process or reduce materials handling operations, then you should be interested in this unusual "rent-or-pay-as-you-use" plan. Proper cost accounting methods often show that man-hours saved, storage space gained, or time in transit reduced, add up to a profit well above the payments required for LIFTRUK for purchase or rental charges.

Exclusive FLUID DRIVE

Write for "Earn-Its-Way" Plan to

SILENT HOIST & CRANE CO.
Pioneer Mfrs. of Heavy Duty Materials-Handling Equipment
849 63rd Street, Brooklyn 20, N. Y.

This is the NEW
WISCONSIN
Model ACN, 5½ H. P.
Single Cylinder
HEAVY-DUTY
Air-Cooled ENGINE



Here is a new, light weight engine, designed and built to Wisconsin heavy-duty standards in all details, offering original equipment builders and engine users maximum power advantage and performance in a 2.3 to 5.6 hp. range at 1600 to 3600 rpm.

Like all Wisconsin Engines, the Model ACN has the built-in Lugging Power that hangs on through the shock load pinches and keeps the job moving without stalling. With a 2⅝" bore x 2¾" stroke, it has a 14.88 cu. in. displacement.

Heavy-duty features include tapered roller main bearings at BOTH ends of the crankshaft; rotary type high tension OUTSIDE Magneto with Impulse Coupling for quick, all-weather starts at low cranking speed, pump-circulated splash lubrication *plus* efficient AIR-COOLING from extreme sub-zero to 140° F.

Perhaps this is just the power component you have been looking for — *power to fit the machine; power to fit the job.* Write for Bulletin S-179.

MOST H.P. HOURS
WISCONSIN MOTOR CORPORATION
World's Largest Builders of Heavy-Duty Air-Cooled Engines
MILWAUKEE 46, WISCONSIN

A 8495-½ AA

You see
FREEWAY
WASHERS
everywhere...

because they're

made better and cost less!

Regardless of the metal you specify . . . you'll find Freeway Washers are made better, cost less! They're flat, burr-free, concentric . . . to cut assembly time in your own plant. And they're priced LOW . . . because patented dies enable us to pass definite production savings on to you. Quotations gladly submitted.

Freeway semi-precision ball bearings, for shafts to 5/8", have case hardened races to withstand heavy radial loads. An ideal, inexpensive answer to your low RPM problems. Write today.

Freeway-formed stampings are blanked, drawn and trimmed in ONE operation. This exclusive processing method insures you better small parts . . . at minimum cost. The coupon will bring you additional facts.

Freeway
WASHER & STAMPING COMPANY

P. O. Box 1756, Cleveland 5, Ohio

Gentlemen: Please send us more facts about . . . . .
( ) Washers, ( ) Bearings, ( ) Stampings.

Company. . . . . .

Street. . . . . .

City. . . . . State. . . . . .

Signature. . . . . .

A

COWLES

GANG SLITTING KNIVES

OVER 30 YEARS EXPERIENCE

Standard for *Service* and *Durability*. Ground to extremely close Tolerances and Finish. Made by *Toolmakers*.

COWLES
TOOL COMPANY
2086 W. 110th ST. CLEVELAND 2, OHIO

MODERN ELECTROPLATING

563 PAGES
ILLUSTRATED

Price $8.50 Postpaid

BY ALLEN G. GRAY, Technical Editor, STEEL Magazine.

Brings you a complete, up-to-date one-volume summary of current industrial electroplating processes. The only book that emphasizes both practical aspects and basic theory. **The Penton Publishing Company,** Book Department, 1213 West Third St., Cleveland 13, Ohio.

ARTUS
PLASTIC
SLITTING
MACHINE
SHIMS

COST JUST A FRACTION OF METAL SPACERS

THE COLOR TELLS THE THICKNESS

ALWAYS RETAINS UNIFORMITY AND EVENNESS UNDER ALL NORMAL CONDITIONS

Save Time! Save Money!

INDUSTRIAL PRODUCTS SUPPLIERS
201 South Dean Street
Englewood, N. J.

So many standard styles. . . . . .

. . . . . *one must be just right for you!*

For more than 67 years we have been producing metal-working tools and adding to our standard line. Today we keep such an extensive range of styles and sizes of PUNCHES and DIES on hand that we can fit most makes of punch presses from stock. The tools you need are *immediately available* when you need them—at regular *low, standard prices.*

SEND FOR OUR COMPLETE CATALOG SHEETS
SEE HOW YOU CAN SAVE WITH LEWTHWAITE TOOLS

T. H. LEWTHWAITE MACHINE CO., INC.

310 East 47th Street, New York 17, N. Y.

Current Ferroalloy Quotations

MANGANESE ALLOYS

Spiegeleisen: Carlot, per gross ton, Palmerton, Pa. 21-23% Mn, $90.50; 19-21% Mn, 1-3% Si, $88; 16-19% Mn, $86.

Standard Ferromanganese: (Mn 74-76%, C 7% approx.) Base price per net ton $190, Clairton, Duquesne, Johnstown and Sheridan, Pa.; Alloy, W. Va.; Ashtabula, Marietta, Philo, O.; Sheffield, Ala.; Portland, Oreg., and Tacoma, Wash. Add or subtract $2.00 for each 1% or fraction thereof of contained manganese over 76% or under 74%, respectively.

(Mn 79-81%). Lump $198 per net ton, f.o.b. Anaconda or Great Falls, Mont. Add $2.60 for each 1% above 81%; subtract $2.60 for each 1% below 76%, fractions in proportion to nearest 0.1%.

Low-Carbon Ferromanganese, Regular Grade: (Mn 85-90%). Carload, lump, bulk, max, 0.07% C, 29.95c per lb of contained Mn, carload packed 30.7c, ton lots 31.8c, less ton 33c. Delivered. Deduct 1.5c for max 0.15% C grade from above prices, 3c for max 0.30% C, 3.5c for max 0.50% C, and 6.5c for max 75% C—max 7% Si. **Special Grade:** (Mn 90% min, C 0.07% max, P 0.06% max). Add 2.05c to the above prices. Spot, add 0.25c.

Medium-Carbon Ferromanganese: (Mn 80-85%, C 1.25-1.5%, Si 1.5% max). Carload, lump, bulk 21.85c per lb of contained Mn, packed, carload 22.9c, ton lot 24.5c, less ton 25.7c. Delivered. Spot, add 0.25c.

Manganese Metal: 2" x D (Mn 95.5% min, Fe 2% max, Si 1% max, C 0.2% max): Carload, lump, bulk, 45c per lb of metal; packed, 45.75c; ton lot 47.25c; less ton lots 49.25c. Delivered. Spot, add 2c.

Electrolytic Manganese Metal: Min carloads, 30c; 2000 lb to min carloads, 32c; 250 lb to 1999 lb 34c. Premium for hydrogen-removed metal, 0.75c per lb. Prices are f.o.b. cars, Knoxville, Tenn., freight allowed to St. Louis or to any point east of Mississippi; or f.o.b. Marietta, O., freight allowed.

Silicomanganese: (Mn 65-68%). Contract, lump, bulk 1.50% C grade, 18-20% Si, 11.2c per lb of alloy. Packed, c.l. 12.2c, ton 12.65c, less ton 13.65c, f.o.b. Alloy, W. Va., Ashtabula, O., Marietta, O., Sheffield, Ala., Portland, Oreg. For 2% C grade, Si 15-17%, deduct 0.2c from above prices. For 3% C grade, Si 12-14.5%, deduct 0.4c from above prices. Spot, add 0.25c.

TITANIUM ALLOYS

Ferrotitanium, Low-Carbon: (Ti 20-25%, Al 3.5% max, Si 4% max, C 0.10% max). Contract, ton lots 2" x D, $1.50 per lb of contained Ti; less ton $1.55. (Ti 38-43%, Al 8% max, Si 4% max, C 0.10% max). Ton lots $1.35, less ton $1.37 f.o.b. Niagara Falls, N.Y., freight allowed to St. Louis. Spot, add 5c.

Ferrotitanium, High-Carbon: (Ti 15-18%, C 6-8%). Contract $177 per ton, f.o.b. Niagara Falls, N. Y., freight allowed to destinations east of Mississippi river and north of Baltimore and St. Louis.

Ferrotitanium, Medium-Carbon: (Ti 17-21%, C 2-4.5%). Contract $195 per ton, f.o.b. Niagara Falls, N. Y., freight not exceeding St. Louis rate allowed.

CHROMIUM ALLOYS

High-Carbon Ferrochrome: Contract, c.l., lump, bulk 26.25c per lb of contained Cr; c.l. packed 27.5c, ton lot 29.25c, less ton 30.65c. Delivered. Spot, add 0.25c.

Low-Carbon Ferrochrome: (Cr 67-71%). Contract, carload, lump, bulk, C 0.025% max (Simplex) 31.75c per lb contained Cr, 0.02 max 38.50c, 0.03 max 38c, 0.06 max 36.50c, 0.1 max 36c, 0.15 max 35.75c, 0.2 max 35.50c, 0.5 max 35.25c, 1.0 max 34c, 1.5 max 33.85c, 2.0 max 33.75c. Ton lot, add 3.1c, less ton add 4.8c. Carload packed add 1.45c. Delivered. Spot, add 0.25c.

Foundry Ferrochrome, High-Carbon: (Cr 62-66%, C 5-7%, Si 7-10%). Contract, c.l. 8 M x D, bulk 27.4c per lb contained Cr. Packed c.l. 28.7c, ton 30.5c, less ton 32c. Delivered. Spot, add 0.25c.

Foundry Ferrochrome, Low-Carbon: (Cr 50-54%, Si 28-32%, C 1.25% max). Contract, carloads, packed 8 M x D, 19.6c per lb of alloy, ton lot 20.85c; less ton lot, 22.05c. Delivered. Spot, add 0.25c.

Low-Carbon Ferrochrome-Silicon: (Cr 34-41%, Si 42-49%, C 0.05% max). Contract, carload, lump, 4" x down and 2" x down, bulk, 39.05c per lb of contained Cr; 1" x down, bulk 39.8c. Delivered.

Chromium Metal, Electrolytic: Commercial grade (Cr 99.2% min, Fe 0.2 max). Contract, carlot, packed 2" x D plate (about ⅛" thick) $1.25 per lb, ton lots $1.27, less ton lots $1.28. Delivered. Spot, add 5c.

VANADIUM ALLOYS

Ferrovanadium: Open-hearth Grade (V 50-55%, Si 8% max, C 3% max). Contract, any quantity, $3.10 per lb of contained V. Delivered. Spot, add 10c. **Special Grade** (V 50-55% or 70-75%, Si 2% max, C 0.5% max) $3.20. **High Speed Grade** (V 50-55%, or 70-75%, Si 1.50% max, C 0.20% max) $3.30.

Grainal: Vanadium Grainal No. 1, $1.05 per lb; No. 6, 68c; No. 79, 50c, freight allowed.

Vanadium Oxide: Contract, less carload lots, packed, $1.33 per lb contained V_2O_5, freight allowed. Spot, add 5c.

SILICON ALLOYS

25-30% Ferrosilicon: Contract, carload, lump, bulk, 20.0c per lb of contained Si, Packed 21.40c; ton lot 22.50c f.o.b. Niagara Falls, freight not exceeding St. Louis rate allowed.

50% Ferrosilicon: Contact, carload, lump, bulk, 11.75c per lb of contained Si. Packed, c.l. 13.85c, ton lot 15.3c, less ton 16.95c. F.o.b. Alloy, W. Va., Ashtabula, O., Marietta, O., Sheffield, Ala., and Portland, Oreg. Spot, add 0.45c.

Low-Aluminum 50% Ferrosilicon: (Al 0.40% max). Add 1.2c to 50% ferrosilicon prices.

65% Ferrosilicon: Contract, carload, lump, bulk, 14.5c per pound contained silicon. Packed, c.l. 16.2c, ton lots, 18c; less ton, 19.35c. Delivered. Spot, add 0.35c.

75% Ferrosilicon: Contract, carload, lump, bulk, 15.4c per lb of contained Si. Packed c.l. 17.05c, ton lot 18.7c, less ton 19.95c. Delivered. Spot, add, add 0.3c.

90% Ferrosilicon: Contract, carload, lump, bulk, 18.5c per lb of contained Si. Packed, c.l. 19.95c, ton lot 21.35c, less ton 22.4c. Delivered. Spot, add 0.25c.

Silicon Metal: (Min 98% Si, 0.75% max Fe, 0.07 max Ca). C.l. lump, bulk, 20.5c per lb of Si. Packed, c.l. 21.95c, ton lot 23.25c, less ton 24.25c. Add 0.5c for max 0.03 Ca grade. Deduct 0.5c for max 2% Fe grade analyzing min 96.5% Si. Spot, add 0.25c.

Alsifer: (Approx, 20% Al, 40% Si, 40% Fe). Contract, basis f.o.b. Niagara Falls, N. Y., lump, carload, bulk, 10.65c per lb of alloy, ton lots packed 11.8c.

ZIRCONIUM ALLOYS

12-15% Zirconium Alloy: (Zr 12-15%, Si 39-43%, C 0.20% max). Contract, c.l. lump, bulk 8.5c, per lb of alloy. Packed, c.l. 9.5c, ton lot 10.65c, less ton 11.5c. Delivered. Spot add 0.25c.

35-40% Zirconium Alloy: (Zr 35-40%, Si 47-52%, Fe 8-12%, C 0.50% max). Contract, carload, lump, packed 26.25c per lb of alloy, ton lot 27.4c, less ton 28.65c. Freight allowed. Spot, add 0.25c.

BORON ALLOYS

Ferroboron: (B 17.50% min, Si 1.50% max, Al 0.50% max, C 0.50% max). Contract, 100 lb or more 1" x D, $1.20 per lb of alloy; less than 100 lb $1.30. Delivered. Spot add 5c. F.o.b. Washington, Pa., prices, 100 lb and over, are as follows: Grade A (10-14% B) 85c per pound; Grade B (14-18% B) $1.20; Grade C (19% min B) $1.50.

Borosil: (3 to 4% B, 40 to 45% Si). $5.25 per lb contained B, delivered to destination.

Bortam: (B 1.5%-1.9%). Ton lots, 45c per lb; smaller lots, 50c per lb.

Carbortam: (B 1 to 2%). Contract, lump, carloads 9.50c per lb, f.o.b. Suspension Bridge, N. Y., freight allowed same as high-carbon ferrotitanium.

CALCIUM ALLOYS

Calcium-Manganese-Silicon: (Ca 16-20%, Mn 14-18% and Si 53-59%). Contract, carload, lump, bulk 22c per lb of alloy, carload packed 23.05c, ton lot 24.95c, less ton 25.95c. Delivered. Spot, add 0.25c.

Calcium-Silicon: (Ca 30-33%, Si 60-65%, Fe 1.5-3%). Contract, carload, lump, bulk 21.5c per lb of alloy, carload packed 22.95c, ton lot 25.25c, less ton 26.75c. Delivered. Spot, add 0.25c.

BRIQUETTED ALLOYS

Chromium Briquets: (Weighing approx. 3⅜ lb each and containing exactly 2 lb of Cr). Contract, carload, bulk, 16.95c per lb of briquet, carload packed in box pallets 17.15c, in bags 17.85c; 3000 lb to c.l. in box pallets 18.35c; 2000 lb to c.l. in bags, 19.05c; less than 2000 lb in bags 19.95c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Ferromanganese Briquets: (Weighing approx. 3 lb and containing exactly 2 lb of Mn). Contract, carload, bulk 12.1c per lb of briquet, c.l. packed, pallets 12.3c, bags 13.1c; 3000 lb to c.l., pallets 13.5c; 2000 lb to c.l., bags, 14.3c, less ton 15.2c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Silicomanganese Briquets: (Weighing approx. 3½ lb and containing exactly 2 lb of Mn and approx. ½ lb of Si). Contract, c.l. bulk 12.7c per lb of briquet, c.l. packed, pallets, 12.9c; bags 13.7c, 3000 lb to c.l., pallets, 14.1c; 2000 lb to c.l., bags, 14.9c; less ton 15.8c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Silicon Briquets: (Large size—weighing approx. 5 lb and containing exactly 2 lb of Si). Contract, carload, bulk 6.75c per lb of briquet; packed, pallets, 6.95c; bags, 7.75c; 3000 lb to c.l., pallets, 8.55c; 2000 lb to c.l. bags 9.35c; less ton 10.25c. Delivered. Spot, add 0.25c.

(Small size—Weighing approx. 2½ lb and containing exactly 1 lb of Si). Carload, bulk 6.9c. Packed, pallets 7.1c; bags 7.9c; 3000 lb to c.l. pallets 8.7c; 2000 to c.l. bags 9.5c; less ton 10.4c. Delivered. Add 0.25c for notching, small size only. Spot, add 0.25c.

Molybdic-Oxide Briquets: (Containing 2½ lb of Mo each) $1.14 per pound of Mo contained, f.o.b. Langeloth, Pa.

TUNGSTEN ALLOYS

Ferrotungsten: (70-80%), 5000 lb W or more $3.45 per lb of contained W; 2000 lb W to 5000 lb W. $3.55; less than 2000 lb W, $3.67. Delivered.

OTHER FERROALLOYS

Ferrocolumbium: (Cb 50-60%, Si 8% max, C 0.4% max). Contract, ton lot, 2" x D, $6.90 per lb of contained Cb. Delivered. Spot, add 10c.

Ferrotantalum—Columbium: (Cb 40% approx., Ta 20% approx., and Cb plus Ta 60% min C 0.30% max). Ton lots, 2" x D, $4.65 per lb of contained Cb plus Ta, delivered; less ton lots $4.70.

Silicaz Alloy: (Si 35-40%, Ca 9-11%, Al 6-8%, Zr 3-5%, Ti 9-11%, B 0.55-0.75%). Carloads packed 1" x D, 45c per lb of alloy, ton lot 47c, less ton 49c. Delivered.

SMZ Alloy: (Si 60-65%, Mn 5-7%, Zr 5-7%, Fe 20% approx.). Contract, c.l. packed ⅛" x 12 M, 18.5c per lb of alloy, ton lots 19.65c, less ton 20.9c. Delivered. Spot, add 0.25c.

Graphidox No. 5: (Si 48-52%, Ca 5-7%, Ti 9-11%). C.l. packed, 18.5c per lb of alloy, ton lots 19.65c; less ton lots 20.9c, f.o.b. Niagara Falls, N. Y.; freight allowed to St. Louis.

V-5 Foundry Alloy: (Cr 38-42%, Si 17-19%, Mn 8-11%). C.l. packed 17.2c per lb of alloy; ton lots 18.7c; less ton lots 19.95c, f.o.b. Niagara Falls; freight allowed to St. Louis.

Siminal: (Approx. 20% each Si, Mn, Al; bal, Fe). Lump, carload, bulk 16.50c. Packed c.l. 17.50c, 2000 lb to c.l. 18.50c, less than 2000 lb 19c per lb of alloy. Delivered.

Ferrophosphorus: (23-25% based on 24% P content with unitage of $4 for each 1% of P above or below the base); carloads, f.o.b. sellers' works, Mt. Pleasant, Siglo, Tenn., $90 per gross ton.

Ferromolybdenum: (55-75%). Per lb contained Mo, in 200-lb containers, f.o.b. Langeloth, Pa., $1.46 in all sizes except powdered which is $1.57; Washington, Pa., furnace, any quantity $1.46.

Technical Molybdic-Oxide: Per lb contained Mo, f.o.b. Langeloth, Pa., $1.25 in cans; in bags, $1.24, f.o.b. Langeloth, Pa.; $1.24, Washington, Pa.

ELECTRIC FURNACE

STEEL CASTINGS

ARE FOUNDRY ENGINEERED

Regardless of the type of product you make — if you are interested in strength, toughness, uniform structure, resistance to fatigue, long life, lower machining and lower assembly costs — you'll be interested in C Steel Castings. The point is that they are sound, clean, true to pattern castings that by alloy and heat treating possess an almost unlimited range of mechanical properties.

Why Not Investigate?

Perhaps by cooperating with your engineers in details of design and pattern construction we may be able to save you both machining and assembling costs.

CRUCIBLE STEEL CASTING CO.
LANSDOWNE, PENNA.

POOLE



A COPY OF CATALOG GIVING FULL DESCRIPTION AND ENGINEERING DATA SENT UPON REQUEST.

FLEXIBLE COUPLINGS

POOLE FOUNDRY & MACHINE COMPANY WOODBERRY, BALTIMORE, MD.

STEEL-BRASS and ALUMINUM STAMPINGS

Looking for a dependable source of supply to keep an un-interrupted flow of parts coming in on scheduled time? Our reputation is behind every promise date. Send blueprints or samples for quotation.

WORCESTER STAMPED METAL CO.
Established 1883
10 HUNT STREET • WORCESTER, MASS.

H&G Insert Chaser DIE HEADS



famous for accuracy and straightness of threads, low chaser costs, less downtime, more pieces per day.

THE EASTERN MACHINE SCREW CORP., 22-42 Barclay Street, New Haven, Conn.
Pacific Coast Representative: *A. C. Berbringer, Inc., 334 N. San Pedro St., Los. Angeles, California.* Canada: *F. F. Barber Machinery Co., Toronto, Canada.*

To Lower your Overhead..

BROWNING ELECTRIC TRAVELING CRANES AND HOISTS
up to 125-TON CAPACITY

VICTOR R. BROWNING & CO., INC. WILLOUGHBY (Cleveland), OHIO

IF METALWORKING PLANTS ARE YOUR PROSPECTS . . .

STEEL can put you in touch with the important ones, those that do more than 92% of the industry's business. Tell the buyers and specifiers in these plants of the machines or materials you have for sale through an "Equipment—Materials" advertisement. For rates write STEEL, Penton Building, Cleveland 13, Ohio.

Ores

Lake Superior Iron Ore
(Prices effective for the 1955 shipping season, gross ton, 51.50% iron natural, rail of vessel, lower lake ports)

Old range bessemer	$10.40
Old range nonbessemer	10.25
Mesabi bessemer	10.25
Mesabi nonbessemer	10.10
Open-hearth lump	11.25
High phosphorus	10.00

Eastern Local Iron Ore
Cents per unit, deld. E. Pa.

Foundry and basic 52-62% concentrates contract	17.00-18.00

Foreign Iron Ore
Cents per unit, c.i.f. Atlantic ports

Swedish basic, 60-68%	20.00
N. African hematite (spot)	nom. 18.00-20.00
Brazilian iron ore, 68-69% (spot)	24.00-26.00

Tungsten Ore
Net ton unit, before duty

Foreign, wolframite, good commercial quality	$34.50-$35.00
Domestic, scheelite, mine	63.00

Manganese Ore
Mn 48%, nearby, 95c-$1.05 per long ton unit, c.i.f. U. S. ports, duty for buyer's account; 46-47%, 75c-80c.

Chrome Ore
Gross ton, f.o.b. cars New York, Philadelphia, Baltimore, Charleston, S. C., plus ocean freight differential for delivery to Portland, Oreg., Tacoma, Wash.

Indian and African

48% 2.8:1	nom. $45.00-$50.00
48% 3:1	42.00-44.00
48% no ratio	34.00

South African Transvaal

44% no ratio	$19.00-$20.00
48% no ratio	32.00

Domestic
Rail nearest seller

18% 3:1	$39.00

Molybdenum

Sulphide concentrate, per lb of Mo content, mines, unpacked	$1.00

Antimony Ore
Per unit of Sb content, c.i.f. seaboard

55-60%	$3.60-$3.85
60-65%	3.85-4.00

Vanadium Ore
Cents per lb V_2O_5 content, deld. mills

Domestic	31.00

Refractories

Fire Clay Brick (per 1000)
High-Heat Duty: Ashland, Grahn, Hayward, Hitchins, Haldeman, Olive Hill, Ky., Athens, Troup, Tex., Beech Creek, Clearfield, Curwensville, Lock Haven, Lumber, Orviston, West Decatur, Pa., Bessemer, Ala., Farber, Mexico, St. Louis, Vandalia, Mo., Ironton, Oak Hill, Parral, Portsmouth, O., Ottawa, Ill., Stevens Pottery, Ga., $122; Salina, Pa., $127; Niles, O., $133.
Super-Duty: St. Louis, $150.

Silica Brick (per 1000)
Standard: Alexandria, Claysburg, Mt. Union, Sproul, Pa., Ensley, Ala., Portsmouth, O., Hawston, Pa., $128; Warren, Niles, O., Hays, Pa., $133; Morrisville, Pa., $131.50; E. Chicago, Ind., Joliet, Rockdale, Ill., $138; Lehigh, Utah, $144; Los Angeles, $151.
Super Duty: Hays, Sproul, Hawston, Pa., Warren, Windham, O., Athens, Tex., $145; Morrisville, Pa., Niles, O., $148; Joliet, Ill., $151; Curtner, Calif., $163.

Semisilica Brick (per 1000)
Clearfield, Pa., $139; Philadelphia, $124; Woodbridge, N. J., $122.

Insulating Fire Brick (per 1000)
2300° *F:* Massillon, O., $178.50; Clearfield, Pa., $213; Augusta, Ga., Beaver Falls, Zelienople, Pa., Mexico, Mo., $206; Vandalia, Mo., $214.10; Portsmouth, O., $207.50; Bessemer, Ala., $212.80.

Ladle Brick (per 1000)
Dry Pressed: Alsey, Ill., Chester, New Cumberland, W. Va., Freeport, Johnstown, Merrill Station, Pa., Mexico, Mo., $88.50; Wellsville, O., $92.50; Clearfield, Pa., Portsmouth, O., $98.

High-Alumina Brick (per 1000)
50 *Per Cent:* Clearfield, Pa., St. Louis, Mexico, Mo., $194; Danville, Ill., $197; Philadelphia, $201.
60 *Per Cent:* St. Louis, Mexico, Vandalia, Mo., Clearfield, Pa., $241; Danville, Ill., $244; Philadelphia, $248.
70 *Per Cent:* St. Louis, Mexico, Vandalia, Mo., $279; Danville, Ill., $281; Clearfield, Pa., Philadelphia, $286.

Sleeves (per 1000)
Reesdale, Johnstown, Bridgeburg, Pa., $157; Clearfield, Pa., $158.50; St. Louis, $169.30.

Nozzles (per 1000)
Reesdale, Pa., $253.70; Johnstown, Pa., $259.20; Clearfield, Pa., $259.40; St. Louis, $259.45; Bridgeburg, Pa., $286.

Runners (per 1000)
Reesdale, Johnstown, Bridgeburg, Pa., $196; Clearfield, Pa., $198; St. Louis, $195.80.

Dolomite (per net ton)
Domestic, dead-burned, bulk, Billmeyer, Blue Bell, Williams, Plymouth Meeting, York, Pa., Millville, W. Va., Bettsville, Millersville, Martin, Woodville, O., Gibsonburg, Narlo, O., $15; Thornton, McCook, Ill., $15.60; Dolly Siding, Bonne Terre, Mo., $14.

Magnesite (per net ton)
Domestic, dead-burned, bulk, ⅛-in. grains with fines: Chewelah, Wash., $40; Luning, Nev., $40. ⅜-in. grains with fines: Baltimore, $66.40.

Metallurgical Coke

Price per net ton
Beehive Ovens

Connellsville, furnace	$13.25-$14.00
Connellsville, foundry	16.00-17.00

Oven Foundry Coke

Kearny, N. J., ovens	$25.50
Camden, N. J., ovens	25.00
Everett, Mass., ovens	
New England, deld.	*27.05
Chicago, ovens	25.75
Chicago, deld.	27.25
Terre Haute, Ind., ovens	25.50
Milwaukee, ovens	26.25
Indianapolis, ovens	25.50
Portsmouth, O., ovens	24.75
Cincinnati, deld.	27.34
Painesville, O., ovens	26.25
Cleveland, deld.	28.18
Birmingham, ovens	24.40
Cincinnati, deld.	29.33
Buffalo, ovens	25.75
Buffalo, deld.	27.00
Lone Star, Tex., ovens	19.50
Neville Island, Pa., ovens	25 00
Philadelphia, ovens	25 00
Swedeland, Pa., ovens	25 00
St. Paul, ovens	25.00
Detroit, ovens	26.25
Detroit, deld.	27.25
Pontiac, deld.	27.81
Saginaw, deld.	29.33

*Or within $4.55 freight zone from works.

Coal Chemicals

Spot, cents per gallon, ovens

Pure benzene	36.00
Toluene, one deg.	32.00-34.00
Industrial xylene	32.00-35.00
Per ton, bulk, ovens	
Ammonium sulphate	$42-$45
Birmingham area	42.00†

†With port equalization against imports.

Cents per pound, producing point
Phenol: Grade 1, 14.00; Grade 2-3, 13.50; Grade 4, 15.50; Grade 5, 14.25.

Fluorspar

Metallurgical grades, f.o.b. shipping point, in Ill., Ky., net tons, carloads, effective CaF_2 content 72.5%, $38-$39; 70%, $35-$36; 60%, $31-$32. Imported, net tons, f.o.b. cars point of entry, duty paid, metallurgical grade: European, $34; Mexican, $25.50.

Electrodes

Threaded with nipple, unboxed, f.o.b. plant

Inches Diam	Length	Per 100 lb
GRAPHITE		
2	24	$52.50
2½	30	33.75
3	40	32.00
4	40	30.25
5½	40	30.00
6	60	27.25
7	60	26.75
8, 9, 10	60	24.25
12	72	27.25
14	60	23.50
16	72	22.50
17	60	23.00
18	72	22.50
20	72	22.25
CARBON		
8	60	12.10
10	60	11.80
12	60	11.75
14	60	11.70
14	72	10.85
17	60	10.75
17	72	10.35
20	84	10.30
20	90	10.10
24	72, 84	10.30
24	96	10 05
30	84	10 20
40, 35	110	9.90
40	100	9.90



Your machining department for hardened and precision ground screw machine products. Send for brochure & equipment list.
Ottawa
STEEL PRODUCTS INC.
Grand Haven Michigan
OTTAWA STEEL PRODUCTS
OSP
INC.



Leaders in Iron & Steel Scrap Since 1889

For over half a century our experience, personnel, equipment and key office locations have contributed to the steady growth of the iron and steel industry. Possibly our facilities may help you solve a problem in iron or steel scrap—no matter how big or small.

Lusia Brothers and Company, Inc.

main office **PHILADELPHIA NATIONAL BANK BUILDING,** *Phila. 7, Pa.*

PLANTS

LEBANON, PENNA. — READING, PENNA. — MODENA, PENNA. — DETROIT (ECORSE), MICHIGAN — PITTSBURGH, PENNA. — ERIE, PENNA.

OFFICES

BIRMINGHAM, ALA. — BOSTON, MASS. — BUFFALO, N. Y. — CHICAGO, ILLINOIS — CLEVELAND, OHIO — DETROIT, MICHIGAN — HOUSTON, TEXAS — LEBANON, PENNA. — LOS ANGELES, CAL. — NEW YORK, N. Y. — PITTSBURGH, PENNA. — PUEBLO, COLORADO — MONTREAL, CANADA — READING, PENNA. — ST. LOUIS, MISSOURI — SAN FRANCISCO, CAL. — SEATTLE, WASH.

IMPORT & EXPORT — **LIVINGSTON & SOUTHARD, INC.,** 99 Park Ave., New York, N. Y. • *Cable Address:* **FORENTRACO**

Scrap . . .

Scrap Prices, Page 208

Chicago—The scrap market in this district continues to lag in volume, but there has been clarification in prices. A larger consumer, which normally states its future buying policy at month end, placed orders for No. 1 industrial bundles at $47, No. 1 industrial heavy melting steel at $46 and No. 2 bundles at $34. The effect of this was to firm up No. 1 heavy melting by $1 a ton to a level which prevailed up to two weeks ago and to reaffirm current prices on the bundle grades.

Buffalo — Prices on steelmaking grades of scrap jumped $1 a ton for No. 2 material and $4 a ton for No. 1 quality on sales to one of the area's leading mills. Business also was reported in blast furnace grades at advances of $1 a ton.

Cleveland—Prices on steelmaking grades of scrap are unchanged here despite the absence of substantial sales in the area. The market is being supported by activity in the Valley. Reported sales there last week: No. 1 heavy melting at $48.50 and electric furnace scrap at $49. The foundry grades of scrap are firm. A recent purchase by a leading automotive foundry of low phos material boosted the price on that grade to a range of $50-$51.

Pittsburgh—Small amounts of No. 1 heavy melting scrap were sold to a local producer at prevailing prices last week. It was practically the only action in major scrap grades. Scrap is moving slowly here in contrast to neighboring areas, brokers say, but the market is considered strong. Rail prices moved up about $3 a ton on latest lists. Stainless steel scrap grades are also showing greater strength.

Cincinnati — Some new buying by district mills is expected shortly. The tone of the market is firm. The only price changes last week resulted in advances on cast iron borings and mixed borings and turnings to a range of $24.75-$25.75.

Boston—The spread in brokers' buying prices for No. 1 heavy melting steel is $39 shipping point for district mill consumers and $27.50 for eastern Pennsylvania. Shipments against orders for eastern Pennsylvania are substantial, the bulk of bundles in both grades going to that area. Cast grades are up an average of $1 on slightly heavier movement.

New York—Except for an advance of $1 on No. 1 cupola to $37-$38, brokers' buying prices are unchanged. Buying prices in most cases appear high enough to bring out a steady flow of tonnage.

Philadelphia—While there is an underlying note of strength in the steel scrap market, prices are sufficiently high in most cases to bring out a steady flow of tonnage. No. 2 heavy melting is a shade higher at $41, delivered, and couplers, springs and wheels have advanced to a flat $52, delivered. Otherwise, the steel grades are unchanged.

Detroit—Prices on blast furnace grades of scrap appear to be weak, with machine shop turnings quoted at $22; mixed borings and turnings, $22; and short shovel turnings, $24. Demand for electric furnace and foundry scrap is strong—prices are up about $2 on the latest automotive lists.

Los Angeles—Increasing exports of scrap to Japan from West Coast ports are causing a shortage in the No. 1 grades. Japan has been taking heavy tonnage for several weeks.

Birmingham—The scrap market continues strong with specialty items advancing. Blast furnace, open-hearth and cast grades are steady.

San Francisco—No. 1 cupola cast price has been advanced $2 to $3 a ton.

Seattle—Competition for scrap has forced some relaxation in specifications. Almost any quality material is salable. Buyers are accepting scrap they rejected a few months ago. Mill inventories are only fair; export demand is reported increasing.

Japan is said to be paying above $60 a ton.

Pig Iron . . .

Pig Iron Prices, Page 195

Merchant pig iron business is holding up well, with bookings this fall the heaviest for the year. Seasonal factors probably will have a depressing effect on the market over the remainder of the year.

(*Please turn to page* 210)

"NONE BETTER"
FOR PERFECT SOLDERING IN LESS TIME
Use Rubyfluid soldering flux. Fast acting . . . easy to use . . . wets out freely . . . insures strong unions. Ask your jobber or write for special $1.00 offer.
RUBY CHEMICAL CO.
75 S. McDowell St.
Columbus 8, Ohio
Rubyfluid

Wide or Narrow...
1 C-F LIFTER HANDLES THEM ALL
Whether your production requires a few or many widths of sheet steel, 1 C-F Lifter, with its wide range of jaw and carrying angle adjustments will probably meet all your sheet handling requirements.
Adjustments are made by the operator in a few seconds, permitting the Lifter to shift from wide to narrow sizes almost instantly.
Because it can pick up, carry and unload more loads per hour, using less man and crane time than any other method, a C-F Lifter will soon pay for itself.
Bulletin SL-25 gives you the complete story of C-F Lifter advantages to you. Ask for it today. There's no obligation.
CULLEN-FRIESTEDT CO.
1308 South Kilbourn Avenue • Chicago 23, Illinois

Iron and Steel Scrap

Consumer prices, per gross ton, except as otherwise noted, including broker's commission, as reported to STEEL. *Changes shown in italics.*

STEELMAKING SCRAP COMPOSITE

Nov. 2	$45.17
Oct. 26	45.00
Oct. Avg.	45.17
Nov. 1954	33.33
Nov. 1950	41.33

Based on No. 1 heavy melting grade at Pittsburgh, Chicago and eastern Pennsylvania.

PITTSBURGH

(Delivered consumer's plant)

No. 1 heavy melting..	44.00-45.00
No. 2 heavy melting..	40.00-41.00
No. 1 bundles	44.00-45.00
No. 2 bundles	37.00-38.00
No. 1 busheling	44.00-45.00
Machine shop turnings..	*29.00-30.00*
Mixed borings, turnings.	*29.00-30.00*
Short shovel turnings..	33.00-34.00
Cast iron borings	33.00-34.00
Cut structurals, 3 ft lengths	49.00-50.00
Heavy turnings	42.00-43.00
Punchings & plate scrap	49.00-50.00
Electric furnace bundles	48.00-49.00

Cast Iron Grades

No. 1 cupola	42.00-43.00
Charging box cast	39.00-40.00
Heavy breakable cast..	39.00-40.00
Unstripped motor blocks	29.00-30.00
No. 1 machinery cast..	48.00-49.00

Railroad Scrap

No. 1 R.R. heavy melt.	49.00-50.00
Rails, 2 ft and under	*58.00-59.00*
Rails, 18 in. and under.	*59.00-60.00*
Rails, random lengths...	*55.00-56.00*
Railroad specialties	54.00-55.00

Stainless Steel Scrap

18-8 bundles & solids	270.00-285.00
18-8 turnings	130.00-140.00
430 bundles & solids	100.00-110.00
430 turnings	60.00-65.00

CLEVELAND

(Delivered consumer's plant)

No. 1 heavy melting..	45.00-46.00
No. 2 heavy melting..	40.00-41.00
No. 1 bundles	45.00-46.00
No. 2 bundles	35.00-36.00
No. 1 busheling	45.00-46.00
Machine shop turnings	23.00-24.00
Mixed borings, turnings	27.50-28.50
Short shovel turnings..	27.50-28.50
Cast iron borings	27.50-28.50
Low phos.	45.00-46.00
Cut structural plates 2 ft and under	*50.00-51.00*
Alloy free, short shovel turings	31.00-32.00
Electric furnace bundles.	*45.50-46.50*

Cast Iron Grades

No. 1 cupola	47.00-48.00
Charging box cast	40.00-41.00
Stove plate	46.00-47.00
Heavy breakable cast..	37.00-38.00
Unstripped motor blocks	29.00-30.00
Brake shoes	35.00-36.00
Clean auto cast	48.00-49.00
Burnt cast	37.00-38.00
Drop broken machinery	49.00-50.00

Railroad Scrap

No. 1 R.R. heavy melt.	45.00-46.00
R.R. malleable	53.00-54.00
Rails, 2 ft and under..	62.00-63.00
Rails, 18 in. and under	63.00-64.00
Rails, random lengths..	58.00-59.00
Cast steel	48.00-49.00
Railroad specialties	54.00-55.00
Uncut tires	49.00-50.00
Angles, splice bars	54.50-55.50
Rails, rerolling	63.00-64.00

Stainless Steel

(Brokers' buying prices; f.o.b. shipping point)

18-8 bundles, solids..	290.00-300.00
18-8 turnings	130.00-140.00
430 clips, bundles, solids	90.00-100.00
430 turnings	40.00-50.00

YOUNGSTOWN

(Delivered consumer's plant)

No. 1 heavy melting...	47.50-48.50
No. 2 heavy melting...	35.00-36.00
No. 1 bundles	47.50-48.50
No. 2 bundles	32.00-33.00
No. 1 busheling	47.50-48.50
Machine shop turnings.	24.00-25.00
Short shovel turnings..	29.00-30.00
Cast iron borings	29.00-30.00
Low phos.	47.50-48.50
Electric furnace bundles	47.50-48.50

Railroad Scrap

No. 1 R.R. heavy melt.	48.00-49.00

CHICAGO

No. 1 heavy melting...	*43.00-46.00*
No. 2 heavy melting..	34.00-35.00
No. 1 factory bundles.	46.00-47.00
No. 1 dealer bundles..	43.00-44.00
No. 2 bundles	33.00-34.00
No. 1 busheling	*43.00-46.00*
Machine shop turnings	27.00-28.00
Mixed borings, turnings	29.00-30.00
Short shovel turnings..	29.00-30.00
Cast iron borings	29.00-30.00
Cut structurals, 3 ft	*47.00-48.00*
Punchings & plate scrap	*48.00-49.00*

Cast Iron Grades

No. 1 cupola	47.00-48.00
Stove plate	37.00-38.00
Unstripped motor blocks	34.00-35.00
Clean auto cast	*50.00-51.00*
Drop broken machinery..	*50.00-51.00*

Railroad Scrap

No. 1 R.R. heavy melt.	47.00-48.00
R.R. malleable	56.00-57.00
Rails, 2 ft and under.	60.00-61.00
Rails, 18 in. and under	61.00-62.00
Angles, splice bars	57.00-58.00
Rails, rerolling	65.00-66.00

Stainless Steel Scrap

18-8 bundles & solids	*305.00-315.00*
18-8 turnings	*205.00-215.00*
430 bundles & solids	100.00-105.00
430 turnings	45.00-50.00

DETROIT

(Brokers' buying prices; f.o.b. shipping point)

No. 1 heavy melting..	40.00
No. 2 heavy melting..	30.00
No. 1 bundles	40.00
No. 2 bundles	29.00
No. 1 busheling	40.00
Machine shop turnings..	*22.00*
Mixed borings, turnings.	*22.00*
Short shovel turnings...	*24.00*
Punchings & plate scrap.	*48.00*

Cast Iron Grades

No. 1 cupola	40.00
Charging box cast	33.00
Stove plate	32.00
Heavy breakable	32.00
Unstripped motor blocks	22.00
Clean auto cast	44.00
Malleable	35.00

BIRMINGHAM

No. 1 heavy melting..	38.00-39.00
No. 2 heavy melting...	35.00-36.00
No. 1 bundles	38.00-39.00
No. 2 bundles	28.00-29.00
No. 1 busheling	38.00-39.00
Cast iron borings	17.00-18.00
Short shovel turnings	*28.00-29.00*
Machine shop turnings..	*27.00-28.00*
Electric furnace bundles.	*43.00-44.00*

Cast Iron Grades (F.o.b. shipping point)

No. 1 cupola	47.50-48.00
Stove plate	44.50-45.50
Bar crops and plate....	*47.00-48.00*
Structural plate, 2 ft...	*46.00-47.00*
Unstripped motor blocks	36.00-37.00
Charging box cast	30.00-31.00
No. 1 wheels	38.00-39.00

Railroad Scrap

No. 1 R.R. heavy melt.	43.00-44.00
Rails, 18-in. and under.	*58.50-59.50*
Rails, rerolling	*58.00-59.00*
Rails, random lengths...	*53.00-54.00*
Angles, splice bars	*55.00-56.00*

PHILADELPHIA

(Delivered consumer's plant)

No. 1 heavy melting...	46.00-47.00
No. 2 heavy melting...	*41.00*
No. 1 bundles	46.00-47.00
No. 2 bundles	37.00-38.00
No. 1 busheling	46.00-47.00
Electric furnace bundles	48.50
Machine shop turnings.	28.50-29.50
Mixed borings, turnings	28.50-29.50
Short shovel turnings..	30.50-31.50
Structurals & plate	49.00-50.00
Heavy turnings	43.00
Couplers, springs, wheels	*52.00*
Rail crops, 2 ft & under	59.00-60.00

Cast Iron Grades

No. 1 cupola	42.00-43.00
Malleable	*46.00-46.50*
Heavy breakable cast..	45.00-46.00
Drop broken machinery	47.00-48.00

NEW YORK

(Brokers' buying prices)

No. 1 heavy melting..	41.00-42.00
No. 2 heavy melting..	37.00-38.00
No. 1 bundles	41.00-42.00
No. 2 bundles	32.00-33.00
Machine shop turnings.	20.00-21.00
Mixed borings, turnings	21.00-22.00
Short shovel turnings.	22.00-23.00
Low phos. (structural & plate)	42.00-43.00

Cast Iron Grades

No. 1 cupola	*37.00-38.00*
Unstripped motor blocks	25.00-26.00
Heavy breakable	38.00-39.00

Stainless Steel

18-8 sheets, clips, solids	290.00-300.00
18-8 borings, turnings..	150.00-160.00
430 sheets, clips, solids	120.00-125.00
410 sheets, clips, solids	100.00-105.00

BOSTON

(Brokers' buying prices; f.o.b. shipping point)

No. 1 heavy melting....	*37.50-39.00*
No. 2 heavy melting....	*30.00-30.50*
No. 1 bundles	*37.50-38.00*
No. 2 bundles	*28.00-28.50*
Machine shop turnings	20.00-20.50
Mixed borings, turnings	22.50-23.00
Short shovel turnings..	23.50-24.00
No. 1 cast	*31.00-32.00*
Mixed cupola cast	*29.00-30.00*
No. 1 machinery cast..	*36.00-37.00*

BUFFALO

No. 1 heavy melting....	*43.00-44.00*
No. 2 heavy melting....	*37.00-38.00*
No. 1 bundles	*43.00-44.00*
No. 2 bundles	32.00-33.00
No. 1 busheling	*43.00-44.00*
Mixed borings, turnings.	*29.00-30.00*
Machine shop turnings..	*27.00-28.00*
Short shovel turnings...	*30.00-31.00*
Cast iron borings	*30.00-31.00*
Low phos.	*47.00-48.00*

Cast Iron Grades (F.o.b. shipping point)

No. 1 cupola	40.00-41.00
No. 1 machinery	43.00-44.00

Railroad Scrap

Rails, random lengths.	47.00-48.00
Rails, 2 ft and under.	51.00-52.00
Railroad specialties....	48.00-49.00

CINCINNATI

Brokers' buying prices; f.o.b. shipping point)

No. 1 heavy melting...	41.50-42.50
No. 2 heavy melting...	36.00-37.00
No. 1 bundles	41.50-42.50
No. 2 bundles	33.00-34.00
No. 1 busheling	41.50-42.50
Machine shop turnings.	27.00-28.00
Mixed borings, turnings.	*24.75-25.75*
Short shovel turnings..	30.00-31.00
Cast iron borings	*24.75-25.75*
Low phos., 18 in.	50.00-51.00

Cast Iron Grades

No. 1 cupola	45.00-46.00
Heavy breakable cast..	41.00-42.00
Charging box cast	41.00-42.00
Drop broken machinery	49.00-50.00

Railroad Scrap

No. 1 R.R. heavy melt.	44.00-45.00
Rails, 18 in. and under	60.00-61.00
Rails, random lengths.	53.00-54.00

ST. LOUIS

(Brokers' buying prices)

No. 1 heavy melting	38.50
No. 2 heavy melting	36.00
No. 1 bundles	39.50
No. 2 bundles	31.50
Machine shop turnings.	28.00
Short shovel turnings..	28.00

Cast Iron Grades

No. 1 cupola	46.50
Charging box cast	39.00
Heavy breakable cast..	37.00
Unstripped motor blocks	37.00
Brake shoes	36.00
Clean auto cast	47.00
Stove plate	38.00

Railroad Scrap

No. 1 R.R. heavy melt.	48.00
Rails, 18 in. and under	59.00
Rails, random lengths..	56.00
Rails, rerolling	64.00
Angles, splice bars	55.00

SEATTLE

(Delivered consumer's plant)

No. 1 heavy melting..	44.00
No. 2 heavy melting..	40.00
No. 1 bundles	39.50
No. 2 bundles	34.00
No. 3 bundles	19.00
Machine shop turnings.	15.00-16.00
Mixed borings, turnings	15.00-16.00
Short shovel turnings..	15.00-16.00
Electric furnace, No. 1.	50.00

Cast Iron Grades (F.o.b. shipping point)

No. 1 cupola	43.00
Heavy breakable cast..	38.00
No. 1 wheels	35.00
Unstripped motor blocks	29.00
Clean motor blocks	40.00
Stove plate (f.o.b. plant)	30.00
Brake shoes	35.00

Railroad Scrap (Delivered consumer's plant)

Rails, random lengths..	33.00

LOS ANGELES

No. 1 heavy melting..	39.00
No. 2 heavy melting..	37.00
No. 1 bundles	39.00
No. 2 bundles	35.00
Machine shop turnings	12.00

Cast Iron Grades (F.o.b. shipping point)

No. 1 cupola	43.00-45.00

SAN FRANCISCO

No. 1 heavy melting...	39.00
No. 2 heavy melting...	37.00
No. 1 bundles	39.00
No. 2 bundles	33.00
No. 1 busheling	39.00
Machine shop turnings.	18.00
Mixed borings, turnings	18.00
Short shovel turnings..	20.00
Cast iron borings	18.00
Cut structurals	41.00
Heavy turnings	20.00
Punchings & plate scrap	39.00

Cast Iron Grades

No. 1 cupola	*47.00-48.00*
Charging box cast	35.00
Stove plate	39.00
Heavy breakable cast..	36.00
Unstripped motor blocks	32.00
Brake shoes	35.00
Clean auto cast	45.00
No. 1 wheels	39.00
Burnt cast	23.00
Drop broken machinery	48.00

HAMILTON, ONT.

(Delivered prices)

No. 1 heavy melting..	38.50
No. 2 heavy melting..	35.50
No. 1 bundles	38.50
No. 2 bundles	32.50
Mixed steel scrap	32.50
Mixed borings, turnings	17.00
Rails, remelting	47.50
Busheling, new factory: Prepared	36.50
Unprepared	32.50
Short steel turnings....	21.00

Cast Iron Grades†

No. 1 machinery cast..	42.00-45.00

†F.o.b., shipping point.



LOGEMANN HYDRAULIC OPERATING VALVE

This compact valve was designed to control the movements of the hydraulic rams in large scrap presses but can be modified to suit similar operations on other hydraulic equipment. Interested parties will please outline the nature of the service, operating sequence, gallonage and pressure requirements.



Get low cost, high density bales with LOGEMANN SELF-CONTAINED TRIPLE-COMPRESSION PRESSES

The illustration shows one of two large scrap-press units in a modern automotive plant. Over a period of many years, such units have baled sheet scrap skeletons and trim from metal operations in large industrial plants throughout the country, forming the scrap into high-density bales for re-melting in steel mills. Low baling costs are the result of correct design for heavy duty service, minimum maintenance and operating interruptions, as well as simplicity, accessibility and safety features.

Pioneers in the metal baling field, LOGEMANN engineers embodied in the design those features that have proven dependable over an extended period of years. Some installations in service over 35 years are still operating economically.



LOGEMANN TYPE DA DOUBLE PRESSURE PUMPS

These compact and efficient opposed-cylinder reciprocating-plunger pumps for low and high pressure service lend themselves to a wide range of double pressure applications. They are close-coupled, reliable, and capable of delivering high gallonage, at low and high pressures, at low power costs.

Tell Us the nature of your scrap!

LOGEMANN press sizes are not confined to the large models. Producers of sheet scrap—steel, copper, brass, or aluminum—are invited to submit their scrap baling problems regardless of tonnage. Please state the character of the metal, minimum tonnage to be handled in a given period of hours, range of gauges and, where possible, indicate maximum and minimum lengths and widths of pieces. Experienced sales engineers are available for discussion of your conditions and requirements.

LOGEMANN BROTHERS CO.

3126 W. BURLEIGH STREET • MILWAUKEE 10, WISCONSIN

(*Concluded from page* 207)

Foundries are holding operations at a high level, averaging about 85 per cent of capacity. Their inventories are not large, and they encounter continued strength in the scrap market, which tends to support their buying interest in pig iron.

Inland Steel Co. ended an eight-year campaign for its Madeline "A" blast furnace at Indiana Harbor on Nov. 1 when it blew out the unit for relining. About 3.2 million tons of iron were produced since the stack was blown in Aug. 1, 1947—a new record for Inland blast furnaces. Its rated capacity is 390,650 tons of pig iron a year. Relining will take about two months.

Kaiser Steel Corp. will ship 110,000 gross tons of pig iron to Japan, starting in late November and continuing through 1956. Shipments will be made through the port of Long Beach (Calif.) from Kaiser's Fontana (Calif.) plant.

Iron Ore . . .

Iron Ore Prices, Page 205

Lake iron ore shipments totaled 2,719,011 gross tons in the week ended Oct. 31, reports the Lake Superior Iron Ore Association. This compares with 1,516,657 tons shipped in the corresponding week a year ago. Cumulative shipments to Oct. 31 in the 1955 shipping season are 79,610,132 tons. Movement to the same date in the 1954 season was only 57,736,665 tons.

WARD STEEL CO.

We specialize in
FINISHED STEEL
BARS—TUBES—STRIP

PROMPT WAREHOUSE SERVICE ONLY

Most Complete Stock in America of
BLUE TEMPERED SPRING STEEL

We believe that the way to sell is to carry a stock which permits satisfying any reasonable warehouse demand.

87A Rindge Ave. Ext. Phone UN 4-2460
CAMBRIDGE 40, MASS.

Branches:
3042-3058 W. 51st Street, CHICAGO, ILL.
Phone: Grove Hill 6-2600

Fenner Street, Providence, R. I.
Phone: Gaspee 1-5573, 1-8573

EUREKA FIRE BRICK WORKS
Works: Mt. Braddock, Fayette Co., Pa.
Dunbar, Pa. 4213
COVERED HOT TOP BRICK
INGOT MOLD PLUGS



Sales Office
132 S. Whitfield St.
PITTSBURGH 6, PA. EM: 2-0614

CHEMSTEEL CONSTRUCTION COMPANY, INC.
203 Chemsteel Bldg., Walnut St., Pittsburgh 32, Pa.

(No "tie-in" with any manufacturer)
Send data on your Design, Engineering & Construction Facilities for erection of
ACID-ALKALI-PROOF TANKS & FLOORING

NAME.....
COMPANY.....
ADDRESS.....
CITY.....ZONE..STATE....

CLASSIFIED

Help Wanted

TITANIUM METALLURGIST. Either experienced man or one interested in entering this field covering titanium production in mill converting to bars, forgings, sheet, strip and wire. Work will include both the technical and production aspects of material. Send information giving education, experience, age references, etc. Reply Box 330, STEEL, Penton Building, Cleveland 13, Ohio.

METALLURGIST

Steel Foundry in East desires services of graduate metallurgist with some experience in acid and basic melting procedures and sand control. Please give full particulars regarding background and salary desired in first letter. Reply Box 334, STEEL Penton Bldg., Cleveland 13, Ohio.

PLANT ENGINEER

With Electrical background for malleable iron foundry in New England. Must have had experience in supervising foundry plant maintenance. Full details will be given in personal interview. Write, giving all pertinent information to Box 335, STEEL, Penton Building, Cleveland 13, Ohio.

Employment Service

SALARIED POSITIONS $5,000 to $35,000. We offer the original personal employment service (established 45 years). Procedure of highest ethical standards is individualized to your personal requirements. Identity covered: present position protected. Ask for particulars. R. W. BIXBY, INC., 665 Brisbane Bldg., Buffalo 3, N.Y.

Positions Wanted

CHIEF MANUFACTURING ENGINEER—MASTER MECHANIC—TOOLING SUPERINTENDENT. Seeking new field. Graduate Engineer. Age 47. Specialized stampings, deep draw, progressive. Automation. Reply Box 332, STEEL, Penton Building, Cleveland 13, Ohio.

AVAILABLE
PLANT SUPERINTENDENT
STRUCTURAL STEEL FABRICATION

Have had over 30 years experience, supervising the fabrication of bridge girders, plate girders, trusses, columns, floor beams, girts, etc., required for industrial and apartment construction, either welded, riveted or bolted. Can assume full responsibility from point of mill order, details, template (wood or paper) fitting punching, layout and assembly departments. All supervision from floor of plant with the men. Have excellent experience with trade and labor. Supervised plant with average tonnage of 12,600 tons per year. Willing to move anywhere. Reply Box 326, STEEL, Penton Bldg., Cleveland 13, Ohio.

LARGE MACHINE AND WELDMENT CAPACITY

Open capacity on 24 ft. and 10 ft. Vertical Boring Mills 7", 5" and 4" Horizontal Boring Mills; large radials and supporting small machines including new 2 AC Warner & Swasey automatic chucking. Especially interested in producing weldments requiring machining.

C. H. WHEELER MANUFACTURING CO.
Sedgley Ave. at 19th & Lehigh
Philadelphia 32, Pa.
Phone: Henry Kingston—Sagamore 2-6500

EASTERN FABRICATOR OF PLATE AND STRUCTURAL STEEL IN PENNSYLVANIA-JERSEY AREA WANTS

CHIEF ENGINEER
DESIGNER - DRAFTSMAN
PURCHASING AGENT

Old established Company in phase of modernizing equipment and personnel. Excellent opportunity for experienced men in above classifications. State experience, past connections, education and positions held.

Replies Confidential

Box 329, STEEL
Penton Building Cleveland 13, Ohio

METALLURGICAL GRADUATES

Openings in mill production metallurgical group and laboratory in mill producing high speed steels, tool steels, stainless, high temperature alloys and many specialty steels. Will consider both experienced men and recent graduates interested in these fields. Reply giving details of education, experience, age, references, etc.

Address Replies to:
Personnel Department
UNIVERSAL-CYCLOPS STEEL CORPORATION
Bridgeville, Pennsylvania

MAINTENANCE ENGINEER OR GENERAL MASTER MECHANIC—Age 38 to 45 with 15 years experience in heavy Steel Plant maintenance-technical education or practical equivalent. Supervisory ability, knowledge of maintenance trades necessary. Permanent position with Eastern Penna. Steel Company. Send resume, salary expected to Box 324, **STEEL**, Penton Bldg., Cleveland 13, Ohio.

ENGINEERS WANTED

MECHANICAL ENGINEERS, DESIGNERS, CHECKERS AND DRAFTSMAN, WHO ARE QUALIFIED PERSONNEL WITH EXPERIENCE IN HEAVY EQUIPMENT ARE REQUIRED FOR WORK ON SEVERAL PROJECTS. THE EQUIPMENT BEING PROCESSED COVERS ROLLING MILLS, STEEL MILL AUXILIARY EQUIPMENT, HYDRAULIC PRESSES, MATERIAL HANDLING EQUIPMENT AND SPECIAL MACHINERY. REPLY BOX 336 STEEL, PENTON BUILDING, CLEVELAND 13, OHIO.